

Resource
Information
Display
System

USER'S GUIDE

REVISED DRAFT

March 1979
Revised October 1979



Forest Service-USDA
Washington, D.C. 20013

Revised Draft

RETURN TO GOV. DOCS. CLERK

USER'S COMMENTS

Users are requested to submit comments, questions, and recommendations concerning the RIDS User's Guide. Direct this correspondence to the address listed on the facing page.

**Resource
Information
Display
System**

USER'S GUIDE

REVISED DRAFT

March 1979
Revised October 1979



Forest Service- USDA
Attn: Engineering Computer Systems
Operation & Maintenance Group
Box 2417
Washington, D.C. 20013

Revised Draft

TABLE OF CONTENTS

SECTION A

GRID PROGRAM

I. General Information	Page
A. Identification System Name	A-1
B. Summary	A-1
1. General	A-1
2. Documentation	A-3
3. Objectives	A-3
4. Goals	A-3
5. Assumptions	A-3
II. Application	A-10
A. Introduction	A-10
B. GRID Functions and Characteristics	A-12
1. Introduction	A-12
2. Functions and Basic Features	A-12
3. System Characteristics	A-13
C. Operations Procedures	A-15
1. Run Control	A-15
2. Prototype Exec-8 Assignments	A-19
D. Demand Mode Operations	A-20
1. Demand Mode Input Procedure (DMIP)	A-21
2. Input/Output Aids	A-21
3. Terminating a Series of Statements	A-23
4. Considerations for Demand Users	A-24

III. Procedures	Page
A. Data File Development	A-24
1. Introduction to Method I and Method II	A-25
2. Determine Input Method	A-25
3. Define Study Area	A-26
a. Identify Study Area Boundary	A-26
b. Determination of Cell Size (Method I)	A-27
c. Determine grid code and sector size	A-32
(1) Sector grid system - description	A-33
(2) Sector size - description	A-37
(3) Input from P-cards	A-42
(4) Base sector grid code; change	A-43
(5) Sector computation examples	A-45
4. Map types and forms	A-51
5. Data Format	A-60
6. Data Base Drafting	A-61
a. Supplies needed to begin project	A-61
(1) Master grid	A-61
(2) Coding grid	A-61
(3) ID strips	A-61
b. Procedure for Obtaining Supplies	A-61
(1) Obtain master grid mylar	A-61
(2) Obtain code sheets	A-65
(3) Obtain ID strips	A-65

	Page
c. Development of master grid	A-65
(1) Divide grid	A-65
(2) Identify sector row/column	A-65
(3) Delineate boundary on master grid	A-66
(4) Obtain copy of grid for each topic	A-66
d. Coding Values	A-66
e. Prepare code sheet for keypunching	A-66
(1) Divide sector in half	A-66
(2) Attach ID strip - rows	A-67
(3) Attach ID strip - columns	A-67
(4) Record values - FORTRAN coding form	A-68
(5) Key punch cards	A-70
(6) Caution Note	A-71
B. Input Forms	A-71
1. General	A-71
2. Initial Run-Passive	A-72
3. Verification Run-Passive	A-76
4. Create Initial File-Active	A-77
5. Adding New Topics	A-81
C. Data Manipulation - GRID	A-82
1. Summary	A-82
2. Data Display	A-83
a. General	A-83
(1) Single character	A-83
(2) Grey Scale	A-83
(3) Geographic topic outline	A-83
(4) Selective display (window)	A-83

	Page
b. Map Generation	A-83
(1) Print six or eight lines p/inch	A-83
(2) Overprint characters	A-84
(3) Produce statistical reports	A-84
(4) Slow speed terminals	A-84
3. Data Mapping Options	A-84
a. Single topic display	A-85
b. Intersection	A-97
c. Linear combination	A-103
d. Window display	A-111
e. Text overlay	A-115
IV. Cost Analysis	A-118

TABLE OF CONTENTS

SECTION C

I. Data Sources Acceptable to GRID	Page
A. General Information	C-1
B. Digitized Features	C-3
C. Attributes	C-4
II. Structure of GRID standard files	C-5
III. Processing "COMLUP-FORMATTED" data	C-7
A. Runstream for Tape Input	C-7
B. Runstream for Card Image Input	C-8
C. Error Messages	C-9
D. GRID Runstream	C-9

SECTION D
PROCESSING POLYGON DIGITIZED DATA
IN GRID SYSTEM

I. General Information	Page D-3
A. Overview	D-3
B. Operating Procedure	D-4
1. Digitize Polygons	D-4
2. Transmit Data to FCCC	D-5
3. Execute RID*PLOT.EDIT	D-6
4. Execute RID*PLOT.PLOT	D-8
5. Save Output File	D-8
6. Execute RID*GRID.PREPRC/PLOT	D-10
a. Step 1 - Create Runstream	D-10
b. Step 2 - Start Runstream	D-11
7. Execute RID*GRID.GRID (Passive Mode)	D-11
a. Step 1 - Create Runstream	D-11
b. Step 2 - Start Runstream	D-14
8. Execute RID*GRID.GRID (Active Mode)	D-14
9. Data Manipulation	D-14
II. Cost Analysis	D-16

SECTION E
SLOPE AND ASPECT MAPS

	PAGE
I. OVERVIEW	E-1
II. DESCRIPTION	E-4
1. Note	E-4
2. DMA Data Tapes	E-4
3. Execute .COPYNCIC	E-4
4. Save Output	E-4
5. Execute .PRINT	E-9
6. Execute .SCANDMA	E-12
7. Execute .SLOPE	E-15
8. Execute .ZONEIT	E-16
9. Execute Conversion Program RID*GRID.GELCOM	E-23
10. Execute Preprocessor RID*GRID.PREPRC/COMLUP	E-23
11. Sample Outputs of Map File Through RID*GRID.GRID Program	E-28
III. Cost Analysis	E-37

EXHIBITS

EXHIBIT	DESCRIPTION	PAGE
A1	Grid Layout, Row and Column	A-2
A2	Grid Mapping System Process (4 Parts)	A-5-7
A3	Grid System Flow Chart (2 Parts)	A-8-9
A4	Demand/Batch Modes of Grid System Flow (2 Parts)	A-16-17
A5	Sample Demand Run Intersection Display	A-22
A6	Sector Grid System	A-33
A7	Grid Code Level - 1 (Sector Size 3.75 x 3.75)	A-34
A8	Grid Code Level - 2 (Sector Size 7.50 x 7.50)	A-34
A9	Grid Codes and Corresponding Sector Sizes	A-35-36
A10	Sector Grid Numbering (Sector Size 15.00 x 15.00)	A-38
A11	Sector Subdivision - Elements	A-39
A12	Sample Problem - Method I	A-46-48
A13	Grid Map Types	A-52
A14	Alpha Conformal Topic Map	A-57
A15	Numeric Conformal Topic Map - Grey Tone	A-58
A16	Numeric Continuous Topic Map - Grey Tone	A-59
A17	Sample Coding Form	A-69

EXHIBITS (Continued)

EXHIBIT	DESCRIPTION	PAGE
A18	Sample Runstream - Passive With Output (2 Parts)	A-74-75
A19	Sample Verification Run - Passive With Output (3 Parts)	A-77-79
A20	Sample Output Create Initial File - Active	A-80
A21	Sample Output - Single Display With Boundaries Printed Solid (3 Parts)	A-88-90
A22	Sample Output - Single Display Without Boundaries (2 Parts)	A-91-92
A23	Sample Output - Single Display With Boundary Only (2 Parts)	A-93-94
A24	Sample Output - Single Display With Boundary as Drop Out (2 parts)	A-95-96
A25	Single Intersection Display (4 Parts)	A-99-102
A26	Runstream for Recoding Linear Combi- nation and Obtaining Output Linear Combination - Numeric Map Display (2 Parts)	A-107-109
A27	Linear Combination - Grey Scale Display	A-110
A28	Window Display Sample (2 Parts)	A-113-114
A29	Text Overlay (2 Parts)	A-116-117

EXHIBITS (Continued)

EXHIBIT	DESCRIPTION	PAGE
D1	Runstream - Transmit Data to FCCC (Sample Output)	D-7
D2	Runstream - RID*PLOT.PLOT (Sample Output)	D-9
D3	Runstream - RID*GRID. PREPRC/PLOT (Sample Output)	D-1
D4	Runstream - RID*GRID.GRID (Coding Form)	D-1
D5	Runstream - RID*GRID.GRID (Sample Output)	D-1

EXHIBITS (Continued)

EXHIBIT	DESCRIPTION	PAGE
E1	Topographic Analysis System (TOPAS)	E-5
E2	DMA Tapes Selection Program (2 Parts)	E-6-8
E3	.PRINT Output (2 Parts)	E-10-11
E4	.SCANDMA Output (2 Parts)	E-13-14
E5	.SLOPE Output (2 Parts)	E-18-19
E6	.ZONEIT Output (3 Parts)	E-20-22
E7	RID*GRID.GELCOM Output (2 Parts)	E-24-25
E8	RID*GRID.PREPRC/COMLUP Output (2 Parts)	E-26-27
E9	Sample Input to Obtain Output Display and Create Map File (2 Parts)	E-29-30
E10	Sample Input to Obtain Single Topic Display (Demand Mode) - Passive Run	E-31
E11	Sample Input to Obtain Grey Scale Display (3 Parts)	E-32-35
E12	Topographic Map of .GRID Output	E-36

APPENDIX A
INPUT FORMS *

CARD	DESCRIPTION	PAGE
	REFERENCE CARD	A-REF-
A Card	Mapping Request	A-A-1
	Requester, Organization	A-1
	Transactions, Passive, Active	A-2
	Special Subset Units	A-3
	No Input Map File	A-4
	Map File Name	A-5
B Card	Dictionary Definition	A-B-1
	Grid Code, Dictionary Name	B-1
	Noncontiguous Search Factor	B-2
	Area Pointer Representation	B-3
	Aggregate Area Suffices	B-3
C Card	Area Identification	A-C-1
	Area Code	C-1
	Area Symbol, Pointer	C-2
	Pointer Representations	C-5
	Area Name	C-6
	Aggregate Area Symbols	C-6

* NOTE: A, G, H, I, J, K, P, R, S, T, V, W, Y, Z are the only input forms available in Demand Mode. All forms available in Batch.

CARD	DESCRIPTION	PAGE
D and E Card	External Data	A-D-1
	Introduction	D-1
D Card	File Description	A-D-2
	External File Name	D-2
	File Type Selection	D-2
	01 FORTRAN I/O Formatted	D-2
	02 FMPS Files	D-3
	03 GIM Data Base	D-4
	04 ERTS Imagery	D-4
	05 F-Cards Data Only	D-4
	06 "USER" Data	D-4
	07 GIRAS Files	D-6
	08 CENSUS (digitized)	D-17
	09 COMLUPS Formatted Tapes	D-17
	10 F-Cards (data and digitized)	D-17
	11 "OTHER" Digitized Data Bases	D-17
	12 PLOT Formatted Tapes (digitized)	D-24
	Dictionary	D-25
	Clipping Coordinates	D-
E Card	Field Labels and Format	
	Field Label	
	Format	

CARD	DESCRIPTION	PAGE
F Card	Inputting External Data on Cards	A-F-1
	Feature Type (Digitized Features)	F-1
	Data Fields	F-1
G Card	Topic Definition	A-G-1
	Grid Code	G-1
	Map Name	G-2
	Sector Size Reduction	G-2
	Number Down	G-4
	Sector Row and Column	G-4
	Element Row and Column	G-4
H Card	Text Overlay	A-H-1
	Row and Column	H-1
	Length, Text	H-1
I Card	Title	A-I-1
J Card	Scale	A-J-1
	Category Name	J-1
	Assigned Symbol and Thresholds	J-1
K Card	Topic Generation by Symbol Conversion	A-K-1
	Reference Topic, Mask	K-1
	Symbol Conversions	K-1
L Card	Omitted	
M Card	Omitted	

CARD	DESCRIPTION	PAGE
N Card	Topic Generation by Dictionary Symbol Conversion	A-N-1
	Reference Dictionary	N-1
	Symbol	N-1
	Value	N-2
O Card	Generation by Points or Lines	A-O-1
	Formula Number	O-1
	Global Dispersion	O-1
	Convergence Limit	O-2
	Reference Sector	O-2
	Point/Line Coordinates	O-2
	Local Dispersion	O-3
	Values	O-4
P Card	Generation by Element Matrix	A-P-1
	Row Number	P-2
	Print Positions	P-2
Q Card	Generation by External Data	A-Q-1
	Reference Field Label	Q-1
	Digitized Data Indicator	Q-2
	Proximity, Radius and Accessibility	Q-2
	Internal Composition Rule	Q-2
	LP Model Number	Q-3
	No Scaling Required	Q-3
	Mask Symbol	Q-3
	Auto-Scaling and Number of Intervals	Q-4
	Reference-Accept Label, Value	Q-5

CARD	DESCRIPTION	PAGE
R Card	Map Composition	A-R-1
	R-Expressions, Conditional and Arithmetic	R-1
	Examples	R-1
	Literal Values in R-Expressions	R-3
	Data Types	R-3
	NULL	R-4
	Transfer Function	R-4
	Language Elements--Operators Connectives and Functions	R-5
	Description of Grammar	R-5
	Statistics	A-S-1
S, T and U Cards	Introduction	S-1
	Report Title	S-1
T Card	Statistic Parameters	A-T-1
	Type	T-1
	No Graph	T-2
	Limit Value for Stepwise Regressions	T-2
	Dependent of Multivariate Histogram Topic	T-2
	Starting Point	T-3
	Masking Topic	T-3
	Masking Symbol	T-3
	Excluded Symbols	T-4
U Card	Independent Map Topics in MR or SR	A-U-1
	Independent Topic Names	U-1
	Force (Entrance into SR)	U-1

CARD	DESCRIPTION	PAGE
V Card	Study Area Legend	A-V-1
W Card	Windowing Map Display	A-W-1
	Sector Position	W-1
	Element Position	W-1
	Number of Rows and Columns in Window	W-1
	Grey Tone	W-1
	Display Symbol Conversion	W-2
X Card	Precedence Table	A-X-1
	Precedence Ordering, Single Characters	X-1
Y Card	Change Overprint Combinations	A-Y-1
Z Card	Map Display	A-Z-1
	Boundary Overlay Topic	Z-1
	Overlay Topic Symbols	Z-1
	Base Topic Symbols	Z-2
	Grey Tone for Numeric Maps	Z-2
	Mask Symbol	Z-3
	Auto translation	Z-3
	Display Symbol Conversion	Z-4
	Multiple Overlay Boundaries	Z-5
\$ Card	CSF\$ Requests	A-\$-1
	Text	\$-1
	APPENDIX B -- PROGRAM MESSAGES	
	Edit Phase Messages	B-1
	Processing Phase Messages	B-23
	Map-File Generation Messages	B-30
	Run Stop (Fatal) Messages	B-31

SECTION A
USER GUIDE

I. GENERAL INFORMATION

A. Identification System Name: Resource Information Display,
GRID (RID*GRID)

Location: FCCC

Language: FORTRAN

B. Summary


1. General

GRID is designed to provide an efficient means for storage and graphic display of large quantities of land use information collected on the basis of a grid made up of square or rectangular cells of a specified area. Cells are located by their row and column positions (See Exhibit A1).

GRID is also able to handle polygon digitized data that can be converted to a grid format using a preprocessor (See Section "C & D").

The data displayed by GRID can be used for:

- ° Identifying areas suitable and/or desirable for specific uses or management practices.
- ° Developing alternatives.
- ° Testing alternatives.
- ° Identifying areas where resource or use conflicts exist or have potential for occurring.



		C O L U M N S									
		1	2	3	4	5	6	7	8	9	10
R O W S	1	cell 1,1	cell 1,2								
	2	cell 2,1									
	3						cell 3,6				
	4							cell 4,7			
	5										cell 5,10

11.--Grid layout, row and column

2. Documentation

This documentation will cover development of the computerized data base, editing and maintaining the data base, generation of new variables in the data base, and obtaining the following graphic displays: (1) single display, (2) intersection, (3) linear combinations, (4) window display (see Exhibits A2 and A3).

3. Objectives

- a. Provide a computer tool for fast and efficient data manipulation and mapping.
- b. Provide system for preserving spatial information.
- c. Provide user instructions that can be understood by non-programmers and easily and efficiently applied by field units.
- d. Provide sufficient general documentation for Service-wide application.
- e. Provide graphic examples for easy interpretation of program features.
- f. Build user confidence in using a computer mapping system.

4. Goals

After reading this documentation users will be able to:

- a. Develop data bases.
- b. Edit and maintain existing data bases.
- c. Generate displays from data bases.

5. Assumptions

Users have access to a demand terminal for demand operation and facilities for batch mode operations.

GRID MAPPING SYSTEM

DETERMINE INPUT METHOD

- 7.5' Quad as one sector

DEFINE STUDY AREA

- Identify Study Area Boundary
- Determine cell size (Method I)
- Determine Grid Code and Sector Size

DATA FORMAT

- Topic and Values
- Clean Data

DATA BASE DRAFTING

- Supplies needed
- Procedures for obtaining supplies
 - Development of Master Grid
 - Coding Values
- Prepare Code sheet for Key punching

INPUT FORMS

- Initial Run - Passive
- Verification Run - Passive
- Create initial File-Active
 - Adding new topics


DATA MANIPULATION

- Single Character
- Gray Scale (numeric map only)
 - Geographic Topic Outline
 - Selective Area (window)

DATA MAPPING OPTIONS


- Single Topic
- Intersection
- Linear Combination
 - Window

*ibit A2.--Grid mapping system process
(Part 1 of 4)*



FLOW CHART FOR RUNNING GRID (1)

Exhibit A2.--Flow chart for running grid
(Part 2 of 4)



A2.--Flow chart for running grid
(Part 3 of 4)




Exhibit A2.--Flow chart for running grid
(Part 4 of 4)




Exhibit A3.--Grid system flow chart
(Part 1 of 2)

GRID SYSTEM CREATE AND MANIPULATE MAP FILES




Exhibit A3.--Grid system flow chart
(Part 2 of 2)

II. APPLICATION

A. Introduction

The program RID*GRID is a FORTRAN Program to store, retrieve, manipulate, and combine information that has an on-the-ground relationship. The program features:

- An ability to display a single topic from combining layers of resource and physical data such as soils, topography, vegetation, etc.
- A fully labeled line-printer map display with quantitative output such as statistical area summaries and histograms.
- A geographic base system of which the data base is keyed latitude and longitude map coordinates. This facilitates the registration and location of the output map.
- Topic maps can be created using linear combinations.

Map generation can be generated and printed at the Forest computer terminal or generated and printed on the line printer in the Regional Office. Turnaround time will depend on processing priority and mailing. As mentioned in the section on data base development, line printer characters occupy a rectangular area 1/10" wide by 1/8" high. The line printer has the capability to:

- (1) Print six or eight lines per inch depending on the desired map scale (see Exhibit A9 under data base development).
- (2) Overprint characters to obtain desired grey scale shades.
- (3) Produce statistical reports; user can suppress the map output and obtain statistical outputs only if requested.

(4) Slow speed terminals such as demand terminals are not suitable for large map display requests and are not always capable of producing overstrike characters to produce a grey output map.

GRID is a generalized system which is user-oriented and open-ended for future expansion. "User-oriented" refers to the ability to operate the system without the need for a programmer, and "open-ended" refers to the structuring of the GRID logic such that additional features can be incorporated without extensive reprogramming. For illustration purposes the following display mapping options will be discussed.

-- Single topic display

- 1) Cell data only without geographic boundary outline
- 2) Cell data with boundary printed solid
- 3) Cell data with boundary outline dropped out
- 4) Geographic boundary outline only

-- Intersection

- 1) Alpha output

-- Linear combination

- 1) Numeric output
- 2) Grey scale

-- Window display

- 1) With geographic boundary outline
- 2) Cell data only

-- Text Overlay

B. GRID Function and Characteristics

1. Introduction

The Resource Information Display System (RIDS) described here is an attempt to refine a portion of the data-handling needs of planners to facilitate further understanding of the factors contributing to environmental planning. It is hoped that through techniques such as this, significant progress can be made toward optimum problem solutions.

The relatively low cost of computer processing for this technique made it attractive to the Forest Service as a potential planning tool. During the past two years some additions have been introduced into the original program to simplify its use in Forest Service applications while retaining all its original capabilities.

2. Functions and Basic Features

The purpose of the system is to store, retrieve, manipulate, and combine planning area information. It was designed to meet S&PF, Area Planning and Development, needs related to cooperative studies. These studies encompass broad areas, sometimes involving several States, and include: river basin studies, multi-county and State land use planning, 208 planning as part of PL92-500, Wild

River Studies, and Coastal Zone Management.

de its use in other Forest Service

The ways the system has been used to

date by the Forest Service include: combining layers of resource and physical data such as soils, topography, vegetation, etc., to determine land capabilities.

In addition the system will provide quantitative output such as statistical area summaries and histograms.

GRID is a geographic base system, that is, the data base is keyed to latitude and longitude map coordinates which facilitates the registration and location of the output map.

3. System Characteristics

Characteristics of the GRID system are similar to other cellular systems. There are, however, some unique characteristics that need to be highlighted.

The system has the capability for weighting cell information. In most cell systems a given cell is coded to reflect the predominant feature within the cell. To manipulate cell data with the GRID system it is possible to assign values to a cell to be multiplied, added, subtracted, divided, or used relationally with operators such as "equal to" (=), "less than" (<), and "greater than" (>). The weighted information can be printed to appear as shades of gray or a unique output character. Shading is accomplished by symbol selection and overprinting.

A system limitation is the number of levels (i.e. each timber type is a level, soil type is a level, etc.) that can be used for data output. The GRID system has 44

levels. This means that complex maps such as timber type would usually require more than one computer printout to display all levels.

The assignment of grid cells to specific levels may be accomplished in one of two ways; (1) for map layers with descriptive codes, (Timber, Ecological Land Types, Political) the user may specify which codes are to be associated with what level. (2) For map layers representing quantitative data, (SLOPE 0-10%), the user may specify the ranges of values to be assigned to the various levels; the GRID program will then compute the proper level for each grid cell. Input selection criteria is specified by the user. Consequently, this system afford greater flexibility for characterization of land inventory than other grid mapping systems.

Combination of multiple map layers (area intersections) in this system is a one-step operation. A maximum of ten (10) layers may be combined at one time.

There are two options for output maps. (1) Numeric maps can be displayed in shades of gray or single character output at 6 or 8 lines per inch on output printer, (2) other maps are displayed with single character map output.

following features are also available in the RID System and are discussed in APPENDIX "A" of the RID User's Guide obtaining Multivariate Histograms, Multivariate Frequency, Multiple Linear Regressions and Stepwise Regression. The system will also enable planners to perform optimization or simulation analysis and to produce maps and data graphics of the solution in various alphanumeric formats. A mathematical programming model is used for spatial optimization analysis.

C. Operating Procedures


The GRID Program executes under the Univac Exec-8 operating system at FCCC. GRID requires certain standard control cards to be present both before and after the actual GRID request deck to communicate with the Exec-8 system.

This section provides for run set-up procedures and describes the required control cards.

It should be noted that the information in this manual is intended for use by persons who have a fundamental knowledge of the operational requirements of the Univac 1100 Exec-8 system.

1. Run Control

Exhibit A4 is a macro flow chart which shows the input/output characteristics of GRID for Demand Operation and for Batch Mode Operations.



*d mode of grid system flow
rt 1 of 2)*




Exhibit A4.--Batch mode of grid system flow
(Part 2 of 2)

Executions of GRID may be classified as either active or passive. Active Participation (runs) implements some change on the GRID System Map File and requires an output tape to be assigned. Passive Participation (runs) indicates that the Map File is not physically affected, only monitored.

For a systematical construction of the Map File there should always exist a data tape for backup to protect against a hardware or software error. For example, a suggested Input/Output Cycle (see below) could be as follows: Run #1 creates the initial output map file on Unit 9. Run #2 takes this output file from Run #1 as input on Unit 7. Then the output of Run #2 is used as input for Run #3. Note that the Input File of Run #2 is saved as the backup map file. Thus, there will be two reels of tapes used for every active GRID run, an input map file used for tape Unit 7, an output map file used for tape Unit 9, and one reel as backup from the previous run.

RUN NUMBER	INPUT MAP FILE Unit 7	OUTPUT MAP FILE Unit 9	BACKUP MAP FILE
1	--	TAPE 1	--
2	TAPE 1	TAPE 2	--
3	TAPE 2	TAPE 3	TAPE 1

Approximately 2700 Alpha Maps * or 900 master maps ** can
be stored on a standard reel of computer magnetic tape

* Alpha Maps are used to describe a geographic area in terms of
single characteristics. P/cell, i.e., soil type A.

** Master Maps are alpha maps used to describe a geographical area in
terms of three characteristics P/cell, i.e., A13; A = Soil Type,
1 = Slope, 3 = Ranger District. The characters 1 and 3 must be
added using "R cards." See APPENDIX "A" for additional
information.

(2000, if the tape is 1600 bpi). If we assume that the
average study area contains 12 sectors, then approximately
225 alpha or 83 master maps could be stored for all
sectors within this area on one reel of tape.

2. Prototype Exec-8 Assignments

@ASG,A RID*GRID RIDS program file

@ASG,T 7.,U9V,File Name,Tape Number Input map-file

@ASG,T 9,U9V,File Name Output map-file

(for "ACTIVE" runs)

Any of the above files (Input/Output Cycle) may alternatively be assigned to catalogued files on mass storage, with @USE name relationships established. Internal file names are indicated on the appropriate GRID control cards; they are all single character names.

In compliance with installation operations policy, it may be necessary to precede output tape assignments with a write-ring message:

@MSG RING IN reel#

. Demand Mode Operation

GRID may be executed in either DEMAND or BATCH mode. Each has its advantages. For example, BATCH runs are far less expensive; but in DEMAND mode, the user has the advantages of immediate feedback and recovery from errors which would inhibit a BATCH run from executing. As a result of the file size restriction (50K) imposed by FCCC in March 1978, for demand runs, a modified version of the standard GRID program was prepared for demand use only. The program is called GRID*GRID.DGRID. The following data manipulation options are available in a demand mode of operation; single topic display, intersection with alpha outputs, linear combinations with numeric output and gray scale window display of selected areas. Statistics are also displayed with the above options.

See Appendix "A" for a complete description of these mapping options.

1. Demand Mode Input Procedure (DMIP)

The input procedure performs several functions: To prompt the user for the next control card, to display control card patterns and column enumerations to allow recovery in case of detected errors. (See Exhibit A5.)

2. Input/Output Aids

After the user, in response to the prompt, has entered his control card character, e.g., ('G' for G-card, etc.), DMIP displays a pattern which marks off the fields of that control card. This is to facilitate the entrance of data. Most of GRID's control cards are fixed-field format and column positioning is critical. In addition to the pattern, the user may at any time request a column enumeration by typing the command; SCALE.

Many of GRID's control cards can appear in multiples--G, H, I, J, P, R, S, Z. After the user has typed several of a given card, the pattern may be quite remote with respect to his current line. If the user desires another pattern, he may type the command, PATTERN~~n~~n, where n is the control card letter.

3. Terminating a Series of Statements

When the user has finished entering a series of (multiple) images, he types the command, EXIT, which causes his statement to be executed. He then receives another prompt from the DMIP.

In DEMAND mode, DGRID immediately analyzes all control cards (in BATCH, some analysis is deferred until the processing phase). If errors are detected, the system issues diagnostics and the statement just entered is voided. If errors are found on card which can appear only as singletons--A, K, T, V, W, Y, \$--the user is returned to the top level of the DMIP which prompts him for another card. Singleton statements without errors are interpreted and executed as they are entered.

If the user hits a line-delete character (usually CTRL-X), his next input line will be offset from his pattern and/or scale. DMIP scans each line entered for its own line delete, '?'. If it discovers a '?' then the line is ignored, but a prompt character will appear at the terminal thereby preserving alignment.

The following feature applies to R-card only. Should the user decide to cancel a whole sequence of the same type card he may type, ABORT, which cancels the transaction and returns him to the top level of the DMIP.

4. Considerations for Demand Users

Since demand processing time is billed at a higher rate than BATCH, it would be prudent not to execute large time consuming tasks in GRID from a terminal.

Since a considerable volume of output would be produced if an entire map is displayed, the demand user is advised to use the windowing card (W-card) to examine his maps at the terminal. The user also has the opportunity to redirect his printed output to an alternate device (via @SYM PRINT\$, , device). DGRID will query the user about redirection of output if he asks to display more than one sector.

Occasionally the user may wish to "@ADD" previously created files or elements into his GRID runstream.

Normally, images entered at the terminal by an @ADD statement would not be echoed, but since errors may exist in the @ADD'ed text, it may sometimes be desirable to have the statements printed. The user may cause statements to be echoed by typing, ECHO~~ON~~ON, and terminate it with ECHO~~OFF~~OFF.

. PROCEDURES

A. Data File Development

The following outline provides instructions for preparation

data to be processed by the GRID program. The use of a USGS 7.5 minute quadrangle sheet, scale 1:24,000 is used throughout this example. This does not mean to imply that other scales cannot be used.

1. Introduction to Method I

Method I is used if a 1:1 input relationship between a given map sheet and one sector is desired, i.e., one 7.5 minute USGS quadrangle sheet to represent one sector.


— — — — Portion of page deleted

METHOD I

Input by 7.5 minute quad using one sector.

This is the most accurate method of preparing your data base for coding, manipulation and output. The features of this method are: (See page 26)

- Accurate statistics
- Geographic referenced output
- Data manipulation of adjoining sheets
- No reference card needed
- Compute sector row/column only for input
- Output of adjoining sheets at one time
- Output not at 1:1
- Quad sheet divided into 120 rows by 120 columns
- Each cell approximately 2.5 acres @ 1:24,000
- A separate coding grid is constructed for each quad sheet



--- Portion of page deleted

3. Define the Study Area

a. Identify Study Area Boundary

(Continued on page A-27)

METHOD I

- (1) Decide on map scale to be used throughout data collection and study area boundaries. Boundaries may coincide with previously established boundaries, e.g., unit planning boundary, wilderness boundary, or Forest boundary.
- (2) Delineate boundary on map of same scale to be used throughout data collection. This may be a USGS quad sheet at 1" = 2000' or a reduced Forest map at 2" = 1 mile, etc.
- (3) Identify geographic coordinates, latitude and longitude values of study area limits or sheet corners.

b. Determination of Cell Size.


METHOD I


The cell size for input using Method I is determined by a program--RID*GRID.GRIDDER (See Paragraph 6, Page 61).


When the geographic corner values of your quad sheet are input, a plot tape will be created that will produce a grid 120 rows by 120 columns for the entire quad sheet.

For example, a 1:24,000 scale map the grid cell size will represent approximately 2.5 acres.

____ Remainder of page deleted







c. Determine Grid Code and Sector Size

When large study areas consist of many quad sheets it becomes necessary to divide the area either by quads (METHOD I)

Each map sector has an associated geographic reference. This geographic reference or sector identification is used for identifying adjacent map sectors when maps requiring portions of two or more sectors are requested.

Once the study area and the associated sectors have been defined, each sector is mapped with GRID on a grid which is 120 columns wide and 120 rows high. An element of a map corresponds to one grid position within the sector. Since a sector is comprised of 120 rows and 120 columns, there are 14,400 elements per sector. The number of elements within a sector remains constant regardless of the mapping scale selected.

All map sectors are relative to a base latitude and longitude--that being latitude 53 N and longitude 128 W. With this origin the entire contiguous United States can be mapped. However, this base can be altered to suit the needs of the user (See Paragraph (2) and (4) of this section). The reference point is used in creating maps from digitized data sector rows and columns are computed according to the reference coordinates and the grid code. Maps participating in a composition must have been created relative to the same reference.

1) Sector Grid System -- Description

Maps produced by GRID are composed of areas called map sectors. The size of each sector is the product of the grid code level and the base sector size. The base sector has a default size of 3.75 by 3.75 minutes of arc. Thus, if the grid code level is given as 2, then the sector size is 7.50 by 7.50 minutes of arc (see Exhibit A9). Each sector is referenced by sector row and sector column numbers. Rows are numbered from top to bottom and columns are numbered from left to right (see Exhibit A6). For the GRID system the northern edge of the sector grid system is at 53 degrees north latitude; the western edge is at 128 degrees west longitude. Exhibits A7 and A8 illustrate the sector grid numbering convention for grid codes of 1 and 2 respectively. The southernmost sector row that can be referenced is 999; likewise, the easternmost column is 999.




Exhibit A6.--Sector grid system





Exhibit 7.--Grid code level-1 (sector size 3.75 x 3.75)



bit A8.--Grid code level-2 (sector size 7.50 x 7.50)

Grid Code Level	Sector Size	Default Base Sector
001	(1/16 Deg)	3.75 Min.
002	(1/8 Deg)	7.50 Min.
003		11.25 Min.
004	(1/4 Deg)	15.00 Min.
005		18.75 Min.
006		22.50 Min.
008	(1/2 Deg)	30.00 Min.
010		37.50 Min.
012		45.00 Min.
015		56.25 Min.
016	1 Deg	0.00 Min.
018	1 Deg	7.50 Min.
020	1 Deg	15.00 Min.
024	1 Deg	30.00 Min.
025	1 Deg	33.75 Min.
030	1 Deg	52.50 Min.
032	2 Deg	0.00 Min.
036	2 Deg	15.00 Min.
040	2 Deg	30.00 Min.
045	2 Deg	48.75 Min.
048	3 Deg	0.00 Min.
050	3 Deg	7.50 Min.
054	3 Deg	22.50 Min.
060	3 Deg	45.00 Min.
064	4 Deg	0.00 Min.
072	4 Deg	30.00 Min.
075	4 Deg	41.25 Min.

Exhibit A9.--Grid codes and corresponding sector sizes for line printer output 6 or 8 lines per inch

Grid Code Level	Sector Size	Default Base Sector
080	5 Deg	0.00 Min.
081	5 Deg	3.75 Min.
090	5 Deg	37.50 Min.
096	6 Deg	0.00 Min.
100	6 Deg	15.00 Min.
108	6 Deg	45.00 Min.
120	7 Deg	30.00 Min.
125	7 Deg	48.75 Min.
128	8 Deg	0.00 Min.
135	8 Deg	26.25 Min.
144	9 Deg	0.00 Min.
150	9 Deg	22.50 Min.
160	10 Deg	0.00 Min.
162	10 Deg	7.50 Min.
180	11 Deg	15.00 Min.
192	12 Deg	0.00 Min.
200	12 Deg	30.00 Min.
216	13 Deg	30.00 Min.
222	13 Deg	52.5 Min.
240	15 Deg	0.00 Min.
480	30 Deg	0.00 Min.

*Exhibit A9.--Grid codes and corresponding sector sizes for Z
printer output 6 or 8 lines per inch (continued)*


2) Sector Size

METHOD I

The sector size is identical to the quad size that is being used to code the data. That is, a quadrangle is evenly divided into 120 rows by 120 columns to form a single sector covering the entire quad.

— — — — Remainder of page deleted

SECTOR SIZE CHANGE ILLUSTRATED



SECTOR GRID NUMBERING

GRID CODE LEVEL = 1

BASE SECTOR SIZE = 15 min x 15 min

ORIGIN = 43° N LAT BY 115° WEST LONG

Exhibit A10.--Sector grid numbering (sector size 15.00 x 15

METHOD I

Each sector is subdivided into rectangular cells called elements. There are 120 element columns across each sector. The number of element rows down each sector is either 120 or 90 depending on whether the lines per inch subfield of the grid code is specified as 8 or 6 respectively. This arrangement allows a map sector consisting of 14400 or 10800 elements respectively, to be displayed as an array of characters on a line printer (Exhibit A11). The sectors can then be taped together to form a complete map.




Exhibit A11.--Sector subdivision - elements

Although the specified sector size of a map does not effect the scale of the output map, it controls the area calculations for the map. Establishing the correct sector size is, therefore, necessary in order to obtain correct area statistics from GRID.

METHOD I

When using this method to input your cell data into the GRID system you are utilizing the system as it was designed. That is, to use the geographic reference system and the Grid Codes available in GRID (see Exhibit A9).

____ Remainder of page deleted

3) Input From P-Cards

P-Cards are used to generate an element matrix for input to GRID. That is, each cell within a sector must be accounted for by a single character entry on the P-Card. See Appendix A for a complete description of the P-Card.

If the map is input from P-Cards then the scale of the output map depends on the scale of the source map, the mesh size of the grid that will be used to hand code the P-Cards, and the printing characteristics of the line printer on which the output map is displayed. Therefore, the following relationship exists:

$$\text{X-direction} \quad SX = CX/(GX*PX) \quad (\text{Equation } 3)$$

$$\text{Y-direction} \quad SY = CY/(GY*PY) \quad (\text{Equation } 4)$$

Where:

CX . . The scale of the source map in the x-direction

GX . . The mesh size of the grid in the x-direction

PX . . The number of characters per inch printed in the x-direction

SX . . The scale of the output map in the x-direction

Suppose for example, that the source map has a scale of 1:24,000, that the mesh size of the grid is 0.1 in the x-width by 0.125 in the y-height and that a line printer produces pages which have 10 characters per inch across and 8 characters per inch down.

Then we have:

$$CX = 24000$$

$$CY = 24000$$

$$GX = 0.10$$

$$GY = 0.125$$

$$PX = 10$$


$$PY = 8$$

and so substituting in equations (1) and (2),

$$SX = 24000 / (0.10 * 10) = 24000$$

$$SY = 24000 / (0.125 * 8) = 24000$$

The output map will therefore have a scale of 1:24,000.



4) Base Sector Grid Code Change, (Batch Mode Only)

A user may want to change the origin of his data from the systems default of latitude 53°N and longitude 128°W. An example would be if a Forest desires to have the sector row/

To change these entries, input a REFERENCE Card with the following information at the beginning of the runstream:

Columns 1 through 9 REFERENCE

Columns 11 through 20 Extent in the x direction (longitude),
(BX in ex. 7.223) expressed in minutes-per-sector of the
base sector. (Grid code 1). Decimal
point must be entered.

Columns 21 through 30 Extent in the y direction (latitude),
(BY in ex. 6.533) expressed in minutes-per-sector of the
base sector. Decimal point must be
entered.

Columns 31 through 40 The reference latitude in decimal
(44°05'00" = 44.0833) degrees. Decimal point must be
entered.

Columns 41 through 50 The reference longitude decimal
(71°25'00" = 71.4166) degrees. Decimal point must be
entered.

1	9	11	20	21	30	31	40	41	50
REFERENCE	7.223	6.533	44.0833	71.4166					

NOTE: The following procedure is used to determine how many acres will be represented by each cell either for input to GRID or as an output of GRID.

Determine acres per cell

Given:

Cell Dimensions

Square feet per acre 43560

Map scale 1/24000

Output printer character dimensions in inches

SAMPLE PROBLEM

a) $X = 24000/10 = 2400$ inches per cell in x

$Y = 24000/6 = 4000$ inches per cell in y

b) Convert inches to feet for both x and y

$x = 2400 \div 12 = 200$ feet


$y = 4000 \div 12 = 333.33$ feet

c) Convert to square feet per cell

$200 \times 333.33 = 66666.7$

d) Convert to acres per cell

$66666.7 \div 43560 = 1.53$ acres per cell



OUTPUT PRINTER
CHARACTER DIMENSIONS
IN INCHES

5) Sector Computation Examples

The following sample problem describes the procedure used in METHOD 1 (see Exhibit A12) to calculate sector row--column values for input into GRID. This example shows how to convert geographic coordinates to GRID sector row--column.

GIVEN:

--Input map sheet--7.5' quad

--Scale = 1:24000

--Input map size is equal to one
sector

a -- Determine Sheet Size:

Measure x and y of map sheet in inches:

Example x = 17.5 inches

y = 22.0 inches

b -- Sector Size of Map in Minutes

x = 7.5 minutes

y = 7.5 minutes

c -- Determine Degrees Per Sector in Longitude (x) and Latitude (y)

Given: Minutes per degree = 60

1) Compute degrees per sector longitude

Degrees p/sector long. = $\frac{\text{sector size in minutes}}{\text{minutes per degree}}$

$$DX = \frac{7.5}{60} = 0.125 \text{ degree per sector}$$

2) Compute degrees per sector latitude

$$DY = \frac{7.5}{60} = 0.125 \text{ degree per sector}$$

Exhibit A12.--Sample problem - Method I

d -- Determine Sector Row/Column Locations of NW Corner of Input Map Sheet

- Given:
- Base sector longitude = 128°
 - Base sector latitude = 53°
 - Geographic value (in degrees) of NW corner of input map
 - 71.417 longitude*
 - 44.083 latitude*
 - Degrees per sector in longitude
 - $DX = 0.125$
 - Degrees per sector in latitude
 - $DY = 0.125$

Compute location of sector column/row

$$\text{Sector column} = \frac{\text{base sector long.} - \text{long. input map}}{\text{degree per sector longitude}}$$

$$C = \frac{128^{\circ} - 71.417}{.125} = 452.664$$

Repeat computation for row (latitude)

$$R = \frac{53^{\circ} - 44.083}{.125} = 71.336$$

NOTE: Use digits of whole number only, i.e., 452 and 71

- * Note minute and second values of geographic coordinates must be changed to decimal, i.e., $71^{\circ}25'00''$ - Change minutes to decimal $25 \div 60 = .417$ then 71.417°

Exhibit A12.--Sample problem - Method I (continued)

add one (+1) to the computed values to identify sector row and column where the NW corner of the input map sheet appears.


$$\text{Hence } C = 452 + 1 = \underline{453}$$


$$R = 71 + 1 = \underline{72}$$



Enter the value -- sector column 453 and row 72 in columns 29 thru 34 on the "G" input card.

Exhibit A12.--Sample problem - Method I (continued)





4. Map Types and Forms

Maps, as defined within GRID, appear in a variety of types and forms. Exhibit A13 provides a graphic representation of the basic relationship between the various map configurations.

The elements of a map when printed on the page, may be represented by numbers exclusively (numeric map) or by a combination of letters, numbers and special characters (alpha maps). The numeric maps provide the ability to distinguish between elements within a map on the basis of some discrete quantitative characteristic and also can lend themselves to mathematical manipulation. Alpha maps are generally used for storing data with a large number of unique categories and for special display purposes.

Real-valued maps allow continuous quantitative information to be stored and present a great advantage to the user for arithmetic composition. They, however, cannot be displayed unless their values are transformed into a discrete set (numeric or alpha).

Boundary maps are derived from alpha or numeric maps or are created from a digitized data source. What they actually contain are the boundaries separating homogeneous areas within the parent maps (county, tract boundaries, etc.).

Real-valued, numeric and alpha maps can be used to describe a geographical area in terms of a single characteristic such as Timber Crown Diameter Classes, soil type, or annual rainfall. Timber Crown Diameter




Exhibit A13.--Grid map types

Classes and annual rainfall are quantitative measures and as such would probably be best described by a real-valued map or, in the case of a map to be displayed, in numeric terms where each of the digits (zero through nine) represents, in ascending scale, a range of values. Soil type is a characteristic which is generally qualitative in its use. Each discrete soil type can be equated to a different print character. In such a case an alpha map is suitable because the names of different soil types do not lend themselves to mathematical operations. Another reason why an alpha map is preferable is that the number of different soil types may exceed the available ten digits to which one is limited on a numeric map. In cases of quantitative characteristics the scale ranges can be set to form ten or fewer categories, (see below); however, in the case of discrete qualitative characteristics, the larger number of symbols available in the alphanumeric character set may be required.

<u>SYMBOL</u>		<u>FEET</u>
0	=	10
1	=	12
2	=	14
3	=	16
4	=	18
5	=	20

The numbers appearing in the elements of individual numeric topic maps must be considered as indices. This is so because the attribute being displayed is divided into ten (or fewer) classifications, each of which is assigned a digit. These assigned digits or index numbers are used in such a way that a higher number generally represents better or more desirable conditions. For example, the elements with higher numbers could represent more desirable locations in terms of a target or goal than elements with lower numbers. These index numbers are unique to their definitions. It would not be correct, therefore, for the reader to presume that a "3" as an element value indicates that this location whose element contains a "2". All that one can say is the location indicated by a "3" is better than those which have "2's," but not as good as those locations represented by "4's" or higher numbers.

Maps which describe geographical areas in terms of a single characteristic, either quantitative or qualitative are called topic maps. There are three fundamental forms of topic maps: conformal (block), continuous and master maps.

Conformal maps are those where the basic geographic shape conforms to some previously defined boundaries such as

counties or regions. In these maps, all elements within an area, for example, a county, are of uniform value which represent the statistical total or average reported for the area. This type of conformal or block mapping is characteristic of most socio-economic data, and is quite acceptable for economic analysis. Conformal maps can be either numeric, alpha or real.

Exhibit A14 gives an example of an alpha conformal topic map. In this case, the element values within the sector vary with the county boundaries. Each county has a unique alphanumeric element symbol. Exhibit A15 gives an example of a numeric conformal topic map. Median family income is expressed with the values ranging from one to nine. The boundaries of similar element values correspond in general with the alpha conformal topic map of Exhibit A14 since the median income statistics were originally collected on a county basis. Adjacent counties having equal median income ranges will have their county boundaries suppressed.

Continuous maps show variations from element to element where data are available in fine grain for such topics as soil types, intensity of land use, or amount of rainfall over the area. Continuous maps may be either real-valued, numeric or alpha. Exhibit A16 gives an example of a numeric continuous

Master maps are generally created for the express purpose of storing geographic shapes such as county boundaries, State boundaries, planning regions, etc. Master maps may be created either from digitized data files or by manual means. Master map names begin with an asterisk such as *COUNTY to designate a master map at the county level.

Composite topic maps are new topic maps based upon some expression relating any number of topic maps. For example, a composite topic map indicating feasible locations for certain mineral processing facilities might be derived from topic maps showing mineral accessibility, rail accessibility, power accessibility, pipeline accessibility, labor accessibility, and local buildable land.

Study Area Reference

Whenever a map analysis study is to be conducted, a GRID Study Area Reference should be constructed. This brief reference shows valid entries for file names, grid codes sector identifications, and topic names. A reference of this nature can reduce the time required to complete GRID parameter cards as well as reduce the frequency of input errors as the result of invalid entries. Ideally, the Study Area Reference would be in looseleaf form to facilitate easy updating.




Exhibit A14.--Alpha conformal topic map



Exhibit A15.--Numeric conformal topic map - grey tone




Exhibit A16.--Numeric continuous topic map - grey tone.

5. Data Format

- a. Topic and value grid type mapping involves storing data in a manner similar to map overlays or layers of information. These layers of information are known as topics. The maximum number of topics one expects to store is limited only by the availability of tape storage. The data elements of a topic are known as elements and they are coded with either alpha or numeric characters. Authorized characters for RAP are:

-	=	+	*	,	\$	/	()	A	B	C	D
F	G	H	I	J	K	L	M	N	P	Q	R	S
U	V	W	X	Y	Z	9	8	7	6	5	4	3
1	0											

There are 44 characters that can be used, note that the letter "O" and the period "." are not valid characters.

- b. Data collected for a topic should describe in the most basic way the characteristics of the topic. For example, "high erosion hazard" as a value name for soil topic places an interpretation of the land, but no definite classification of the data, with such facts as slope, pH, and soil type, simply describe the most basic characteristics of the soil. Such individual nonintegrated data provides much greater flexibility of use and objectivity.

6. Data Base Drafting

At this point, sector row/column, element row/column, grid cell size, and map scale have been identified.

a. Supplies needed to begin project:

- (1) Master Grid--a mylar of the selected grid with appropriate row and column numbers and rectilinear study area boundaries.
- (2) Code sheets--mylar copies of the master grid to be used for coding values. One copy will contain all the coded values for one topic.
- (3) I.D. Strips--two identification (I.D.) strips are used on each sector. One is attached to the left side of the code sheet to identify the row of the sector. The other I.D. strip is attached to the top of the sector and contains card column numbers. This is explained in more detail in Section 3 (2 and 3).

b. Procedure for obtaining supplies:

- (1) Obtain master grid mylar:

There is a program at FCCC that produces a grid format which divides the input map sheet into 120 rows by 120 columns. The program is called RID*GRID.GRIDDER. The grid is created by either inputting geographic coordinate values or map dimensions of the source map.

The program can be run at the Forest terminal but the grid must be plotted at the Regional Office

and mailed to the Forest. (Use @MSG command to specify "Plot on mylar with black ballpoint" for description of plots.)

To input geographic coordinate values use

runstream: A. To input map dimensions use th

runstream: B.

RUNSTREAM A

DEMAND TERMINAL

RUNSTREAM TO EXECUTE GRIDDER PROGRAM -- OPTION -- 1
INPUTTING GEOGRAPHIC COORDINATES

>@RUN
DATE: 032778 TIME: 072918 AUTONEWS OFF
>@ASG,A RID*GRID.
FACILITY WARNING 000000000200
>@ASG,T 7,///1000

READY
>@XQT RID*GRID.GRIDDER

INPUT OPTION--1, IF INPUTTING GEOGRAPHICAL COORDINATES
OPTION--2, IF INPUTTING MAP DIMENSIONS

>1
OPTION 1--INPUT TYPE OF REFERENCE SPHEROID--1, 2, or 3
NO. 1: CLARK 1880 SPHEROID
NO. 2: INTERNATIONAL
NO. 3: CLARK 1866

>3
OPTION 1--INPUT LATITUDE AND LONGITUDE OF THE SOUTHWEST
CORNER OF A QUAD AS DEG,MIN,SEC,DEG,MIN,SEC

>43,15,0,73,0,0
INPUT LATITUDE AND LONGITUDE OF THE NORTHEAST CORNER
AS DEG,MIN,SEC,DEG,MIN,SEC

>43,30,0,72,45,0
INPUT MAP SCALE

>31680
>@ASG,CP RIDS*PLOTPT1 ← User supplied file name
READY
>@USE P, RIDS*PLOTPT1 ←
READY
>@BRKPT PRINT\$/P
>@MSG,N PLOT ON MYLAR WITH BLACK BALL POINT PEN ← Optional
>@XQT RDS*RDS.CALT
>@BRKPT PRINT\$
>@FREE P
READY
>@SYM RIDS*PLOTPT1,, (USE YOUR OWN SITE ID)
>@FIN

RUNSTREAM B

DEMAND TERMINAL

RUNSTREAM TO EXECUTE .GRIDDER PROGRAM -- Option - 2
INPUTTING MAP DIMENSIONS

```
>@RUN
DATE: 032778 TIME: 073711 AUTONEWS OFF
>@ASG,A RID*GRID.
FACILITY WARNING 000000000200
>@ASG,T 7,///1000
READY
>@XQT RID*GRID.GRIDDER
INPUT OPTION--1, IF INPUTTING GEOGRAPHICAL COORDINATES
--2, IF INPUTTING MAP DIMENSIONS
>2
OPTION 2, FOR A GIVEN QUAD, INPUT THE VERTICAL MEASUREMENT
IN INCHES FIRST, THEN THE LOWER BASE LINE
MEASUREMENT IN INCHES, THEN THE UPPER BASE LINE
IN INCHES AS INCHES1,INCHES2,INCHES3
>17.25,12.60,12.58
>@ASG,CP RIDS*PLOTPRT2
READY
@USE P, RIDS*PLOTPRT2
READY
>@BRKPT PRINT$/P
>@MSG,N PLOT ON MYLAR WITH BLACK BALL POINT PEN
>@XQT RDS*RDS,CALT
>@BRKPT PRINT$
>@FREE P
READY
>@SYM RIDS*PLOTPRT2,, (USE YOUR OWN SITE ID)
>@FIN
```

Handwritten annotations:

- An arrow points from "User supplied file name" to PLOTPRT2 in the command `>@ASG,CP RIDS*PLOTPRT2`.
- An arrow points from "Optional" to the second comma in the command `>@SYM RIDS*PLOTPRT2,, (USE YOUR OWN SITE ID)`.

- (2) Obtain Code Sheets. Send master grid mylar to local duplicating firm. Request one mylar copy for each topic to be coded.
- (3) Obtain ID Strips. ID strips are made from cut up sections of prints of the master grid before rows and columns are numbered and the boundary delineated.

c. Development of Master Grid.


(1) Divide Grid

METHOD I - The master grid is created as one sector which covers the entire source map.


____ Portion of page deleted

(2) Identify the sector row/column.

METHOD I - This is the value computed on page which designates the sector in which the NW corner of the input quad sheet will be found.




- (3) Delineate Boundary on Master Grid. This often involves transforming curvilinear lines into a rectilinear grid pattern. For cells adjacent to the intended boundary, if 50 percent or more of the cell falls within the study area, include the cell within the boundary.
 - (4) Obtain mylar copy of master grid for each topic. These will be used as the code sheets.
- d. Coding Values - overlay mylar code sheet on source map and record appropriate values. A cell may have only one coded value per topic.
 - e. Prepare Code Sheet for Key punching. Values are key-punched on cards which are read by the computer. There are 80 columns on a keypunch card.
- (1) Since each sector contains 120 rows by 120 columns, it is necessary to divide the columns in half for coding purposes and to designate them as right hand and left hand side.



____ Portion of page deleted

- (2) Beginning with the NW sector, attach an ID strip to the left side to identify the rows 001 thru 120.
- (3) Again at the NW sector attach an ID strip to the top of the sheet to identify columns 9 thru 68 for left hand side and 2 thru 61 for right hand side.

PREPARE CODE SHEET FOR KEYPUNCHING



- ① DIVIDE SECTOR IN HALF
- ② ATTACH ID STRIPS NW CORNER

(4) Then record the cell values on an 80 column coding form similar to a FORTRAN coding form as shown in Exhibit first line entered on the coding form is to enter the request card of "A" card ('A' card always necessary) for illustration purposes the sample "A" card contains the following information:

Column 1 Identifies card as "A"

Columns 3-14 Requester A. B. DICK

31-36 Action CREATE a map file

('CREATE' indicates active mode
and requires a @ASG,T 7.,U9V)

58 No Input Map File "X" denotes new file
being created

61-72 Map File Name "BENCHRAP"

The second line entered on the coding form is to enter the topic definition card or "G" card ('G' card always necessary). A complete discussion of the "A" and "G" cards is found in Appendix A. For illustration purposes the sample "G" card contains the following information:

Column 1 Identifies card as "G"

3 Grid Code Type "C" (Optional-no longer
used)

4-6 Grid code level 001 (See Table 2)

7 Grid code lines-per-inch "8"

9-21 Topic Name (.SOILS)

29-31 Sector Row Number 82

32-34 Sector Column Number 470

US DEPARTMENT OF AGRICULTURE FORTRAN CODING	PROGRAM NO.	SYSTE**	P-CC	1
DATA CODING				

DATA CODING

[illegible]

FROM 07573 18-747

(5) Record the cell value for input on a "P" card as shown below. See Appendix A for a complete discussion on the use of the "P" card. All left side data is keypunched first followed by right side data entries.

a. To record the left side:

Column 1 Identify card as "P"

3-5 Starting row number

6-8 End row number

9-68 Left hand side cell values

b. To record the right side:

Column 2-61 Right hand side cell values

63-65 Start row number

66-68 End row number

NOTE #1: At any point in the data matrix with the exception of the first data position at each left and right hand column, a period (.) may be used to indicate the column repetition of the previous data value until a new data value in the same column is encountered.

NOTE #2: If you have an area where the rows have identical values for the entire row and they are duplicated in successive rows the data may be entered in block form. See column form line numbers 7 and 20, Exhibit A17 for example. This indicates that the cell data for rows 21 thru 35 and 102 thru 108 are identical.

(6) NOTE: All cells must be accounted for in a sector. For those cells that fall outside the study area the user selects a unique character to code these null cells. In the data manipulation phase this null cell is suppressed so that these cells are not counted in the calculations.


The cost of keypunching and verifying is approximately \$0.105 per card. To determine the number of cards to be punched, multiply the number of cards per row times the number of rows. Keypunching turnaround time is influenced by size of data base (number of cells and variables) and by number of digits per coded value.

Turnaround time will rarely exceed 1 week.

Input Forms

1. General

All input cards must have the card type indicated in column 1. This applies to Batch Processing and to Demand Mode of operation. In Batch Processing the input deck must be preceeded by an asterisk card and must be followed by an asterisk card. The input deck should look as follows:



NOTE: See Appendix A for complete description of input cards.

2. Initial Run-Passive

Now that you have all your data coded and cards prepared for input to GRID, the following procedure is recommended for initial input of data. The initial run will be in a passive mode, that is, no files will be created. The purpose of the initial run is to obtain an output which can be used for editing and verification purposes.

Phase I will list the original input, error messages if any and the printed output with all cells filled in. The initial run is executed in the batch mode. Data is input one sector at a time and each sector is identified by a "G" Card. The following is a sample runstream for the initial input of data (see Exhibit A18).

SAMPLE RUNSTREAM

@RUN

@ASG,A RID*GRID

@XQT,OU RID*GRID.GRID

GRID PROGRAM FILE

* Asterisk Card

A Personal Identification Card

G Topic Definition Card

*I Legend Input

P Data Cards

T Statistical Parameters

Z Map Display

G Topic Definition Card

*I

P

T

Z (Repeat until all sectors are inputted)

G Second topic/First Sector

G (Repeat until all topics/sectors are inputted)

* Asterisk

@ FIN

The I cards are optional at this time.

legend or title information. See Appa

Explanation of I card.

Exhibit A18. -- Sample purchase
(Part 1 of 2)

***** TRANSACTION REGISTER *****

Call into left side

1234567890123456789012345678901234567890123456789012345678901234567890

A ED CHAPMAN ENGINEERING K BENCHRAP

Q 0010 (SOILS)

P 1 G. R. D. M. D. Q. H. G. C. F. E. K.

P 2 G. K. D. M. D. Q. H. G. C. F. E. K.

P 3 K. G. D. M. D. Q. H. G. C. F. E. K.

P 4 K. D. D. M. D. Q. H. G. C. F. E. K.

P 5 DK. D. M. D. Q. H. G. C. F. E. K.

/// ERROR 65, DOT MISSING IN COLUMN 010

P 6 D. K. D. M. D. Q. H. G. C. F. E. K.

/// ERROR 65, DOT MISSING IN COLUMN 017

P 7 D. K. D. M. D. Q. H. G. C. F. E. K.

P 8 D. K. D. M. D. Q. H. G. C. F. E. K.

P 9 D. K. D. M. D. Q. H. G. C. F. E. K.

P 10 D. K. D. M. D. Q. H. G. C. F. E. K.

P 11 D. K. D. M. D. Q. H. G. C. F. E. K.

P 12 D. K. D. M. D. Q. H. G. C. F. E. K.

P 13 D. K. D. M. D. Q. H. G. C. F. E. K.

P 14 D. K. D. M. D. Q. H. G. C. F. E. K.

P 15 D. K. D. M. D. Q. H. G. C. F. E. K.

P 16 D. K. D. M. D. Q. H. G. C. F. E. K.

P 17 D. K. D. M. D. Q. H. G. C. F. E. K.

P 18 D. K. D. M. D. Q. H. G. C. F. E. K.

P 19 D. K. D. M. D. Q. H. G. C. F. E. K.

P 20 D. K. D. M. D. Q. H. G. C. F. E. K.

P 21 D. K. D. M. D. Q. H. G. C. F. E. K.

P 22 D. K. D. M. D. Q. H. G. C. F. E. K.

P 23 D. K. D. M. D. Q. H. G. C. F. E. K.

P 24 D. K. D. M. D. Q. H. G. C. F. E. K.

/// ERROR 68, NONNUMERIC CHARACTER IN ROW DESIGNATION

P 25 D. K. D. M. D. Q. H. G. C. F. E. K.

P 26 D. K. D. M. D. Q. H. G. C. F. E. K.

P 27 D. K. D. M. D. Q. H. G. C. F. E. K.

P 28 D. K. D. M. D. Q. H. G. C. F. E. K.

P 29 D. K. D. M. D. Q. H. G. C. F. E. K.

P 30 DK. D. K. D. M. D. Q. H. G. C. F. E. K.

P 31 DK. D. K. D. M. D. Q. H. G. C. F. E. K.

P 32 DK. D. K. D. M. D. Q. H. G. C. F. E. K.

P 33 DK. D. K. D. M. D. Q. H. G. C. F. E. K.

P 34 K. D. D. M. D. Q. H. G. C. F. E. K.

P 35 K. D. D. M. D. Q. H. G. C. F. E. K.

P 36 K. D. D. M. D. Q. H. G. C. F. E. K.

P 37 K. D. D. M. D. Q. H. G. C. F. E. K.

P 38 K. D. D. M. D. Q. H. G. C. F. E. K.

P 39 K. D. D. M. D. Q. H. G. C. F. E. K.

P 40 K. D. D. M. D. Q. H. G. C. F. E. K.

P 41 K. D. D. M. D. Q. H. G. C. F. E. K.

P 42 K. D. D. M. D. Q. H. G. C. F. E. K.

P 43 K. D. D. M. D. Q. H. G. C. F. E. K.

P 44 K. D. D. M. D. Q. H. G. C. F. E. K.

P 45 K. D. D. M. D. Q. H. G. C. F. E. K.

P 46 K. D. D. M. D. Q. H. G. C. F. E. K.

P 47 K. D. D. M. D. Q. H. G. C. F. E. K.

P 48 K. D. D. M. D. Q. H. G. C. F. E. K.

P 49 K. D. D. M. D. Q. H. G. C. F. E. K.

/// ERROR 65, DOT MISSING IN COLUMN 029

P 50 K. D. D. M. D. Q. H. G. C. F. E. K.

P 51 K. D. D. M. D. Q. H. G. C. F. E. K.

P 52 K. D. D. M. D. Q. H. G. C. F. E. K.

P 53 K. D. D. M. D. Q. H. G. C. F. E. K.

P 54 K. D. D. M. D. Q. H. G. C. F. E. K.

P 55 K. D. D. M. D. Q. H. G. C. F. E. K.

P 56 K. D. D. M. D. Q. H. G. C. F. E. K.

P 57 K. D. D. M. D. Q. H. G. C. F. E. K.

P 58 K. D. D. M. D. Q. H. G. C. F. E. K.

1234567890123456789012345678901234567890123456789012345678901234567890

Exhibit A18.--Initial run - passive
(Part 2 of 2)

3. Verification Run-Passive

Upon completion of editing your input data cards and updating your deck with corrected data, you then rerun your deck to obtain clean output copies of your input data. This run is executed in the same manner as inputting your initial data. This output will be a verification of the edited data deck. It will include Phase I input listing and Phase II, the topic generation and display file (See Exhibit A20).

4. Create Initial File-Active

Once you are satisfied with your corrected data you then input the data in an active mode to "CREATE" a permanent tape file. The following suggested runstream is executed in a batch mode to create a permanent data file. (Exhibit A21.)

@RUN

@ASG,A RID*GRID.

@USE 9, (QUAL*FILENAME) This is your output file

@ASG,T 9, U9V

@XQT, OU RID*GRID.GRID

(Runstream identical to initial input, and obtaining verification plots. With the exception of entering "CREATE" in the action field of A-card.)

@FIN

Your output will be; Phase I, an input listing, Phase II,




Exhibit A19.--Verification run/map - passive
(Part 2 of 3)

5. Adding New Topics

To add new topics to an existing file the procedure is identical to inputting data in an initial run-passive mode. Edit your data, rerun to obtain verification plots in the passive mode then once you are satisfied with your input add new data to your existing file with the following suggested runstream.

```
@RUN
```

```
@ASG,A RID*GRID.
```

```
@ASG,T QUAL*FILENAME (your existing file name) U9V, F12345
```

```
@USE, 7 Existing File
```

Note Unit 7 is used to input existing file.

```
@USE 9, QUAL*FILENAME (new file name)
```

Note Unit 9 is used to output a map file

```
@ASG,T 9, U9V
```

```
@XQT, OU RID*GRID.GRID
```

```
*
```

Input Data

```
*
```

```
@FIN
```

Once your run has been successfully executed do not forget to save your file.

C. Data Manipulation - GRID

1. Summary

The program RID*GRID is a FORTRAN program to store, retrieve, manipulate, and combine information that has an on-the-ground relationship. The program features:

- An ability to display a single topic, from combining layers of resource and physical data such as soils, topography, vegetation, etc.
- A fully labeled line-printer map display with quantitative output such as statistical area summaries and histograms.
- A geographic base system of which the data base is keyed to latitude and longitude map coordinates. This facilitates the registration and location of the output map.
- Topic maps can be created using linear combinations.

2. Data Display

- a. General - The data is "displayed" or "mapped" with row and column numbers as elected. There are four basic display options that are available with GRID.

- (1) Single character display is limited to the 44 input characters (see Exhibit A22).

- (2) Gray scale display can only be obtained when cell coded data contains numeric values (0-9), one to ten levels of coded values of a single topic can be displayed on one map. The "Z-card" is used to define the gray scale output (see Exhibit A27).

- (3) The geographic boundary outlines may be displayed by themselves or suppressed from the output (see Exhibits A23 and A24).

- (4) Selective display of portions of an area or sector (window display) by using the "W" input card (see Exhibit A28).

- b. Map Generation can be generated and printed at the Forest computer terminal or generated and printed on the line printer in the Regional Office. Turnaround time will depend on processing priority and mailing. As mentioned in the section on data base development, line printer characters occupy a rectangular area 1/10" wide by 1/8" high. The line printer has the capability to:

- (1) Print six or eight lines per inch depending on the

desired map scale (see Exhibit A9 under data base develop-
(2) Overprint characters to obtain desired gray scale
(3) Produce statistical reports; user can suppress the
output and obtain statistical outputs only if requested.
(4) Slow speed terminals such as demand terminals are not
suitable for large map display requests and are not always
capable of producing overstrike characters to produce a
scale output map.

3. Data Mapping Options

GRID is a generalized system which is user-oriented and open
for future expansion. "User-oriented" refers to the ability
to operate the system without the need for a programmer, and "open-
ended" refers to the structuring of the GRID logic such that
additional features can be incorporated without extensive re-
programming. For illustration purposes the following display map
options will be discussed:

-- Single topic display

- 1) Cell data only without geographic boundary outline
- 2) Cell data with boundary printed solid
- 3) Cell data with boundary outline dropped out
- 4) Geographic boundary outline only

-- Intersection

- 1) Alpha output
 - Linear combination
- 1) Numeric output
- 2) Gray scale
 - Window display
- 1) With geographic boundary outline
- 2) Cell data only
 - Text Overlay

1) Titling Map Features

a. Single Topic Display

One to forty-four (1-44) coded values of a single topic can be displayed on one map. If there are more than 44 values coded for a single topic and the user wishes to display all values, more than one map must be generated.

Sample - Single Display

The user wants to display values by topic, geographic area outline, and obtain acreage calculations.

Topic to be displayed:

*Ecological land types

Values to be used:

*A-N, P-T, X total 20 values

Sample runstream with boundary printed, Exhibit A21

Sample runstream without boundary, Exhibit A22

Sample runstream outputs with boudary only, Exhibit A23

Sample runstream with boundary drop-out, Exhibit A24

The following suggested runsteam is used to obtain single topic display

* @RUN (Your run card)

* @ASG, A RID*GRID. (Program file)

* @ASG, T RIDS*BMRAP3., U9V, F10759 (Input file)

* @USE 7, RIDS*BMRAP3

* @XQT, OU RID*GRID.GRID

** (Asterisk Card)

REFERENCE (User specified sector origin)

* A (Mapping Request)

* G (Topic Definition)

* I

T (Statistics Parameters)

Z (Map Display)

** (Asterisk Card)

* @ FIN

* These cards are required for all runs

See Appendix "A" for explanation of Input Card Formats

ABCDEFGHIJKLMNOPQRSTUVWXYZ 1234567890 P...# \$ % & ' () * + , - . : ;

U.S. DEPARTMENT OF AGRICULTURE
FORTRAN CODING

SINGLE TOPIC - DISPLAY WITH BOEN DRIVES

BLOCK PUNCH



WILLIAM W. W.

2

91C - 1

5126 Gd

FORALIN



Table 1. Summary of the results of the 1996-1997 survey.

[illegible]

[illegible]

442, 473 and 494
 4015 4040 4065
 4110 4135 4160

1000



Date		Time		Location		Remarks	
Day	Month	Year	Hour	Minute	Place	Wind	Sea
1	Jan	1950	08	15	Off Cape Cod	10	3
2	Jan	1950	09	30	Off Cape Cod	12	4
3	Jan	1950	10	15	Off Cape Cod	15	5
4	Jan	1950	11	45	Off Cape Cod	18	6
5	Jan	1950	12	30	Off Cape Cod	20	7
6	Jan	1950	13	15	Off Cape Cod	22	8
7	Jan	1950	14	00	Off Cape Cod	25	9
8	Jan	1950	15	45	Off Cape Cod	28	10
9	Jan	1950	16	30	Off Cape Cod	30	11
10	Jan	1950	17	15	Off Cape Cod	32	12
11	Jan	1950	18	00	Off Cape Cod	35	13
12	Jan	1950	18	45	Off Cape Cod	38	14
13	Jan	1950	19	30	Off Cape Cod	40	15
14	Jan	1950	20	15	Off Cape Cod	42	16
15	Jan	1950	21	00	Off Cape Cod	45	17
16	Jan	1950	21	45	Off Cape Cod	48	18
17	Jan	1950	22	30	Off Cape Cod	50	19
18	Jan	1950	23	15	Off Cape Cod	52	20
19	Jan	1950	24	00	Off Cape Cod	55	21
20	Jan	1950	24	45	Off Cape Cod	58	22
21	Jan	1950	25	30	Off Cape Cod	60	23
22	Jan	1950	26	15	Off Cape Cod	62	24
23	Jan	1950	27	00	Off Cape Cod	65	25
24	Jan	1950	27	45	Off Cape Cod	68	26
25	Jan	1950	28	30	Off Cape Cod	70	27
26	Jan	1950	29	15	Off Cape Cod	72	28
27	Jan	1950	30	00	Off Cape Cod	75	29
28	Jan	1950	30	45	Off Cape Cod	78	30
29	Jan	1950	31	30	Off Cape Cod	80	31
30	Jan	1950	31	15	Off Cape Cod	82	32
31	Jan	1950	32	00	Off Cape Cod	85	33

A-81

000 000 000 000 000
 000 000 000 000 000
 000 000 000 000 000
 000 000 000 000 000

01-4 474043
1 6 220221
076 34 5772

ALL INFORMATION CONTAINED
HEREIN IS UNCLASSIFIED
DATE 11-19-2008 BY 60322
UCBAW

U D I C O R E

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100

$M = \begin{pmatrix} 7 & 6 & 8 \\ 9 & 10 & 11 \\ 12 & 13 & 14 \end{pmatrix}$

1. The first part of the document discusses the importance of maintaining accurate records of all transactions and activities. It emphasizes that proper record-keeping is essential for transparency and accountability, particularly in the context of public administration and financial management.

2. The second part of the document outlines the various methods and tools used to collect, store, and analyze data. It highlights the need for robust systems that can handle large volumes of information while ensuring data integrity and security.

3. The third part of the document focuses on the role of technology in modern record-keeping. It explores how digital solutions, such as cloud storage and data analytics, can enhance the efficiency and effectiveness of record management processes.

4. The fourth part of the document addresses the challenges associated with maintaining long-term records. It discusses the importance of regular backups, disaster recovery plans, and the use of archival standards to ensure that records remain accessible and usable over time.

5. The fifth part of the document concludes by emphasizing the ongoing nature of record management. It stresses that as technology and organizational needs evolve, record-keeping practices must also adapt to remain effective and relevant.

1 2 3 4 5 6 7 8 9 10 11 12

[illegible]

202010 091201 10111 1111111111 0000000000 0000000000

70148 1976-01 00100101, 5000

[illegible]

141114 0900Z 20 010101 12
 111901 10100101 010 16.1100 0100 14110101 000 10.1000

NOT REPLY TO

100-443887-100

9 - 06/18/07 11:17:07 AM P:\06\04

display map with

3 of 3)

1999, 2000, 2001, 2002, 2003, 2004, 2005, 2006, 2007, 2008, 2009, 2010, 2011, 2012, 2013, 2014, 2015, 2016, 2017, 2018, 2019, 2020, 2021, 2022, 2023, 2024, 2025, 2026, 2027, 2028, 2029, 2030, 2031, 2032, 2033, 2034, 2035, 2036, 2037, 2038, 2039, 2040, 2041, 2042, 2043, 2044, 2045, 2046, 2047, 2048, 2049, 2050, 2051, 2052, 2053, 2054, 2055, 2056, 2057, 2058, 2059, 2060, 2061, 2062, 2063, 2064, 2065, 2066, 2067, 2068, 2069, 2070, 2071, 2072, 2073, 2074, 2075, 2076, 2077, 2078, 2079, 2080, 2081, 2082, 2083, 2084, 2085, 2086, 2087, 2088, 2089, 2090, 2091, 2092, 2093, 2094, 2095, 2096, 2097, 2098, 2099, 2100, 2101, 2102, 2103, 2104, 2105, 2106, 2107, 2108, 2109, 2110, 2111, 2112, 2113, 2114, 2115, 2116, 2117, 2118, 2119, 2120, 2121, 2122, 2123, 2124, 2125, 2126, 2127, 2128, 2129, 2130, 2131, 2132, 2133, 2134, 2135, 2136, 2137, 2138, 2139, 2140, 2141, 2142, 2143, 2144, 2145, 2146, 2147, 2148, 2149, 2150, 2151, 2152, 2153, 2154, 2155, 2156, 2157, 2158, 2159, 2160, 2161, 2162, 2163, 2164, 2165, 2166, 2167, 2168, 2169, 2170, 2171, 2172, 2173, 2174, 2175, 2176, 2177, 2178, 2179, 2180, 2181, 2182, 2183, 2184, 2185, 2186, 2187, 2188, 2189, 2190, 2191, 2192, 2193, 2194, 2195, 2196, 2197, 2198, 2199, 2200, 2201, 2202, 2203, 2204, 2205, 2206, 2207, 2208, 2209, 2210, 2211, 2212, 2213, 2214, 2215, 2216, 2217, 2218, 2219, 2220, 2221, 2222, 2223, 2224, 2225, 2226, 2227, 2228, 2229, 2230, 2231, 2232, 2233, 2234, 2235, 2236, 2237, 2238, 2239, 2240, 2241, 2242, 2243, 2244, 2245, 2246, 2247, 2248, 2249, 2250, 2251, 2252, 2253, 2254, 2255, 2256, 2257, 2258, 2259, 2260, 2261, 2262, 2263, 2264, 2265, 2266, 2267, 2268, 2269, 2270, 2271, 2272, 2273, 2274, 2275, 2276, 2277, 2278, 2279, 2280, 2281, 2282, 2283, 2284, 2285, 2286, 2287, 2288, 2289, 2290, 2291, 2292, 2293, 2294, 2295, 2296, 2297, 2298, 2299, 2300, 2301, 2302, 2303, 2304, 2305, 2306, 2307, 2308, 2309, 2310, 2311, 2312, 2313, 2314, 2315, 2316, 2317, 2318, 2319, 2320, 2321, 2322, 2323, 2324, 2325, 2326, 2327, 2328, 2329, 2330, 2331, 2332, 2333, 2334, 2335, 2336, 2337, 2338, 2339, 2340, 2341, 2342, 2343, 2344, 2345, 2346, 2347, 2348, 2349, 2350, 2351, 2352, 2353, 2354, 2355, 2356, 2357, 2358, 2359, 2360, 2361, 2362, 2363, 2364, 2365, 2366, 2367, 2368, 2369, 2370, 2371, 2372, 2373, 2374, 2375, 2376, 2377, 2378, 2379, 2380, 2381, 2382, 2383, 2384, 2385, 2386, 2387, 2388, 2389, 2390, 2391, 2392, 2393, 2394, 2395, 2396, 2397, 2398, 2399, 2400, 2401, 2402, 2403, 2404, 2405, 2406, 2407, 2408, 2409, 2410, 2411, 2412, 2413, 2414, 2415, 2416, 2417, 2418, 2419, 2420, 2421, 2422, 2423, 2424, 2425, 2426, 2427, 2428, 2429, 2430, 2431, 2432, 2433, 2434, 2435, 2436, 2437, 2438, 2439, 2440, 2441, 2442, 2443, 2444, 2445, 2446, 2447, 2448, 2449, 2450, 2451, 2452, 2453, 2454, 2455, 2456, 2457, 2458, 2459, 2460, 2461, 2462, 2463, 2464, 2465, 2466, 2467, 2468, 2469, 2470, 2471, 2472, 2473, 2474, 2475, 2476, 2477, 2478, 2479, 2480, 2481, 2482, 2483, 2484, 2485, 2486, 2487, 2488, 2489, 2490, 2491, 2492, 2493, 2494, 2495, 2496, 2497, 2498, 2499, 2500, 2501, 2502, 2503, 2504, 2505, 2506, 2507, 2508, 2509, 2510, 2511, 2512, 2513, 2514, 2515, 2516, 2517, 2518, 2519, 2520, 2521, 2522, 2523, 2524, 2525, 2526, 2527, 2528, 2529, 2530, 2531, 2532, 2533, 2534, 2535, 2536, 2537, 2538, 2539, 2540, 2541, 2542, 2543, 2544, 2545, 2546, 2547, 2548, 2549, 2550, 2551, 2552, 2553, 2554, 2555, 2556, 2557, 2558, 2559, 2560, 2561, 2562, 2563, 2564, 2565, 2566, 2567, 2568, 2569, 2570, 2571, 2572, 2573, 2574, 2575, 2576, 2577, 2578, 2579, 2580, 2581, 2582, 2583, 2584, 2585, 2586, 2587, 2588, 2589, 2590, 2591, 2592, 2593, 2594, 2595, 2596, 2597, 2598, 2599, 2600, 2601, 2602, 2603, 2604, 2605, 2606, 2607, 2608, 2609, 2610, 2611, 2612, 2613, 2614, 2615, 2616, 2617, 2618, 2619, 2620, 2621, 2622, 2623, 2624, 2625, 2626, 2627, 2628, 2629, 2630, 2631, 2632, 2633, 2634, 2635, 2636, 2637, 2638, 2639, 2640, 2641, 2642, 2643, 2644, 2645, 2646, 2647, 2648, 2649, 2650, 2651, 2652, 2653, 2654, 2655, 2656, 2657, 2658, 2659, 2660, 2661, 2662, 2663, 2664, 2665, 2666, 2667, 2668, 2669, 2670, 2671, 2672, 2673, 2674, 2675, 2676, 2677, 2678, 2679, 2680, 26

4.00

A-90

```
display map with boundaries as
. 3 of 3)
```


US DEPARTMENT OF AGRICULTURE
FORTRAN CODING


SINGLE TOPIC DISPLAY - BOUNDARIES ONLY

	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100	101	102	103	104	105	106	107	108	109	110	111	112	113	114	115	116	117	118	119	120	121	122	123	124	125	126	127	128	129	130	131	132	133	134	135	136	137	138	139	140	141	142	143	144	145	146	147	148	149	150	151	152	153	154	155	156	157	158	159	160	161	162	163	164	165	166	167	168	169	170	171	172	173	174	175	176	177	178	179	180	181	182	183	184	185	186	187	188	189	190	191	192	193	194	195	196	197	198	199	200	201	202	203	204	205	206	207	208	209	210	211	212	213	214	215	216	217	218	219	220	221	222	223	224	225	226	227	228	229	230	231	232	233	234	235	236	237	238	239	240	241	242	243	244	245	246	247	248	249	250	251	252	253	254	255	256	257	258	259	260	261	262	263	264	265	266	267	268	269	270	271	272	273	274	275	276	277	278	279	280	281	282	283	284	285	286	287	288	289	290	291	292	293	294	295	296	297	298	299	300	301	302	303	304	305	306	307	308	309	310	311	312	313	314	315	316	317	318	319	320	321	322	323	324	325	326	327	328	329	330	331	332	333	334	335	336	337	338	339	340	341	342	343	344	345	346	347	348	349	350	351	352	353	354	355	356	357	358	359	360	361	362	363	364	365	366	367	368	369	370	371	372	373	374	375	376	377	378	379	380	381	382	383	384	385	386	387	388	389	390	391	392	393	394	395	396	397	398	399	400	401	402	403	404	405	406	407	408	409	410	411	412	413	414	415	416	417	418	419	420	421	422	423	424	425	426	427	428	429	430	431	432	433	434	435	436	437	438	439	440	441	442	443	444	445	446	447	448	449	450	451	452	453	454	455	456	457	458	459	460	461	462	463	464	465	466	467	468	469	470	471	472	473	474	475	476	477	478	479	480	481	482	483	484	485	486	487	488	489	490	491	492	493	494	495	496	497	498	499	500	501	502	503	504	505	506	507	508	509	510	511	512	513	514	515	516	517	518	519	520	521	522	523	52
--	---	---	---	---	---	---	---	---	---	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	----

7 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63 64 65 66 67 68 69 70 71 72 73 74 75 76 77 78 79
 80 81 82 83 84 85 86 87 88 89 90 91 92 93 94 95 96 97 98 99 100 101 102 103 104 105 106 107 108 109 110 111 112 113 114 115 116 117 118 119 120 121 122 123 124 125 126 127 128 129 130 131 132 133 134 135 136 137 138 139 140 141 142 143 144 145 146 147 148 149 150 151 152 153 154 155 156 157 158 159 160 161 162 163 164 165 166 167 168 169 170 171 172 173 174 175 176 177 178 179 180 181 182 183 184 185 186 187 188 189 190 191 192 193 194 195 196 197 198 199 200 201 202 203 204 205 206 207 208 209 210 211 212 213 214 215 216 217 218 219 220 221 222 223 224 225 226 227 228 229 230 231 232 233 234 235 236 237 238 239 240 241 242 243 244 245 246 247 248 249 250 251 252 253 254 255 256 257 258 259 260 261 262 263 264 265 266 267 268 269 270 271 272 273 274 275 276 277 278 279 280 281 282 283 284 285 286 287 288 289 290 291 292 293 294 295 296 297 298 299 300 301 302 303 304 305 306 307 308 309 310 311 312 313 314 315 316 317 318 319 320 321 322 323 324 325 326 327 328 329 330 331 332 333 334 335 336 337 338 339 340 341 342 343 344 345 346 347 348 349 350 351 352 353 354 355 356 357 358 359 360 361 362 363 364 365 366 367 368 369 370 371 372 373 374 375 376 377 378 379 380 381 382 383 384 385 386 387 388 389 390 391 392 393 394 395 396 397 398 399 400 401 402 403 404 405 406 407 408 409 410 411 412 413 414 415 416 417 418 419 420 421 422 423 424 425 426 427 428 429 430 431 432 433 434 435 436 437 438 439 440 441 442 443 444 445 446 447 448 449 450 451 452 453 454 455 456 457 458 459 460 461 462 463 464 465 466 467 468 469 470 471 472 473 474 475 476 477 478 479 480 481 482 483 484 485 486 487 488 489 490 491 492 493 494 495 496 497 498 499 500 501 502 503 504 505 506 507 508 509 510 511 512 513 514 515 516 517 518 519 520 521 522 523 524 525 526 527 528 529 530 531 532 533 534 535 536 537 538 539 540 541 542 543 544 545 546 547 548 549 550 551 552 553 554 555 556 557 558 559 560 561 562 563 564 565 566 567 568 569 570 571 572 573 574 575 576 577 578 579 580 581 582 583 584 585 586 587 588 589 590 591 592 593 594 595 596 597 598 599 600 601 602 603 604 605 606 607 608 609 610 611 612 613 614 615 616 617 618 619 620 621 622 623 624 625 626 627 628 629 630 631 632 633 634 635 636 637 638 639 640 641 642 643 644 645 646 647 648 649 650 651 652 653 654 655 656 657 658 659 660 661 662 663 664 665 666 667 668 669 670 671 672 673 674 675 676 677 678 679 680 681 682 683 684 685 686 687 688 689 690 691 692 693 694 695 696 697 698 699 700 701 702 703 704 705 706 707 708 709 710 711 712 713 714 715 716 717 718 719 720 721 722 723 724 725 726 727 728 729 730 731 732 733 734 735 736 737 738 739 740 741 742 743 744 745 746 747 748 749 750 751 752 753 754 755 756 757 758 759 760 761 762 763 764 765 766 767 768 769 770 771 772 773 774 775 776 777 778 779 780 781 782 783 784 785 786 787 788 789 790 791 792 793 794 795 796 797 798 799 800 801 802 803 804 805 806 807 808 809 810 811 812 813 814 815 816 817 818 819 820 821 822 823 824 825 826 827 828 829 830 831 832 833 834 835 836 837 838 839 840 841 842 843 844 845 846 847 848 849 850 851 852 853 854 855 856 857 858 859 860 861 862 863 864 865 866 867 868 869 870 871 872 873 874 875 876 877 878 879 880 881 882 883 884 885 886 887 888 889 890 891 892 893 894 895 896 897 898 899 900 901 902 903 904 905 906 907 908 909 910 911 912 913 914 915 916 917 918 919 920 921 922 923 924 925 926 927 928 929 930 931 932 933 934 935 936 937 938 939 940 941 942 943 944 945 946 947 948 949 950 951 952 953 954 955 956 957 958 959 960 961 962 963 964 965 966 967 968 969 970 971 972 973 974 975 976 977 978 979 980 981 982 983 984 985 986 987 988 989 990 991 992 993 994 995 996 997 998 999 1000 1001 1002 1003 1004 1005 1006 1007 1008 1009 1010 1011 1012 1013 1014 1015 1016 1017 1018 1019 1020 1021 1022 1023 1024 1025 1026 1027 1028 1029 1030 1031 1032 1033 1034 1035 1036 1037 1038 1039 1040 1041 1042 1043 1044 1045 1046 1047

Exhibit A23.--Single topic display runstream
(Part 1 of 2)

— 224 —



A-94

A B C D E F G H I J K L M N O P Q R S T U V W X Y Z 1 2 3 4 5 6 7 8 9 0 * / ' () % & ^ _ ` ~

U.S. DEPARTMENT OF AGRICULTURE
FORTAN CODING

SINGLE TOPIC DISPLAY - BOUNDARIES BLANK

REF ID: A56, A RIDGE GRID
REF ID: A56, T RIDGE BOUNDARIES, USV F10759 (9-14-64)
REF ID: A56, T RIDGE BOUNDARIES
REF ID: A56, T RIDGE BOUNDARIES
REF ID: A56, T RIDGE BOUNDARIES

REFERENCE 7 223 6 533 44-0833 71-4166
A RIDGE DEMO
G COO18 SC

DISPLAY WITH BOUNDARIES BLANK

SCALE 1:100,000
A - 3
B - 10
C - 11
D - 12

(Suppose boundary symbols)

REF ID: A56


Exhibit A24.---Single topic display with boundaries blank
(Part 1 of 2)

b. Intersections

Intersections deal with "sets." A "set" in this context is a collection of cells with the same coded value for a stated topic. For example, all cells in the timber type topic data base with timber type A would be considered a "set." A second set would be all cells with site class B, in the site class topic and a third set would be all cells with age class C in the age class topic. The intersection of these three sets would be the shaded area on the diagram.

On a map displaying the intersection, the levels represent selected values of the primary topic of concern. The frequency distribution represents the occurrence of cells containing all the selected values of all the sets in the intersection. Cells outside the intersection are not displayed.

Percent of total is always 100 percent. Total acres and square miles represents acreage calculations for intersected values. GRID has the capacity to intersect 10 topics with up to 44 values per topic.



Sample problem: Intersection

The user wants to:

Produce a line printer map and acreage calculation depicting the intersection of the following selected topics and values:

<u>Timber</u>	<u>Ecological</u>	<u>Political</u>
B9 (B)	2 (A)	Town of Bartlett (A)
NC (W)	5 (D)	Town of Albany (E)
M9 (V)		

() - Coded value

NOTE: This option is run in a passive mode unless you want to code a new layer of the resulting code. If the user wants to save the output, a new layer of the intersections must be created and the file saved, otherwise it is executed in the passive mode to obtain outputs only. To create and save output, use the following runstream (sample run, sample map, Exhibit A25).

@RUN

@ASG,A RID*GRID. (Program file)

@ASG,T RIDS*BMRAP2., U9V, F04977 (Your input file)

@USE 7, RIDS*BMRAP2

@USE 9, RIDS*BMRAP3 Use these 2 commands to create an

@ASG,T 9, U9V output file

@XQT, RID*GRID.GRID

THE FOLLOWING RECORDS WERE EITHER CREATED, MODIFIED OR DELETED ON THE NEW MAP FILE SEARCHMAP

ACTION	GRID	MAP TOPIC	SECTOR	BLOCK	DATE	PARENT MAP
CREATE	- C0018	.YISOPD	0	1	JAN 05, 1978	-THRESHOLD-
CREATE	- C0018	.YISOPD	1001	1	JAN 05, 1978	-THRESHOLD-
CREATE	- C0018	.YISOPD	1001	2	JAN 05, 1978	-THRESHOLD-
CREATE	- C0018	.YISOPD	1002	1	JAN 05, 1978	-THRESHOLD-
CREATE	- C0018	.YISOPD	2001	1	JAN 05, 1978	-THRESHOLD-
CREATE	- C0018	.YISOPD	2001	2	JAN 05, 1978	-THRESHOLD-
CREATE	- C0018	.YISOPD	2002	1	JAN 05, 1978	-THRESHOLD-
CREATE	- C0018	.YISOPD	2002	2	JAN 05, 1978	-THRESHOLD-

c. Linear Combinations

This feature of GRID allows for the display of unique combinations of selected values which could not be accomplished by intersections. GRID has the capacity to manipulate 10 topics with up to 44 values per topic. Normally, the initial input will be 44 alpha, numeric and special characters. To obtain a linear combination a numeric map must be created. That is, those values that are to be used in the linear combination must be recoded to numerics (0-9). The sample runstream (Exhibit A26) shows the method to recode the values and execute the desired linear combination.

A unique combination of selected values is a result of the following process:

- 1) Identify topics to be used in combination.
- 2) Identify value(s) that will be used in combination.
- 3) Only 10 combinations can be displayed. To learn the number of combinations to expect, multiply the number of identified values of the first topic times the number of identified values in the second, etc. Product cannot exceed 10.
- 4) Assign weights (1-10) to variables if desired.
- 5) Recode values from alpha to numeric if original input was not numeric.

A linear combination is arrived at by multiplying the assigned weight of a topic by its value and adding this product to the products of the other topics included in the linear combination. (See following sample problem)

The sum of these products represent the unique value displayed on the map. Values must be recoded as necessary to obtain the desired unique combinations. Values not to be considered should be recoded above the maximum expected value.

Sample problem - Linear Combination

1) Topics to be used in combination:

Timber

ELT

POL

2) Values to be used in combination

<u>TOPIC</u>	<u>VALUE</u>
TM	L (1)
ELT	A,D,G, (3)
POL	A,B,E (3)

3) Number of expected combinations:

$$1 \times 3 \times 3 = \underline{9}$$

4) TOPIC WEIGHT

TM	1
ELT	3
POL	2

5) TM (Weight 1)

VALUE L

RECODE 1

ELT (Weight 3)

VALUES A D G

RECODE 1 2 3

POL (Weight 2)

VALUES A B E

RECODE 1 2 3

Weight of TM x Val + Weight of ELT x Val + Weight of POL x Val = Sum

1	3	2	6 (level 1)
1	3	4	8 (level 2)
1	3	6	10 (level 4)
1	6	2	9 (level 3)
1	6	4	11 (level 5)
1	6	6	13 (level 7)
1	9	2	12 (level 6)
1	9	4	14 (level 8)
1	9	6	16 (level 9)

The map will be displayed in 9 levels with the minimum value being 6 and the maximum 16. User can designate the order in which the levels are displayed. The sample output shows the levels being displayed in an ascending order of the summed totals.

Level 1 = TM(L) ELT(A) POL(A)

2 = TM(L) ELT(A) POL(B)

3 = TM(L) ELT(D) POL(A)

4 = TM(L) ELT(A) POL(E)

5 = TM(L) ELT(D) POL(B)

6 = TM(L) ELT(G) POL(A)

7 = TM(L) ELT(D) POL(E)

8 = TM(L) ELT(D) POL(B)

9 = TM(L) ELT(D) POL(E)

(Sample Run, Sample Map Exhibits A27 and A28)

1234567891011121314151617181920212223242526272829303132333435363738394041424344454647484950515253545556575859606162636465666768697071727374757677787980

1234567891011121314151617181920212223242526272829303132333435363738394041424344454647484950515253545556575859606162636465666768697071727374757677787980

1234567891011121314151617181920212223242526272829303132333435363738394041424344454647484950515253545556575859606162636465666768697071727374757677787980

1234567891011121314151617181920212223242526272829303132333435363738394041424344454647484950515253545556575859606162636465666768697071727374757677787980

1234567891011121314151617181920212223242526272829303132333435363738394041424344454647484950515253545556575859606162636465666768697071727374757677787980

1234567891011121314151617181920212223242526272829303132333435363738394041424344454647484950515253545556575859606162636465666768697071727374757677787980

1234567891011121314151617181920212223242526272829303132333435363738394041424344454647484950515253545556575859606162636465666768697071727374757677787980

1234567891011121314151617181920212223242526272829303132333435363738394041424344454647484950515253545556575859606162636465666768697071727374757677787980




Exhibit A26.--Numeric display
(Part 2 of 2)



Exhibit A27.--Linear combination - grey scale display

d. Window Display

Often a multitude of sectors are stored on tape but only a few key positions might be needed for display. The W-Card is designed to selectively display portions of an area. A maximum of one sector can be requested for each W-Card. No boundaries may appear on a window display. You may elect to display either the original cell coded values or gray tone (numeric maps only). See Appendix A for a detailed explanation of the W-Card.

A user has determined that a display be produced of a specific area of interest within the study area. To obtain the sample map the following W-Card was submitted.

Col. 1	W	-	Input Card ID
Col. 3-5	1	-	Sector row that contains the upper left most cell of the window interest
Col. 6-8	1	-	Sector column
Col. 10-12	92	-	Element Row #
Col. 13-15	86	-	Element Column #
Col. 17-19	39	-	Number of rows to print starting at sector row 92
Col. 20-22	38	-	Number of columns to print starting at sector column 86
Col. 31		-	Suppresses asterisk

If the user wants to display the map in a gray tone see W-Card explanation in Appendix A (sample run, sample map, Exhibit A28).

Statistics cannot be generated for window area. This capability is for display only.

U.S. DEPARTMENT OF AGRICULTURE FORTRAN CODING	AUTHOR: <u> </u> TITLE: <u> </u> NUMBER: <u> </u> TO WHEN: <u> </u>	SYSTEM: <u> </u> PROGRAM: <u> </u> DATE: <u> </u>	PAGE: <u> </u> OF: <u> </u>
	SAMPLE RUN - WINDOW DISPLAY		
	10 WHEN: <u> </u>		
	11 <u> </u>		

SAMPLE RUN - WINDOW DISPLAY

[illegible]

Window Display

3-2 15 16 18 19 20 2 22 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63 64 65 66 67 68 69 70 71 72 73 74 75 76 77 78 79 80

SOILS

SCALE 1:31680

A - 2
B - 2B
C - 3
=

K - 1/8
L - 1/1
M - 1/2
=

Ditching
on
8 1/1

g + x
• (Simpson's method x)

Ditching method

10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63 64 65 66 67 68 69 70 71 72 73 74 75 76 77 78 79 80

Exhibit A28. --Window display
(Part 1 of 2)

e. Text Overlay

This routine provides the user with an option to annotate the map display. The text overlay procedure is generated through the use of the H-Card. See Appendix A for description and use of the R-Card (sample run, sample map, Exhibit A29).

[illegible]

12345678910111213141516171819202122232425262728293031323334353637383940414243444546474849505152535455565758596061626364656667686970717273747576777879808182838485868788899091929394959697989910010110210310410510610710810911011111211311411511611711811912012112212312412512612712812913013113213313413513613713813914014114214314414514614714814915015115215315415515615715815916016116216316416516616716816917017117217317417517617717817918018118218318418518618718818919019119219319419519619719819920020120220320420520620720820921021121221321421521621721821922022122222322422522622722822923023123223323423523623723823924024124224324424524624724824925025125225325425525625725825926026126226326426526626726826927027127227327427527627727827928028128228328428528628728828929029129229329429529629729829930030130230330430530630730830931031131231331431531631731831932032132232332432532632732832933033133233333433533633733833934034134234334434534634734834935035135235335435535635735835936036136236336436536636736836937037137237337437537637737837938038138238338438538638738838939039139239339439539639739839940040140240340440540640740840941041141241341441541641741841942042142242342442542642742842943043143243343443543643743843944044144244344444544644744844945045145245345445545645745845946046146246346446546646746846947047147247347447547647747847948048148248348448548648748848949049149249349449549649749849950050150250350450550650750850951051151251351451551651751851952052152252352452552652752852953053153253353453553653753853954054154254354454554654754854955055155255355455555655755855956056156256356456556656756856957057157257357457557657757857958058158258358458558658758858959059159259359459559659759859960060160260360460560660760860961061161261361461561661761861962062162262362462562662762862963063163263363463563663763863964064164264364464564664764864965065165265365465565665765865966066166266366466566666766866967067167267367467567667767867968068168268368468568668768868969069169269369469569669769869970070170270370470570670770870971071171271371471571671771871972072172272372472572672772872973073173273373473573673773873974074174274374474574674774874975075175275375475575675775875976076176276376476576676776876977077177277377477577677777877978078178278378478578678778878979079179279379479579679779879980080180280380480580680780880981081181281381481581681781881982082182282382482582682782882983083183283383483583683783883984084184284384484584684784884985085185285385485585685785885986086186286386486586686786886987087187287387487587687787887988088188288388488588688788888989089189289389489589689789889990090190290390490590690790890991091191291391491591691791891992092192292392492592692792892993093193293393493593693793893994094194294394494594694794894995095195295395495595695795895996096196296396496596696796896997097197297397497597697797897998098198298398498598698798898999099199299399499599699799899910001001100210031004100510061007100810091010101110121013101410151016101710181019102010211022102310241025102610271028102910301031103210331034103510361037103810391040104110421043104410451046104710481049105010511052105310541055105610571058105910601061106210631064106510661067106810691070107110721073107410751076107710781079108010811082108310841085108610871088108910901091109210931094109510961097109810991100110111021103110411051106110711081109111011111121131141151161171181191201211221231241251261271281291301311321331341351361371381391401411421431441451461471481491501511521531541551561571581591601611621631641651661671681691701711721731741751761771781791801811821831841851861871881891901911921931941951961971981992002012022032042052062072082092102112122132142152162172182192202212222232242252262272282292302312322332342352362372382392402412422432442452462472482492502512522532542552562572582592602612622632642652662672682692702712722732742752762772782792802812822832842852862872882892902912922932942952962972982993003013023033043053063073083093103113123133143153163173183193203213223233243253263273283293303313323333343353363373383393403413423433443453463473483493503513523533543553563573583593603613623

A-117

IV. COST ANALYSIS

The following representative costs and work units are based on the following: ASSUME 115200 ACRE STUDY AREA

2 Acre grid cell (.125" x .10")

240 rows x 240 columns (4 sectors)

(total cells 57600)

3 topics (POL, ELT, TM)

<u>PHASE</u>	<u>ITEM</u>	<u>COMPUTER COST MATERIALS</u>	<u>LABOR HOURS</u>
Determine Input Method	Decision to use Method I or II		.5
Define Study Area	Base Map - Determine scale, boundary area cell size and shape - Delineate boundary		8 1
Data Format	Determine Topics and Values		2 hours p/topic
Data Base Drafting	Obtain Supplies - Computer generated master grid - Coding grids (1 per topic) - Obtain ID Strips Develop master grid p/sector - Register grid p/topic - Delineate boundary p/topic - Assign row/column p/topic Prepare Code sheet for keypunching - Record values on coding form (POL 3, ELT 15) (TM 17) - Keypunching \$.10 p/card 240 cards p/sector p/topic	\$2 \$3 ea. \$24	.5 .25 1 .5 35 13
Initial Run Passive	Obtain copy of data input for edit p/sector p/topic	\$2	

<u>PHASE</u>	<u>ITEM</u>	<u>COMPUTER COST MATERIALS</u>	<u>LABOR HOURS</u>
Data Edit	Political topic p/sector		.25
	Ecological topic p/sector		1.75
	Timber p/sector		3.0
Data Correction	Keypunch \$.10 p/card		
Verification	To assure that all data is clean		
Run-Passive	Obtain output for each topic by sector	\$2.50 (4 sectors)	
Create			
Initial	Creates data file of topic		
File-Active	for manipulation and storage (3 topics p/sector)	\$2.50 (4 sectors)	
Verification	To assure that all data is topic		
File-Active	for manipulation and storage (3 topics p/sector)	\$2.50 (4 sectors)	
Data Map	Single topic p/sector	\$2	.25
Options	Intersection p/sector	\$2	.50
(batch mode)	Linear combination p/sector	\$4	.50
	Window display p/sector	\$1.75	.50
	Text overlay p/sector	\$2	1.00
(Demand Mode)	Single topic p/sector	\$6	.50
	Intersection	\$7	.50

NOTE: All costs are based on Batch Mode using "N" priority unless
noted otherwise.

Data Base	Storage and costs		
Storage	- Magnetic tape - p/tape p/month	\$1	
	Accessing		
	- Copy tape to disc "P" priority (avg)	\$3	.25
	- Receiving output	\$1	.25
	- Save tape	\$1	.25
	- Create tape "P" priority	\$3	.25

SECTION B

This section is a description of the RID*POLY program. It is being prepared separately and will be included in the RIDS User's Guide as Section B.

TABLE OF CONTENTS

SECTION C

I. Data Sources Acceptable to GRID	Page
A. General Information	C-1
B. Digitized Features	C-3
C. Attributes	C-4
II. Structure of GRID standard files	C-5
III. Processing "COMLUP-FORMATTED" data	C-7
A. Runstream for Tape Input	C-7
B. Runstream for Card Image Input	C-8
C. Error Messages	C-9
D. GRID Runstream	C-9

SECTION C
HANDLING DIGITIZED DATA

I. Data Sources Acceptable to RID*GRID

A. General Information

1. Sources

RID*GRID is capable of interfacing with the following sources of digitized data:

<u>File Class</u>	<u>Reference</u>
(1) GIRAS (Formerly LUDA)	See Appendix "A"
(2) DIMECO (Census County Outline File)	See Appendix "A"
(3) F-Cards	See Appendix "A"
(4) COMLUP Formatted Data	See following page
(5) POLY Formatted Data	See Section
(6) DMA Terrain Data Tapes	See Section
(7) Other files, if correctly preprocessed	See Appendix "A"

Files in Class 1, 2, 4, 5, and 6 are preprocessed, off-line, into what is called "GRID-Standard-Format." The preprocessed data can then be mapped using GRID control statements. Data presented on F-Cards are processed immediately within GRID.

Data in other forms may be handled with a minimum of program effort necessary to produce GRID-formatted files. A skeleton program is provided in the Reference.

The eventual coordinate system used for all GRID data is geographic (latitude, longitude); all coordinates must be

coordinates
transformed into geographic before mapping in the GRID System is possible. DIMECO and F-Card coordinates are already geographic, and the GIRAS, COMLUP, and POLY preprocessors perform the transformation for those files.

B. Digitized Features

RID accepts three types of digitized features:

1. Closed polygonal - e.g., physical land or surface features, census tracts, county boundaries.
2. Open polygonal (arcs) - Features which, at the scale of the source map, are one-dimensional, such as roads and stream beds.
3. Point or incidence data, e.g., population centroids, disease occurrences, etc.

C. Attributes

Quantitative data associated with polygons, arcs, or points are known as attributes. Unless only the boundary or extent of a digitized feature is of interest, these are what are to be mapped in GRID. All attribute values are stored as real ('floating point') numbers. Examples of attributes are population of census areas, average annual rainfall for a Region, vehicular density along traffic corridors, etc.

In case it is required that several attributes of a digitized area are to be mapped, GRID provides a convenient means to do so. A 'master map' is initially created from the polygonal data. Thereafter, all attributes may be mapped by association with the

cross-reference symbols of the 'master map.' A good example would be census information. A new 'master map' must be created each time a new scale is desired.

II. Structure of GRID-Standard-Files

There is one record for each feature. A record consists of a prefix followed by coordinates and attributes, and contains these data items:

1. 'Master Map' symbol. There is a one-to-one correspondence between these and each unique feature.
2. Feature Type.
 - 1 = Polygon
 - 2 = Arc
 - 3 = Point
3. Number of vertices, N. (polygons and arcs)
- 4,5. Interior point coordinates (geographic; polygons only)
- 6,7,8,9. Min longitude, Min latitude, Max longitude, Max latitude (polygons only)

The above nine items constitute the prefix.

10. Vertex coordinates (geographic)

- 1, for a Point.
- N, for an Arc.
- N+1, for a Polygon where $\text{vertex}_{N+1} = \text{vertex}_1$
Vertices are ordered either
clockwise around the bound

11. Zero or more attribute values.

The number and order of these attributes be represented exactly on the E-Card symbols. If no attribute values exist in the file, created, and no E-Cards are necessary;

a 'real-valued' map is to be created, these values must be scaled or otherwise transformed via J-Cards or auto-scaling on the Q-Card in order to produce a cellular map for display. A given 'real-valued' map may be transformed into any other type via R-Cards.

III. Processing "COMLUP-Formatted" Data

As was mentioned before, COMLUP project data tapes must be pre-processed by an off-line program before they may be used as input to GRID. (In addition, the data must be closure-edited by the COMLUP system). Fiducial or registration points are input in a way similar to that described in the previous section. Also, the user may elect to process only a subset of the features in the file, based on their attribute values, by either excepting a few values from the whole or by explicitly listing those values he wishes to include. Attribute selection is done via:

```
NAMelist/ATSLCT/ATTRIB
```

where ATTRIB is an array which will list either the attributes to be included or those to be rejected.

The COMLUP Preprocessor can accept data either from closure-edited COMLUP tapes or from SDF card-image files created from those tapes. The EXEC-8 runstreams for the two types of input are slightly different. Often data is digitized from several separate map sheets. A set of fiducial coordinates is required for each sheet.

A. Runstream for Tape Input

```
@ASG,T A$A.,F///n          Temporary
@ASG,A RID*GRID             GRID Program File
@ASG,THEIJ A,16,ree11/.../ree1N Edited tapes (one per sheet)
@ASG,T B,U9V                Preprocessed file (save reel)
@XQT,OU RID*GRID.PREPRC/COMLUP
$ATSLCT ATTRIB = -1, -3, -7, 97*0
$END
$FIDUC                      Fiducials for 1st map sheet
$END
$FIDUC                      Fiducials for Nth map sheet
$END
```

In the example the user is excluding attributes 1, 3, and 7 from processing.

B. Runstream for Card-Image Input

```
@ASG,T A$A.,F///n
@ASG,A RID*GRID
@ASG,A Sheet 1           File containing arcs of maps
      ⋮
      ⋮
@ASG,A Sheet N           File containing arcs of maps
@ASG,T B,U9V,reel #      Preprocessed file
@XQT,OU RID*GRID.PREPRC/COMLUP
$ATSLCT
$END
$FIDUC                   Fiducials for Sheet 1
$END
@ADD,E Sheet 1
$FIDUC                   Fiducials for Sheet N
$END
@ADD,E SheetN
```

In this example, the user admits all attribute values for processing. NOTE: The preprocessed output file, Unit B, may be assigned to mass storage rather than tape. GRID will accept either.

Presently, the identical point tolerance for COMLUP data is set at .067". The user may alter this by specifying a value for TO in the NAMELIST, FIDUC.

C. Error Messages

'ARCS MISSING FROM POLYGON, XXXX, REEL X'

The identified polygon cannot be chained. Lowering the equal point tolerance from the default value may help.

'DANGLING ARC'

An arc whose overall length is less than the equal point tolerance has been discovered and is not necessary to close the polygon.

'INVALID ENTRIES FOR ORIENTATION VECTORS'

See Appendix "A" D-Card External Data File

'MISSING OR INVALID FIDUCIAL COORDINATES'

Three pairs of coordinates must be present. Digitized coordinates must not be negative.

D. GRID Runstream

In order to identify the COMLUP project tape, the preprocessor affixes the project number in the header of the standardized file. This project number must be referenced on the D-card's external file name field. There is only one attribute on a COMLUP file (e.g., forest-type), and so only one is mentioned on the E-Card. The clipping coordinates entered on the D-Card may be more restrictive than either the source map boundary or the coordinates defined by the G-Card sectors.

EXTERNAL FILE NAME (OR FMPS MODEL NAME)		FILE TYPE UNIT	DICTIONARY ON MASTER MAP NAME		CLIPPING COORDINATES									
01	09250	4 5	31		34	37	38	39	40	41	42	43	44	
					GRID CODE		NORTH ASSECTOR		SOUTH ASSECTOR		WEST ASSECTOR		EAST ASSECTOR	
COORDINATE SYSTEM {					SECTOR	NORTH LATITUDE		SOUTH LATITUDE		WEST LONGITUDE		EAST LONGITUDE		
					GEOGRAPHIC	45	46	47	48	49	50	51	52	
					UTM	53	54	55	56	57	58	59	60	
					MIN EASTING ZONE		MAX EASTING ZONE		MIN NORTHING		MAX NORTHING			

1	FIELD LABEL	FORMAT	38	FIELD LABEL	FORMAT	48	FIELD LABEL	FORMAT
6	TIMBER-TYPE							

GRID CODE LEVEL LPI		MAP NAME	REDUCTION RULE SIZE	SECTOR	ELEMENT	SECTOR	ELEMENT	SECTOR	ELEMENT
4	09250	09250	22	27	28	29	30	31	32
				ND	ROW	ND	ROW	ND	ROW
				COL	COL	COL	COL	COL	COL
				2	3	4	5	6	7

REFERENCE FIELD		RADIUS		ACCEPT LABEL		ACCEPT VALUE	
3	TIMBER-TYPE	11	12	36	37	38	39

1 = DIGITIZER 2 = INTERNAL COMPOSITION RULE 3 = LP MODEL 4 = NO SCALING REQUIRED 5 = MASK SYMBOL 6 = AUTO SCALING 7 = NO OF INTERVALS 8 = RELATION

The COMLUP preprocessor prints a list of 3-character master map cross-reference symbols. A master map may be created from the preprocessed file; no reference field is necessary on the Q-C in this case. The user may subsequently use the master map to create new maps from other data.

SECTION D
PROCESSING POLYGON DIGITIZED DATA
IN GRID SYSTEM

I. General Information	Page D-3
A. Overview	D-3
B. Operating Procedure	D-4
1. Digitize Polygons	D-5
2. Transmit Data to FCCC	D-5
3. Execute RIDS*PLOTS.EDIT	D-6
4. Execute RIDS*PLOTS.PLOT	D-8
5. Save Output File	D-8
6. Execute RID*GRID.PREPRC/PLOT	D-10
a. Step 1 - Create Runstream	D-10
b. Step 2 - Start Runstream	D-11
7. Execute RID*GRID.GRID (Passive Mode)	D-11
a. Step 1 - Create Runstream	D-11
b. Step 2 - Start Runstream	D-14
8. Execute RID*GRID.GRID (Active Mode)	D-14
9. Data Manipulation	D-14
II. Cost Analysis	D-16

EXHIBIT

DESCRIPTION

D1	Runstream - Transmit Data to FCCC (Sample Output)
D2	Runstream - RID*PLOT.PLOT (Sample Output)
D3	Runstream - RID*GRID. PREPRC/PLOT (Sample Output)
D4	Runstream - RID*GRID.GRID (Coding Form)
D5	Runstream - RID*GRID.GRID (Sample Output)

SECTION D

Processing Polygon Digitized Through the RID*GRID System

I. GENERAL INFORMATION

The RID System is able to accept polygon digitized data for input through the PLOT program or converted for use with the grid system.

A. Overview

The polygons are digitized for input to the PLOT program, RIDS*PLOTS. The data is then edited using the edit routine RIDS*PLOTS.EDIT, to insure that all polygons are closed. Then a verification plot is obtained using the RIDS*PLOTS.PLOT routine. The plotted output represents the polygons as they were digitized. If errors are encountered in the EDIT or PLOT outputs and changes are to be made to the data file the UNIVAC EXEC 8 editor is used to accomplish this task. When you are satisfied with the data file it is then saved. At this point you convert the data to grid for processing through the grid system.

To process through the grid system you must input your clean polygon data file through a conversion program called RID*GRID.PREPRC/PLOT. This program will convert polygon data to a grid file for input to the RIDS grid system. The next step is then to input the converted file into the grid system, RID*GRID.GRID for file creation, manipulation and output. The procedures for executing this task are discussed in Section A.

B. Operating Procedure

The following procedure is recommended for processing the pol digitized data, converting to grid, manipulation and obtaining grid outputs with statistical data.

When digitizing it is important to remember that the digitized data must be recorded in PLOT digitized format.

1. Digitize Polygons

CARD FORMAT 1: File Header Record

<u>COLUMN</u>	<u>FORMAT</u>	<u>DESCRIPTION</u>
1 - 2	12	Forest number
3 - 6	14	Compartment number
7 - 8	12	Layer number
9 - 15	F7.3	Acreage factor. This number is used to convert the computed area of each polygon to acres.
16 - 80		Not used

CARD FORMAT 2: Polygon Header Record

<u>COLUMN</u>	<u>FORMAT</u>	<u>DESCRIPTION</u>
1 - 6	6A1	Polygon label
7 - 12		Not used
13 - 18	I6	X-coordinate of interior point
19 - 24	I6	Y-coordinate of interior point
25 - 30	I6	X-coordinate of a vertex of the polygon
31 - 36	I6	Y-coordinate of a vertex of the polygon
The X and Y coordinate of each unit are assumed to be in hundredths of an inch for all computation and plotting.		
37 - 42	I6	X2
43 - 48	I6	Y2
49 - 54	I6	X3
55 - 60	I6	Y3
61 - 66	I6	X4
67 - 72	I6	Y4
73 - 80		Not used

CARD FORMAT 3: Pol

<u>COLUMN</u>	<u>FORMAT</u>	<u>DESCRIPTION</u>
1 - 6	I6	X1
7 - 12	I6	Y1
13 - 18	I6	X2
19 - 24	I6	Y2
25 - 30	I6	X3
31 - 36	I6	Y3
37 - 42	I6	X4
43 - 48	I6	Y4
49 - 54	I6	X5
55 - 60	I6	Y5
61 - 66	I6	X6
67 - 72	I6	Y6
73 - 80		Not used

2. Transmit Data Tape to FCCC

SAMPLE RUNSTREAM

```

@RUN
@ASG,CP GM*DIGIT.
@DATA,IL GM*DIGIT.
//JOB TPLN
* TAPE TO LINE
//UTL TC,FF,A=(80,80), B=(80,80), KY,IR,LN
//ASSIGN I=(11),0=(20)
//EXEC
//END
  
```

Exec 8 command

Data 100 command

SAMPLE OUTPUT

(SEE EXHIBIT D1)

- Execute RIDS*PLOTS.EDIT to insure that all polygon are closed.

SAMPLE RUNSTREAM

```

@RUN
@ASG,A RIDS*PLOTS.
@ASG,A GM*DIGIT.
@USE 8,GM*DIGIT.
@ASG,CP GM*DIGITED.
@USE 9,GM*DIGITED.
@XQT RIDS*PLOTS.EDIT
  
```

USER NAMED

```

***PLOT EDITOR PROGRAM
FORINT 12 COMPARTMENT 1000 LAYER 1 ACRE FACTOR 100.000
  ID LABEL Pts ACRES
  1 1 33 2191.051 5763 537 12152 5737 12
  2 2 11 2035.045 5325 4917 11550 3512 31
  3 3 25 5233.273 5592 5550 12343 13341 22
  4 4 30 2353.401 3349 3992 15154 14520 125
  5 5 50 1740.743 11205 4701 15054 0550 133
  6 6 62 3732.474 11540 -154 21095 5453 123
  7 7 104 1050.355 13332 2051 10201 4324 150
  8 8 30 044.124 13491 3175 13410 5300 15
  9 9 17 1243.133 13030 4315 17044 0403 12
  10 10 53 1491.752 14905 5073 18551 10311 12
  ***** EXIT
  
```

Pts in Bdry	Area of Polygon	MAX X	MIN X	MAX Y	MIN Y
----------------	--------------------	-------	-------	-------	-------

[illegible]

D-

- a. Minor corrections are done with the UNIVAC editor.
 - b. Major corrections must be redigitized and reprocessed through the EDIT Program. See Appendix C for additional information.
4. Execute RID*PLOT.PLOT to obtain verification plot.

SAMPLE RUNSTREAM

```
@RUN
@ASG,A RIDS*PLOTS.
@ASG,A GM*DIGITED. } USER NAMED FILES
@USE 10,GM*DIGITED.
@XQT RIDS*PLOTS.PLOT
```

PLOT PLOTTING PROGRAM

```
ENTER MINIMUM SIZE POLYGON TO BE PLOTTED...USE DECIMAL
.05
ENTER SIZE CHARACTERS DESIRED IN INCHES FOR POLYGON LABELS
ON PLOT...USE DECIMAL
.1
ENTER NUMBER OF LAYERS TO BE PLOTTED
1
ENTER PLOT IDENTIFICATION-36 CHARACTERS-MAX
SAMPLE PLOT GRN MTN TEST
ENTER PLOT MAILING OR HANDLING INSTRUCTIONS
>ROGER PELLETIER WO
DO YOU WANT TO SCALE YOUR PLOT?
>NO
LIST OF DELETED POLYGONS
IDS LABELS
ENTER NUMBER OF PENS
>1
ENTER COLOR OF INK
>BLACK
ENTER TYPE OF PAPER
>GRAPH
ENTER SITE ID TO WHICH YOU WISH TO SYM PLOT FILE
>FCR033 (YOUR SITE ID)
PLOT FILE WILL BE SYMED TO SITE FCR033 (YOUR SITE ID)
* * END OF PLOT PROGRAM * *
>@FIN
```

(See Exhibit D2 for Sample Plot Output)

5. Save output file from RIDS*PLOTS.EDIT This is a clean copy of your raw data.

PLOT

FOREST12
COMPT 1000
LAYERS 1



= 160.00 ACRES

SAMPLE PLOT GREEN MTN TEST




Exhibit D2.--RID*PLOT.PLOT - sample output

6. Execute RID*GRID.PREPRC/PLOT, this program converts the polygon plot file to a grid file for input to the grid system, RID*GRID.

a. Step 1, in Demand Mode--Create a runstream with the necessary commands to convert the PLOT file.


STEP 1 - CREATE THE RUNSTREAM

PREPRC/PLOT

```

@RUN (YOUR RUN CARD)
@ASG,CP ROGER*P. (ASSIGN A FILE NAME TO THE RUNSTREAM YOU ARE ABOUT TO GENERATE).
@ED,I ROGER*P. (FILE NAME ASSIGNED ABOVE)
o
o
o
INPUT (CARRIAGE RETURN)
EDIT
0: I @RUN,L XXXXXX,111111111,AAA,1,50 (YOUR RUN-CARD).
1: I @SYM,U PRINT$,,UCR281 (YOUR SITE-ID).
2: I @ASG,A RID*GRID.
3: I @ASG,A RHP*DIGITED. (YOUR INPUT FILENAME).
4: I @ASG,A RHP*DIGRID. (YOUR OUTPUT FILENAME).
5: I @USE B.,RHP*DIGRID.
6: I @XQT RID*GRID.PREPRC/PLOT
7: I $ATSLCT
8: I $END
9: I $FIDUC
10: I $FIDUC
11: I LNG1=73.00,LAT1=43.25,
12: I LNG2=73.00,LAT2=43.50,
13: I LNG3=72.75,LAT3=43.25,
14: I IX1=0,IY1=0, IX2=403,IY2=34557,
15: I IX3=25185,IY3=0,
16: I $END
17: I @ADD,EP RHP*DIGITED.
18: I @FIN
19: EXIT
@FIN

```



b. @START your runstream.

STEP 2 - SUBMIT THE RUN FOR BATCH PROCESSING

```
@RUN (YOUR RUN CARD)
@ASG,A ROGER*P. (ASSIGN THE NAME OF THE RUNSTREAM YOU GENERATED
                 IN STEP 1)
@START ROGER*P. (FILE NAME ASSIGNED ABOVE)
@FIN
(SEE EXHIBIT D3 SAMPLE OUTPUT)
```

7. Execute RID*GRID.GRID in a passive mode to obtain verification grid conversion output (Batch Mode).

Step 1 -- Create a runstream with the necessary commands to execute RID*GRID.GRID.

STEP 1 - CREATE THE RUNSTREAM

```
@RUN (YOUR RUN CARD)
@ASG,CP (ASSIGN A FILE NAME TO THE RUNSTREAM YOU ARE ABOUT TO
        GENERATE)
@ED,I (FILE NAME ASSIGNED ABOVE)
.
.
.
INPUT (CARRIAGE RETURN)
EDIT
0: I @RUN (TYPE IN RUN CARD FOR YOUR BATCH RUNSTREAM)
1: I @SYM PRINT$,, (YOUR SITE ID)
2: I @ASG,A RID*GRID.
3: I @ASG,A (RID STANDARD OUTPUT FILE CREATED WITH PREPRC/PLOT)
4: I @USE B., (RID STANDARD OUTPUT FILE)
5: I @ASG,T.,U9V (ASSIGN A TEMPORARY OUTPUT FILE } ACTIVE MODE
6: I @USE 9., (OUTPUT FILE ASSIGNED ABOVE) } TO CREATE MAP FILE
7: I @XQT,S RID*GRID.GRID
8: I *
9: I A
10: I D
11: I E
12: I G
13: I Q
14: I T
15: I Z
16: I *
17: I @FIN
18: EXIT
@FIN
```

(See Exhibit D4, Sample Data Entry on coding form)

(See Appendix "A" for description of input form)

```

@XQT,OUT
$FIDUC
MINLAT = .43250000E+02
MAXLAT = .43500000E+02
MINLON = .72750000E+02
MAXLON = .73000000E+02
LNG1 = .73000000E+02
LAT1 = .43250000E+02
LNG2 = .73000000E+02
LAT2 = .43500000E+02
LNG3 = .72750000E+02
LAT3 = .43250000E+02
IX1 = +0
IY1 = +0
IX2 = +403
IY2 = +34557
IX3 = +25185
IY3 = +0
ORNTX = +0, +0
ORNTY = +0, +0
TOLER = .67000000E-01

```

\$END

POLYGON LABEL:	8 8	POLYGON HEADER:	H--	1	88	
72.8425	43.2829	72.8178	43.2741		72.8666	43.2891
POLYGON LABEL:	7 7	POLYGON HEADER:	G--	1	103	
72.8474	43.2758	72.8030	43.2660		72.8680	43.2821
POLYGON LABEL:	9 9	POLYGON HEADER:	I--	1	86	
72.8477	43.2951	72.8318	43.2860		72.8617	43.3191
POLYGON LABEL:	10 10	POLYGON HEADER:	J--	1	62	
72.8278	43.3040	72.8160	43.2880		72.8518	43.3261
POLYGON LABEL:	5 5	POLYGON HEADER:	E--	1	39	
72.8663	43.3059	72.8515	43.2856		72.8885	43.3201
POLYGON LABEL:	2 2	POLYGON HEADER:	B--	1	80	
72.9133	43.2998	72.8862	43.2854		72.9378	43.3131

POLYGON LABEL:	1 1	POLYGON HEADER:	A--	1	82	
72.9083	43.2754	72.8809	43.2552		72.9329	43.2921
POLYGON LABEL:	4 4	POLYGON HEADER:	D--	1	79	
72.8766	43.3403	72.8412	43.3151		72.9132	43.3571
POLYGON LABEL:	6 6	POLYGON HEADER:	F--	1	161	
72.8709	43.2679	72.7913	43.2498		72.8855	43.2911
POLYGON LABEL:	3 3	POLYGON HEADER:	C--	1	94	
72.9126	43.3284	72.8660	43.2908		72.9451	43.3511
TOTAL NUMBER OF POLYGONS PROCESSED:				10		

@FIN

Exhibit D3.--RID*GRID.PREPRC/PLOT - sample output

b. @START your runstream.

STEP 2 - SUBMIT THE RUN FOR BATCH PROCESSING

1. @RUN (YOUR RUN CARD)
2. @ASG,A (ASSIGN THE NAME OF THE RUNSTREAM YOU GENERATED IN STEP
3. @START (FILE NAME ASSIGNED ABOVE)
4. @FIN

(See Exhibit D5 Sample Output)

8. Execute 7 above again only this time in an active mode to create a grid map file.
9. Data Manipulation is the same as RID*GRID. See Section A for data manipulation procedures once file is created.

Exhibit D5.--RID*GRID.GRID - sample output

II. COST ANALYSIS

The following representative costs and work units are based on the following:

Study Area equal to a 7 1/2 minute USGS quadrangle at a scale of 1:24,000

Layers - Political (14 polygons)
Ecological Land Types (145 polygons)
Timber (297 polygons)

Work Unit Costs - GS-5 Step 1 = \$5.05 p/hr.

A. Digitizing --	<u>Layer</u>	<u>Work Unit</u>	<u>Cost</u>
	Political	1.05 hrs	\$ 5.30
	Ecological	4.08 hrs	20.60
	Timber	4.30 hrs	21.72
	TOTALS	9.43 hrs	\$47.62

B. Input and Editing -- (See paragraph D, Section B for detailed cost analysis.) Includes transmitting data to FCCC, executing .EDIT and .PLOT programs and use of the UNIVAC Exec-8 editor in Demand Mode.

Costs

<u>Layer</u>	<u>Work Unit</u>	<u>Computer</u>
Political	2.08 hrs \$10.50	\$ 10.56
Ecological	2.45 hrs 12.37	83.65
Timber	5.14 hrs 25.96	157.60
TOTALS	9.67 hrs \$48.83	\$252.01 (De

C. Execute RID*GRID.PREPRC/PLOT to convert polygon data.

Cost approximately \$.02 p/polygon, "N" priority, batch mode.

Political	\$.28
Ecological	2.90
Timber	5.94
TOTAL	\$9.12

D. Execute RID*GRID.GRID (Passive Mode).

1 Sector 3 Topics \$.60

E. Execute RID*GRID.GRID (Active Mode).

1 Sector 3 Topics \$.60

Note the following is a comparison summary cost between the two methods of inputting data to the GRID System.

INPUT COST ANALYSIS

HAND CODING METHOD

Hand Coding "Work Unit" Cost	\$ 177.55
Keypunching and Verification (930 Cards)	93.00
Input and Editing "Work Unit" Cost	47.07
Input and Editing "Computer" Cost	<u>24.20</u> (N-Priority)
TOTAL	\$ 341.82

$\$341.82 / 3 \text{ Layers} = 113.94$ or $\$114.00$ per layer

DIGITIZER METHOD

Digitizing "Work Unit" Cost	\$ 47.62
Input and Editing "Work Unit" Cost	48.83
Input and Editing "Computer" Cost	<u>252.01</u> (Demand)
TOTAL	\$348.46

$348.46 / 3 \text{ layers} = \116.15 or $\$116.00$ per layer

SECTION E
SLOPE AND ASPECT MAPS

	PAGE
I. OVERVIEW	E-1
II. DESCRIPTION	E-4
1. Note	E-4
2. DMA Data Tapes	E-4
3. Execute .COPYNCIC	E-4
4. Save Output	E-4
5. Execute .PRINT	E-9
6. Execute .SCANDMA	E-12
7. Execute .SLOPE	E-15
8. Execute .ZONEIT	E-16
9. Execute Conversion Program RID*GRID.GELCOM	E-23
10. Execute Preprocessor RID*GRID.PREPRC/COMLUP	E-23
11. Sample Outputs of Map File Through RID*GRID.GRID Program	E-28
III. Cost Analysis	E-37

EXHIBIT	DESCRIPTION	P
E1	Topographic Analysis System (TOPAS)	E
E2	DMA Tapes Selection Program (2 Parts)	E
E3	.PRINT Output (2 Parts)	E
E4	.SCANDMA Output (2 Parts)	E
E5	.SLOPE Output (2 Parts)	E
E6	.ZONEIT Output (3 Parts)	I
E7	RID*GRID.GELCOM Output (2 Parts)	I
E8	RID*GRID.PREPRC/COMLUP Output (2 Parts)	.
E9	Sample Input to Obtain Output Display and Create Map File (2 Parts)	
E10	Sample Input to Obtain Single Topic Display (Demand Mode) - Passive Run	
E11	Sample Input to Obtain Grey Scale Display (3 Parts)	
E12	Topographic Map of .GRID Output	

SECTION E

CREATION OF SLOPE AND ASPECT ZONE MAPS

I. OVERVIEW

An interface is available so that slope and aspect zone maps produced by the Forest Service Topographic Analysis System (TOPAS) can be entered into the Resource Information Display System (RID*GRID). Once in GRID, all of the capabilities of the GRID system can be used; such as combining with other maps, acreage and statistics, display options, etc.

Accuracy of slopes and aspect are limited by the 1:250,000 scale of the original maps. If every elevation point is utilized the map area is equivalent to a 3.75 x 3.75 minute quad. Limitations in the TOPAS system also affect accuracy. If 7 1/2' quads are used, every second elevation point is utilized; if 15' quads are used, every fourth elevation point can be used and for 30' quads, every sixteenth elevation point. Therefore, original inaccuracies from working with a very small scale map are compounded if the user desires outputs larger than 7 1/2' quads. As outputs in GRID can be displayed at any size, the user should be cautious in still related to the original 1:250,000 that TOPAS is not sufficiently accurate.

Most operations are more fully explained in the TOPAS Users Guides. Only references are given here in describing the sequence of operations. It is assumed that users are familiar with

EXHIBIT	DESCRIPTION	PAGE
E1	Topographic Analysis System (TOPAS)	E-5
E2	DMA Tapes Selection Program (2 Parts)	E-6
E3	.PRINT Output (2 Parts)	E-1
E4	.SCANDMA Output (2 Parts)	E-
E5	.SLOPE Output (2 Parts)	E-
E6	.ZONEIT Output (3 Parts)	E-
E7	RID*GRID.GELCOM Output (2 Parts)	E-
E8	RID*GRID.PREPRC/COMLUP Output (2 Parts)	E-
E9	Sample Input to Obtain Output Display and Create Map File (2 Parts)	E-
E10	Sample Input to Obtain Single Topic Display (Demand Mode) - Passive Run	E
E11	Sample Input to Obtain Grey Scale Display (3 Parts)	E
E12	Topographic Map of .GRID Output	E

SECTION E

CREATION OF SLOPE AND ASPECT ZONE MAPS

I. OVERVIEW

An interface is available so that slope and aspect zone maps produced by the Forest Service Topographic Analysis System (TOPAS) can be entered into the Resource Information Display System (RID*GRID). Once in GRID, all of the capabilities of the GRID system can be used; such as combining with other maps, acreage and statistics, display options, etc.

Accuracy of slopes and aspect are limited by the 1:250,000 scale of the original maps. If every elevation point is utilized the map area is equivalent to a 3.75 x 3.75 minute quad. Limitations in the TOPAS system also affect accuracy. If 7 1/2' quads are used, every second elevation point is utilized; if 15' quads are used, every fourth elevation point can be used and for 30' quads, every sixteenth elevation point. Therefore, original inaccuracies from working with a very small scale map are compounded if the user desires outputs larger than 7 1/2' quads. As outputs in GRID can be displayed at any size, the user should be cautious in realizing that accuracy is still related to the original 1:250,000 scale. Many users have found that TOPAS is not sufficiently accurate to meet their needs.

Most operations are more fully explained in either the RIDS or the TOPAS Users Guides. Only references to these documents will be used here in describing the sequence of operations. This brief description assumes that users are familiar with both RIDS and TOPAS processes.

II. DESCRIPTION

1. NOTE: Only slope zone and aspect products of ZONIT are suitable for input to the GRID system (See Exhibit E1).
2. Procurement of DMA data tapes is covered in Chapter II of the TOPAS Users Guide. Notice if additional tapes are purchased, be sure they are 9-track, 1600 BPI. A DMA tapes selector program called PELLE*DMASORT.LIST can be utilized to determine if an individual tape is available from the DMA Tapes Data File. See Exhibit E2 for instructions to execute this program.
3. Process each tape file through COPYNCIC. Obtain instructions for doing this by the following computer commands (either demand or batch):

```
@ADD TOPAS*PGM.COPYNCIC/DOCIN
```

```
@EOF
```

4. After processing through COPYNCIC, save the tape and send the required documentation to WO Geometronics, for updating the library of DMA tapes.

NOTE: COPYNCIC should be run on P priority with allowance of 10 minutes CPU time. Cost at this priority will be about \$40.0 for each execution.

TOPOGRAPHIC ANALYSIS SYSTEM (TOPAS)




Exhibit E1.--Topographic analysis system (TOPAS)

A procedure has been developed to allow users to select individual sheet listings from the DMA Tapes Data File. The procedure has been designed to function primarily in the interactive mode; it may be activated by using identical control statements in the batch environment.

INVOKING THE PROCEDURE

The basic format of control statements to generate a listing is as follows:

```
@RUN RUNID, ACCT NO, PROJ  
@TTY W,132 or @TTY W,80
```

For demand terminal operation:
only. This allows data to be
printed out on a single line.

```
@ ASG, A PELLE*DMASORT.  
@ ASG, A RIDS*DMATAPES.  
@ USE 10, RIDS*DMATAPES.  
@ XQT PELLE*DMASORT.LIST
```

At this point terminal will print out ENTER 0 FOR COMPLETE LISTING
OR 1 FOR SPECIFIC SHEET

User will enter 0 or 1 on terminal
If 0 is selected entire DMATAPES data will be printed

If 1 is selected terminal will print out

ENTER SHEET NAME

User will enter sheet name.

Terminal will then write out

ENTER SHEET HALF

User will enter sheet half.

Then the program will search and print out the data pertaining to the selected sheet. If selected sheet is not on file, terminal will print out SHEET NOT FOUND and ENTER SHEET NAME.

@ FIN to terminate program.

@@ TERM to terminate terminal operation.

*Exhibit E2.--DMA tapes selection program
(Part 1 of 2)*

For Batch Runs use the following:

For complete listing

```
@ RUN
@ ASG, A PELLE*DMASORT.
@ ASG, A RIDS*DMATAPES.
@ USE 10, RIDS*DMATAPES.
@ XQT PELLE*DMASORT.LIST
0 Zero in Card Column 1 will give a complete listing
@ FIN
```

For search of 1 DMA Tape

```
@ RUN
@ ASG, A PELLE*DMASORT.
@ ASG, A RIDS*DMATAPES.
@ USE 10, RIDS*DMATAPES.
@ XQT PELLE*DMASORT.LIST
```

1 in Card Column 1 will give you a search for specific tape.
LOVELOCK Sheet name of tape wanted start in Card Column 1.
EAST Sheet half of tape wanted start in Card Column 1.
@ FIN

Be sure to spell the sheet name exactly as they are on the sheet index.

There will be approximately 100 pages in a complete listing.

*Exhibit E2.--DMA tapes selection program
(Part 1 of 2 continued)*

SAMPLE RUNSTREAM DMA TAPE SEARCH

UNIVAC 1100 OPERATING SYSTEM VER. 32-R2-0E (RSJ)
%@RUN W51F61, [REDACTED], ROGER
DATE: 081778 TIME: 051706
The subject file, BROADCASTS, has been updated as of 08/15/78 08:17:37
%@TTY W,132
-@@COMPLETE
@ASG,A PELLE*DMASORT.
READY
%@ASG,A RIDS*DMATAFES.
READY
%@USE 10, RINS*DMATAFES
READY
%@XQT PELLE*DMASORT.LIST
ENTER 0 FOR COMPLETE LISTING OR 1 FOR SPECIFIC SHEET
%J
ENTER SHEET NAME
GLEN FALLS
ENTER SHEET HALF
EAST

250 SHEET	DMA SHEET HALF	USER TAPE	STATE SW CORNER	TAPE LABEL
NAME	NUMBER	NUMBER		
GLEN FALLS	NK-18-03	EAST F02975	VT 43	73 0FDM*N1H02
98	18	1384	26	98 1759 1361 1778 43 73
SWX	SWY	SEX	SEY	NWX NWY NEX NEY LAT LONG

ENTER SHEET NAME
%@FIN

E2.--DMA tapes selection program - sample runstream
(Part 2 of 2)

5. Data obtained from printfile in running COPYNCIC, or PELLE*DMASORT.LIST (Exhibit E2-2) is utilized to execute the program PRINT (Page 33 of TOPAS Manual). This program provides the x and y coordinates in hundredths of inches for the corners of each 7 1/2', 15' and 30' quad. DO NOT use these coordinates as the x and y coordinates in the GRID preprocessor (Exhibits E3, SAMPLE PRINT OUTPUT).

DATA 1 CARD

PURPOSE: Identifies DMA Sheet information and Forest Service tape number that will be incorporated in page header.

FORMAT:	cc	use	format
	1-30	Name of DMA 1:250,000 Sheet	(5A6)
	31-42	DMA Sheet number	(2A6)
	43-50	(Blank)	
	51-62	DMA Sheet Half (East or West)	(2A6)
	63-68	(Blank)	
	69-80	USFS Tape number	(2A6)

ALL VALUES ARE LEFT JUSTIFIED

DATA 2 CARD

PURPOSE: This card is used to input the machine x and y limits for the DMA Sheet Half involved. The SW latitude and longitude are also put on this card to be placed in the page header with the DMA Sheet information.

FORMAT:	cc	use	format
	1-5	DMA SW X	(I5)
	6-10	DMA SW Y	(I5)
	11-15	DMA SE X	(I5)
	16-20	DMA SE Y	(I5)
	21-25	DMA NW X	(I5)
	26-30	DMA NW Y	(I5)
	31-35	DMA NE X	(I5)
	36-40	DMA NE Y	(I5)
	41-45	SW Latitude of Sheet Half	(I5)
	46-50	SW Longitude of Sheet Half	(I5)

ALL VALUES ARE RIGHT JUSTIFIED

GLEN FALLS

EAST

THE AMS 1/2507000 SHEET NK-18-03 IS ON TAPE F02975
THE S.M. COORDINATES FOR THIS HALF ARE LATITUDE = 43-00 AND LONGITUDE = 73-00.

YXSW = 98 YYSW = 18

+X=	0	+X=	157	+X=	315	+X=	473	+X=	631	+X=	789	+X=	947	+X=	1105	+X=	1263
Y=	1741	Y=	1742	Y=	1743	Y=	1744	Y=	1746	Y=	1749	Y=	1753	Y=	1756	Y=	1760

+X=	0	+X=	157	+X=	315	+X=	474	+X=	632	+X=	790	+X=	949	+X=	1107	+X=	1265
Y=	1523	Y=	1524	Y=	1525	Y=	1526	Y=	1528	Y=	1530	Y=	1534	Y=	1537	Y=	1541

+X=	0	+X=	157	+X=	316	+X=	475	+X=	634	+X=	792	+X=	951	+X=	1110	+X=	1268
Y=	1305	Y=	1306	Y=	1307	Y=	1308	Y=	1310	Y=	1312	Y=	1316	Y=	1318	Y=	1322

+X=	0	+X=	158	+X=	317	+X=	476	+X=	635	+X=	794	+X=	953	+X=	1112	+X=	1271
Y=	1088	Y=	1088	Y=	1089	Y=	1090	Y=	1092	Y=	1094	Y=	1097	Y=	1099	Y=	1103

+X=	0	+X=	158	+X=	318	+X=	477	+X=	637	+X=	796	+X=	955	+X=	1115	+X=	1274
Y=	870	Y=	871	Y=	872	Y=	872	Y=	874	Y=	876	Y=	879	Y=	881	Y=	884

+X=	0	+X=	158	+X=	318	+X=	478	+X=	638	+X=	797	+X=	957	+X=	1117	+X=	1277
Y=	652	Y=	653	Y=	654	Y=	654	Y=	656	Y=	657	Y=	660	Y=	662	Y=	665

+X=	0	+X=	159	+X=	319	+X=	479	+X=	640	+X=	799	+X=	959	+X=	1120	+X=	1280
Y=	435	Y=	435	Y=	436	Y=	436	Y=	438	Y=	439	Y=	442	Y=	443	Y=	446

+X=	0	+X=	159	+X=	320	+X=	480	+X=	641	+X=	801	+X=	961	+X=	1122	+X=	1283
Y=	217	Y=	217	Y=	218	Y=	218	Y=	220	Y=	221	Y=	223	Y=	224	Y=	227

+X=	0	+X=	160	+X=	321	+X=	482	+X=	643	+X=	803	+X=	964	+X=	1125	+X=	1286
Y=	0	Y=	0	Y=	1	Y=	1	Y=	2	Y=	3	Y=	5	Y=	6	Y=	8

Exhibit E3---PRINT output
(Part 2 of 2)

6. From data obtained from program PRINT, execute program SCANDMA (Page 38, TOPAS Manual). For 15' quad, use INC=4; for 30' quad, use INC=16' for 7 1/2' quad, INC=0. (Exhibit E4 SAMPLE INPUT SCANDMA).

FORMAT: ALL VALUES RIGHT JUSTIFIED

cc	use	format
1-5	ILEFT - The lowest x value to be scanned decreased by INC.*	(I5)
6-10	IRITE - The highest x value to be scanned increased by INC.*	(I5)
11-15	IBOT - The lowest y value to be scanned decreased by INC.*	(I5)
16-20	ITOP - The highest y value to be scanned increased by INC.*	(I5)
21-25	INC - Scan interval. For example, if INC = 3, every third elevation point will be copied from a DMA Tape.	(I5)
26-30	IXSW-X value of SW corner obtained from PRINT.	(I5)
31-35	IYSW-Y value of SW corner obtained from PRINT.	(I5)

* This value is increased and decreased to insure overlap of 7 1/2 minute quads. THIS PROCEDURE SHOULD NOT BE USED FOR AROUND THE BORDER OF THE 1/250,000 HALF. In this case, take highest value of ILEFT or IBOT, and the lowest value of ITC IRITE that is divisible by INC.

[illegible]

Exhibit E4.--Sample input for .SCANDMA
(Part 1 of 2)

```

RUNH: N W51F61,          ,ROGER,3,400

BSTM PRINT,

#ASQ: A DTIS:ABS.
FAC MARKING          040200001000

#ASQ: T 010H:K1803E,UFV,F02F75

#USE 7., DEON:K1803E

#ASQ:UP R:SCAN,F24

#USE 8., R:SCAN

#XGT DTIS:ABS,SCANDMA

ITOP AND IRITE VALUES HAVE BEEN MODIFIED IF THEY WERE NOT AN EVEN MULTIPLE OF INC
ILEFT = 4 IRITE = 160 IDOT = 432 ITOP = 454 INC = 2 NCOL = 79 NROW = 112
YOU WILL NEED THE FOLLOWING INFORMATION IN YOUR SIZE CARD IN ORDER TO RUN COUNTOURS WITH OPEC

XSCALE = 0.00041HAP SCALE DENOMINATOR
YSCALE = 0.00041HAP SCALE DENOMINATOR
XCO = 1
YCO = 1
XMIN = 4
XINC = 2
XMAX = 160
YMIN = 432
YINC = 2
YMAX = 454

/

YOU WILL NEED THE FOLLOWING INFORMATION IN YOUR SIZE CARD IN ORDER TO RUN 180SLOPES USING F80PCP

XSCALE = 0.00041HAP SCALE DENOMINATOR
YSCALE = 0.00041HAP SCALE DENOMINATOR
XCO = 1
YCO = 1
XMIN = 5.000
XINC = 2
XMAX = 159.000
YMIN = 433.000
YINC = 2
YMAX = 453.000

YOU WILL NEED THE FOLLOWING INFORMATION FOR ZONE11
XONE = 4
YONE = 432
XTWO = 160
YTWO = 432
XTHREE = 4
THREE = 454

YOU WILL NEED THE FOLLOWING INFORMATION FOR THREE OR PREP3D

XMIN = 833.32
YMIN = 89998.56
XMAX = 33332.80
YMAX = 134247.82
H = 79
H = 112

DX = 416.67 DY = 416.67

QFIN

RUNED: W51F61 ACCT:          PROJECT: ROGER
LOAD F02F75 17/0 K1803E -1 W51F62
TIME: TOTAL: 00100184.823
      CAU: 00100105.113 1/01 00100106.280
      CC/ER: 00100103.429 WAIT: 00100100.000
INAGE: READ: 10 PAGE: 3
START: 05146135 OCT 11,1978 FIN: 05148148 OCT 11,1978
SIZE: Q23K
EST COST: TOTAL 00001.42
      CPU: 00001.00 1/01 00000.42
ESTIMATED COST IS COMPUTED AT SUBMITTED PRIORITIES.
DISCOUNTS FOR RUNS NOT PROCESSED IN SPECIFIED
TURN-AROUND TIMES ARE AUTOMATICALLY COMPUTED IN THE
MONTHLY BILLING. FIFTY CENTS MINIMUM FOR BATCH RUNS.

```

Exhibit E4.--.SCANDMA output
(Part 2 of 2)

7. Using output data from SCANDMA as input, execute program SLOPE (Page 111, TOPAS Manual). (Exhibit E5, SAMPLE RUNSTREAM.)

Data Card Formats

Only one data card is needed for input to program SLOPE. The card format is as follows:

cc	use	format
1-10	XINC Ground distance between adjacent elevation points in the X-direction.	F10.2
11-20	YINC Ground distance between adjacent elevation points in the Y-direction.	F10.2

In the case of DMA tapes, the ground distance between adjacent data points in the original data tape is 208.3 feet, in both the x and y directions. If only every second point is used, then the ground distance between adjacent points becomes 416.7 feet.

8. Using output from SLOPE as input, execute program ZONEIT (Page 132, TOPAS Manual), (See Exhibit E6, SAMPLE RUNSTREAM).

Assign a temporary file, unit 7, which would ordinarily be used for a plot tape for Calcomp plotter, but will be disregarded for our purposes. Assign a file, unit 9, for the output from this program will be the input file that will be converted for use in the RID*GRID System.

Starting on Page 132 of the TOPAS MANUAL--Card 1 is blank (just place a blank card in deck). Card 2 defines the upper ranges of each slope zone. Card 3, use 100.0 for UPERIN always. Obtain ILEFT, etc., from PRINT. Card 4, obtain data needed for this

card from printfile when executing SCANDMA. Card 5, use data from PRINT. Use a separate card for each registration point. Use three registration points. (For aspect, place a -4 in columns 3 and 4 of card 2.) (See Page 139, TOPAS Manual.)

Card 1: BLANK

Card 2: (When ZONEIT is used to plot slope zones)

cc	use	format
1-4	Upper limit of zone 1 (Example: = 15 if zone 1 is to be 0-15% slope)	F4.0
5-8	Upper limit of zone 2	F4.0
9-12	Upper limit of zone 3	F4.0
°		
°		
°		
76-80	Upper limit of zone 20	F4.0

The last zone specified in this card must be either blank or the maximum possible slope in the area.

Card 3: (To Define Boundary Limits of Data Array)

cc	use	forma
1-10	ILEFT + 10 = lowest value of X in grid units	F10.0
11-20	IRIGHT + 10 = highest value of X in grid units	F10.0
21-30	IBOT + 10 = lowest value of Y in grid units	F10.0
31-40	ITOP + 10 = highest value of Y in grid units	F10.0
41-50	UPERIN - 100.0	F10.0

Card 4:

cc	use	format
1-10	XONE - X coordinate in grid units of SW corner of array	F10.0
11-20	YONE - Y coordinate in grid units of SW corner of array	
21-30	XTWO - X coordinate in grid units of SE corner of array	F10.0
31-40	YTWO - Y coordinate in grid units of SE corner of array	F10.0
41-50	XTHREE - X coordinate in grid units of NW corner of array	F10.0
51-60	YTHREE - Y coordinate in grid units of NW corner of array	F10.0

Card 5: (Coordinates of a Registration Point)

cc	use	format
1-2	Latitude in degrees	I2
3-4	Latitude in minutes	I2
5-8	Latitude in hundredths of seconds	I4
9-11	Longitude in degrees	I3
12-13	Longitude in minutes	I2
14-17	Longitude in hundredths of seconds	I4
18-20	Blank	3X
21-30	X-coordinate of registration point in grid units	F10.0
31-40	Y-coordinate of registration point in grid units	F10.0
41	=1 if this is the last registration point in the data deck =0 otherwise	I1

There should be one Card 5 for each registration point. The last registration card has a 1 in column 41. There must be at least one Card 5 (with a 1 in cc41) in each ZONEIT run.

@RUN:R W51F61,

@ASG,A DTIS*ABS,
FAC WARNING 040200004000

@SYM PRINT4,,I

@ASG,A R*SCAN,

@ASG,UP R*SCAN-S,

@ASG,UP R*SCAN-A,

@USE 7., R*SCAN,

@USE 8., R*SCAN-S;

@USE 9., R*SCAN-A,

@XRT DTIS*ABS,SLOPE

@FLN

WORLD: W51F61 ACCT: PROJECT: ROGER

TIME: TOTAL: 00:00:22.657

CAU: 00:00:11.813 I/O: 00:00:06.787

CC/ER: 00:00:04.057 WAIT: 00:00:00.000

IMAGES READ: .12 PAGES: 2

START: 05:56:15 OCT 11,1978 FIN: 05:56:12 OCT 11,1978

SIZE: 044K

EST COST: TOTAL: 00002.89

CPH: 00002.40 I/O: 00000.49

*Exhibit E5.--.SLOPE output
(Part 2 of 2)*

Exhibit E6.--Sample input for .ZONEIT (aspects)
(Part 2 of 3)

PRIN.L W51F61.

@SYM PRINT*:

@ASG,A DTIS*ABS.
FAC WARNING 040200004000

@ASG,A P*SCAN-S.
FAC WARNING 040000000200

@ASG,T 7.

@USE A., P*SCAN-S

@ASG,CP SCAN*P2OUT.

@USE 9, SCAN*P2OUT

@XQT DTIS*ABS.ZONEIT
100.00000 1.69000 2.37000

YFTH

PRINID: W51F61 PRCT: PROJECT: ROGER

TIME: TOTAL: 00:00:25.876

CAU: 00:00:15.237 I/O: 00:00:06.620

COVER: 00:00:04.019 WAIT: 00:00:00.000

IMAGES READ: 17 PAGES: 2

START: 10:33:52 OCT 11, 1978 FIN: 10:36:53 OCT 11, 1978

SIZE: 051K

EST COST: TOTAL: 00006.68

CFU: 00005.70 1/4 . 0000.98

*Exhibit E6.--.ZONEIT output
(Part 3 of 3)*

9. Output from ZONEIT on unit 9 is in digitized format. A program has been developed to convert this data to GRID standard format for input to the GRID system.

This file is called RID*GRID. The executable program element is GELCOM. Input is on unit 7. After the execution command, one data card is required giving a 7-digit project number and 07 in columns 8 and 9. Output file is on unit 8. See Exhibit E7 for sample runstream

On the output (See Exhibit E7) are the registration points needed to be used in the GRID preprocessor. These points are always printed following the execution command. NOTE: On the print file, longitude and latitude are given in degrees and minutes. They must be converted to hundredths of a degree for GRID. Example: $43^{\circ} 15'$ equals 43.25° or $43^{\circ} 22' 30''$ equals 43.375° . etc.

10. The output file from ZONEIT is ready to be run through the G¹ Exhibit E8, shows the runstre¹ The window is checked to ensu covered. The preprocessed GF independent and can be used t the GRID procedures for COMLL See Section C of RIDS User's

01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69
----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----

@PUN W51F61
 DATE: 10/17/78 TIME: 111054
 THE SUBJECT FILES FROMICRATS ARE BEEN UPRATED PS OF 10-26-78 10:59:14
 @ACCT A RID*GRID.
 FACILITY WAPING 000200000000
 @PSG A SCAMP2OUT. → Input from Zaverit
 READY

USE 7. SCAMP2OUT.

REPT
 @PSG CP SCAMP2OUT. → output file
 REPT


USE 8. SCAMP2OUT.

READY

@ACCT RID*GRID.GELCOM

	Y	X
325230607	140	1700
431500000730000000	140	2290
43150000072520050	140	2290
432200500730000000	140	2290

Use these
 coordinates in the
 preprocessor .PREPRC/COMLUP



PROJECT: POCER

@PUN W51F61
 TIME: TOTAL: 00:00:29.982
 CPU: 00:00:20.034
 CC/EP: 00:00:04.280
 IMAGES REPT: 9
 PAGES: 2
 START: 11:10:54 OCT 11, 1978
 FIN: 11:16:00 OCT 11, 1978

SIZE: 009K

EST COST: TOTAL: 00013.00

CPU: 00011.40 I/O: 00001.26 CORRECT: 0000.24
 TERMINAL INACTIVE

Exhibit E7.--RID*GRID.GELCOM output
 (Part 2 of 2)


```

@RUN,N W51F61, PAGEP, 3, 400
@SYM PRINTS, UCI988
@RSG, T ASR, F40/200/TFK/5000
@RSG, F EID@PID.
@RSG, R SCAN@OUT.
@RSG, CP SCAN@E. (Var for input & GRI0)
@USE P.. SCAN@LOPE.
@XOT PII@PID, PREPPC/COMLUP
@ATSELT
@END
@FINUC
LHG1=73.00, LAT1=43.25
LHG2=72.875, LAT2=43.25
LHG3=73.00, LAT3=43.375
IX1=70, IY1=140, IX2=70, IY2=220, IY3=140
TOLEP=.0016
@END
@ADD SCAN@OUT.
@EOF

```

```

* BRUN,N W51F61, ,ADDER,3,400
*
* BSYN PRINT*, ,UZ1988
*
* BASG,T A9A,,F40/200/TRN/5000
*
* BASG,A RID*GRID,
* FOL WARNING 040200000000
*
* BASG,A SCAN*OUT,
*
* BASG,CP SCANSLOPE,
*
* QUSE B,, SCANSLOPE,
*
* *XOT RID*GRID,PREFRC/COMLUP
* *FIDUC
* MINLAT = ,43250000E+02
* MAXLAT = ,43375000E+02
* MINLON = ,72875000E+02
* MAXLON = ,73000000E+02
* LNO1 = ,73000000E+02
* LAT1 = ,43250000E+02
* LNO2 = ,72875000E+02
* LAT2 = ,43250000E+02
* LNO3 = ,73000000E+02
* LAT3 = ,43375000E+02
* TX1 = ,120
* TY1 = ,140
* TX2 = ,120
* TY2 = ,1700
* TX3 = ,1290
* TY3 = ,140
* ORHIX = ,10, 10
* ORHTY = ,10, 10
* TOLTR = ,16000000E-02
*
*
* $END
*
* PROJECT: 2JS2306
*
* 2394 RECTANG,
*
* MASTER-MAF SYMBOL AND POLYGON ID CORRESPONDENCE
*
* IDENT SYMBOL
*
* 1 A--
* 2 B--
* 3 C--
* 4 D--
* 5 E--
* 6 F--
* 7 G--
* 8 H--
* 9 I--
* 10 J--
*
* *WINDOW
* OXMIN = ,72875037E+02
* OXMAX = ,73000142E+02
* OYMIN = ,43250062E+02
* OYMAX = ,43379606E+02
*
* $END
*
* 546 POLYGON WRITTEN,
* 0 ARCS WRITTEN,
*
* RUNID: W51F61 ALCT: PROJECT: R0061
*
* TIME: TOTAL: 0010113,944
* CPU: 00100138,422 I/O: 00100126,707
*
* C/E/R: 00100109,036 WAIT: 00100109,000
*
* IMAGES READ: 2113 PAGES: 3
*
* START: 20126125 OCT 11,1978 FIN: 20132142 OCT 11,1978
*
* SIZE: 049K
*
* EST COST: TOTAL: 00009,42
* CPU: 00007,80 I/O: 00001,82
*
* ESTIMATED COST IS COMPUTED AT SUBMITTED PRIORITIES.
* DISCOUNTS FOR RUNS NOT PROCESSED IN SPECIFIED
* TURN-AROUND TIMES ARE AUTOMATICALLY COMPUTED IN THE
* MONTHLY BILLING. FIFTY CENTS MINIMUM FOR BATCH RUNS.

```

Exhibit E8.--RID*GRID.PREFRC/COMLUP output
(Part 2 of 2)

11. The following runstreams are shown as examples to use the map file that was generated from the RID*GRID.PREPRC/COMLUP preprocessor. A complete description of data input and manipulation is to be found in Section A and Appendix "A" of this user's guide.
- a. Exhibit E9 is used to obtain a grid output display from the PREPRC/COMLUP output file. The initial run is in a passive mode to verify the converted data then the runstream is executed in an active mode to create a master map file in the grid system. To create a map file all that is needed is the command CREATE in the action field of "A" Card.
 - b. Exhibit E10 is used to obtain a single topic display of the created file. Run in a passive mode.
 - c. Exhibit E11 is used to convert the Master Map to alpha and change alpha characters to numeric for grey scale display. This is convenient for displaying slope data in a grey scale output rather than a single character display. These procedures can be run either passive or active, if the user desires the grey scale output, only then run it passive. If the user intends to use the slope data for manipulation in the grid system then it is advantageous to create an alpha map file from the Master Map. This is done by executing only the first "A", "G" and "R" Cards and adding the CREATE command to the action field of the "A" Card.

Exhibit E12 shows a topographic map of .GRID output.




Exhibit E9.--GRID output (slope) alpha
 (Part 2 of 2)

[illegible]

Exhibit E11.--Sample input to obtain master to alpha conversion
(demand mode) grey scale display (Part 1 of 3 continued)





Exhibit E11.--.GRID output (slope) numeric
(Part 2 of 3)



III. COST ANALYSIS

The following are representative costs to create a slope map from DMA tapes for input to the grid system. The example used represents a 7 1/2 minute USGS quadrangle. It is assumed that the DMA tape is on file at FCCC.

<u>PROGRAM</u>	<u>COST</u>	
.PRINT	\$.79	Demand
.SCANDMA (Increment 2)	1.42	Batch Priority "N"
.SLOPE	2.89	Batch Priority "N"
.ZONEIT	6.68	Batch Priority "L"
.GELCOM	13.00	Demand
.PREPRC/COMLUP	9.62	Batch Priority "N"
.GRID Passive	8.28	Batch Priority "N"
Active	11.95	Batch Priority "N"
Cost to process and create map	<u>\$54.63</u>	

The following cost is optional but should be considered for planning purposes. They are incurred on a demand terminal to convert your master map to alpha and change the alpha characters to numeric for grey scale display. The total cost for this procedure is \$8.92, therefore, total cost per 7 1/2 minute quadrangle is \$63.55.

APPENDIX "A" INPUT FORMS

<u>CARD TYPE</u>	<u>DESCRIPTION</u>
REFERENCE CARD	User Option to Change Base Sector Grid Code to Geographic Scale or Base Sector Origin
A	<u>Mapping Request</u> - Distinguishes map requests by one individual from map requests by other individuals
B	<u>Dictionary Definition</u> - A Table Which Relates the Geographic Shops Defined By A Master Map With A Code Representing the Area
C	<u>Area Identification</u> - Provides a pointer to a Specific Area Location and to Define its Unique Symbol
D	<u>External Data File</u> - With External Data B
E	<u>Field Labels and For</u> to be Assigned to Ea Fields Used with D-C

- F External Data on Card-Input File - User Describes
Format and Order of Appearance of the Data Described
on E-Card
- G Map Definition - Provides a Unique Identification
for the Map Being Prepared
- H Text Overlay - Overlays short text statements within
the Body of a Map to Assist in Interpretation of the
Display
- I Title - User Supplies Title or Legend When Generating
New Maps
- J Scale - Used for Re-coding and Weighting Values for
Manipulation and Display
- K Map Generation by Symbol Conversion - Allows for the
Generation of New Maps which may be Created from
Existing Maps
- N Map Generation by Dictionary Symbol Conversion - If
Desired Map to be Generated is Based Upon Areas Defin
in a Dictionary, Use of the N-Card is Required
- O Map Generation by Points or Lines - Provides the Fact
of Generating Maps by Defining Data Points or Data Li
Within the Study Area with Associated Value
- P Generation by Element Matrix - Provides for Initial
of Cell Coded Data in Matrix Form Acceptable to GRID


- Q Topic Generation by External Data - Used in Conjunction
 with an External Data File Defined on D and E-Cards
- R Map Composition - Used for Defining the Combination of
 Overlays to Obtain Desired Output

- S Report Title - User Inputs Alphanumeric
Statistics Reports Title
- T Statistic Parameters - User Selects Type
of Statistical Report Available From
System
- U Independent Maps - Used Only When a Multiple
or Stepwise Regression has been Requested on
T-Card
- V Study Area Legend - Supplies Notes to the
Generated Map which are Pertinent to all
Maps in Study Area
- W Window Display - Selectively Displays a
Portion of the Area Defined in the G-Card
- X Precedence Table Change - Used to Change
Values of Default Settings
- Y Change Overprint Combinations - Varies Gray
Tone Output for Numeric Maps
- Z Map Display - User Options to Modify Output
for Display Purposes

APPENDIX "A" INPUT FORMS

INPUT FORMS

This Appendix deals with the card input definitions and allowable codes. All input cards must have the card type indicated in column 1. This applies to Batch Processing and to Demand Mode* of operation. In Batch Processing the input deck must be preceded by an asterisk card and must be followed by an asterisk card. The input deck should look as follows:



*NOTE: Only the following input card options are available in Demand Mode operations.

Reference Card A, G, H, I, J, K, P, R, S, T, V, W, Y, Z.

REFERENCE CARD

The base sector grid-code-to-geographic scale may also be changed by the GRID user. As indicated in Table 2, the default value of the base sector (grid code = 1) is 3.75 minutes in both latitude and longitude at 8 or 6 lines per inch; 3.00 minutes at 10 lines-per-inch. Both latitude and longitude scales may be changed independently of each other.

To change these entries, input a card with the following information at the beginning of the runstream, preferably before the first A-Card. See Section A; II A3c for additional information.

Columns 1 through 9	REFERENCE
Columns 11 through 20 (i.e., 7.233)	Extent in the X-direction (longitude), expressed in minutes-per-sector of the base sector. (Grid Code 1.) Decimal point must be entered.
Columns 21 through 30 (i.e., 6.533)	Extent in the Y-direction (latitude), expressed in minutes-per-sector of the base sector. Decimal point must be entered.
Columns 31 through 40 (44°05'00" = 44.0833)	The reference latitude in decimal degree. Decimal point must be entered.
Columns 41 through 50 (71°25'00" = 71.4166)	The reference longitude decimal degree. Decimal point must be entered.

	911	2021	3031	4041
REFERENCE	7.223	6.533	44.0833	71.4166

A-CARD MAPPING REQUEST

The A-Card distinguishes map requests made by one individual from map requests made by other individuals. It is a personal identification card which is listed on the output transaction register and on the top of each output map. This includes the name of person making a map request, his organization, the type of transaction, and the map file to be used.

Requester

The requester field will contain the name of the user, and is optional. This field should be left adjusted and may contain a maximum of 12 characters. The program will accept any combination of numbers and characters.

REQUESTOR		ORGANIZATION	TRANS ACTION	SPECIAL SUBSET UNITS	MERGER OR SUBSET MAP FILE NAME	NO INPUT MAP FILE	MAP FILE NAME
1	2	17	31	35 40 45	46	50	51
A	A.B.LOVE						

Organization

The organization field will contain the name and/or the number of the requester's department. Its main purpose is to provide an identification for returning the system output to the requester. This field should be left-justified and may contain a maximum of 12 characters. The program will accept any combination of numbers and characters.

REQUESTOR		ORGANIZATION	TRANS ACTION	SPECIAL SUBSET UNITS	MERGER OR SUBSET MAP FILE NAME	NO INPUT MAP FILE	MAP FILE NAME
1	2	17	31	35 40 45	46	50	51
A	A.B.LOVE	MOO					

Transaction

Passive

The transaction field of the A-Card is normally left blank indicating passive participation with the Map File. Passive participation merely indicates that the Map File is not physically affected, only monitored. This passive transaction may be used for editing input card formats and producing verification line printer plots. These plots may be used in conjunction with the source maps in editing the input data. The passive transaction is very cost effective and should be used whenever feasible.

Active

There are six possible entries to the transaction field which will implement a change to the Map File. This is defined as having active participation with the Map File. These transactions are:

"CREATE" would be used in adding new maps titles or dictionaries to the Map File.

"MODIFY" would be used to add new entries to a dictionary or to change current entries in an existing map, title or dictionary on the Map File.

"REMOVE" would be used to erase entries in an existing dictionary the Map File. Parts of dictionary entries may be deleted by specifying appropriate C-Cards.

"DELETE" would be used to destroy an entire map, title, or dictionary on the Map File. Further references to this map, title, or dictionary after a "DELETE" transaction would be flagged as an error by the system since it would no longer exist.

"MERGER" would be used to combine existing maps, titles or dictionaries from one Map File onto another. The merger file name placed in columns 44 through 55 and the file name to which the

elements are to be merged is placed in columns 61 through 72. Only 'B' cards and 'G' cards are permitted to follow a merger operation. These cards will indicate which maps from the merger file are to be kept, and the other data will not be merged onto the new map file. A new 'A' card with another transaction or an '*' card will get the user out of merger mode.

"SUBSET" transaction will produce a spin-off file in this system format containing only the elements referenced on subsequent 'B' or "G" cards. The new subset map file name is entered in columns 44 through 55.

Transaction errors could jeopardize the Map File and for this reason these six transactions must be used by individuals with complete understanding of this system.

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72
REQUESTOR										ORGANIZATION										TRANS ACTION					SPECIAL SUBSET UNITS					MERGER OR SUBSET MAP FILE NAME										NO INPUT MAP FILE					MAP FILE NAME																										
A. B. Love										MOON										CREATE																																																			

Special Subset Units

These columns are usually left blank, but when the transaction of "SUBSET" or "MERGER" are used, the number of the external unit being used must be placed in these columns. If the transaction "MERGER" is placed in columns 31 through 36, then column 38 must contain the unit on which the merger file resides. This unit can be established with an EXEC 8 assign card (@ASG) or with a use card (@USE). Example, if an 'A' was entered in column 38, an assign card could appear as @ASG,T A, U9V, F04977, this would have the tape F04977 mounted on the tape drive and call the tape drive unit "A". Column 40 follows the same rules as column 38 but this applies when "SUBSET" is the transaction.

Column 42 is marked when the "SUBSET" transaction is used and it is desired to have an output tape generated which is suitable for external statistical analysis. The resulting tape file will be void of all legends, titles, etc., and will only represent the actual map values. A form will be printed by the system depicting the output tape format.

Merger or Subset Map File Name

This field is normally left blank. A "MERGER" transaction uses this field to indicate the external map file name which is to be merged onto the file indicated in "map-file-name" field. If it is desirable to have a subset, of the maps stored on the master map file, written on a separate magnetic tape, a subset file name must be entered in this field. The new subset map file created can be considered a master map file in its own right, and in subsequent runs the new name could be referenced in the Map File Name field (columns 61 through 72).

1	31	32	41	42	43	44	51	52	53	54	55	56	57	58	59	60	61	72		
REQUESTOR			ORGANIZATION			TRANS ACTION			SPECIAL SUBSET UNITS			MERGER OR SUBSET MAP FILE NAME			NO INPUT MAP FILE			MAP FILE NAME		
A. B. LOVE			MOON			SUBSET			A			MERGER 2								

No Input Map File

This field is normally left blank. It is used only for the special case of beginning a new map file. If a map file has not been previously established, an X in this field will denote that a file of the name entered in the Map File Name field (columns 61 through 72) does not currently exist. Therefore, in your runstream no tape is assigned to the input unit 7. If this field is used then the Map File Name must be entered.

1 1A	1 REQUESTOR	17 ORGANIZATION	31 TRANS ACTION	36 SPECIAL SUBSET UNITS	44 MERGER OR SUBSET MAP FILE NAME	50 NO INPUT MAP FILE	61 MAP FILE NAME
	A-B-LOVE	MOON	CREATE			X	

Map File Name

The Map File Name is a reference to a specific magnetic tape. It may be thought of as a tape label. The name of the map file must appear exactly as previously defined, since it is used to locate the proper map file. Entries must, therefore, reference a valid file name, be left-adjusted, and may contain a maximum of 12 characters.

1 1A	1 REQUESTOR	17 ORGANIZATION	31 TRANS ACTION	36 SPECIAL SUBSET UNITS	44 MERGER OR SUBSET MAP FILE NAME	50 NO INPUT MAP FILE	61 MAP FILE NAME
	A-B-LOVE	MOON					TIMBER

B-CARD DICTIONARY DEFINITION

The dictionary definition card provides a unique identification to the map dictionary being prepared. The map dictionary is a table which relates the geographic shapes defined by a master map with a code representing the area.

Grid Code

This field provides a means of separating dictionaries with identical names but having different element sizes. The grid code is divided into two parts: level and lines-per-inch. The level refers to the relative area covered by the elements within the map. See Table 2 Section A for correspondence between level designation and map scale.

The second part, lines/inch, must be either 6 or 8 depending on the configuration of the available equipment. Further, since master maps and dictionaries operate in conjunction with one another, the grid code of the dictionary must match the grid code of the associated master map. If the use of dictionaries and master maps of different grid codes is attempted, an error message will result.

GRID CODE		1		2		3		4		5		6		7		8		9		10		11		12	
LEVEL		LINES/INCH		NON CONTIGUOUS SEARCH FACTOR		AREA PRINTER REPRESENTATION GRID WITH GRID		AGGREGATE AREA SUFFICES		AA 1		AA 2		AA 3		AA 4		AA 5		AA 6		AA 7		AA 8	
0000		0000		0000		0000		0000		0000		0000		0000		0000		0000		0000		0000		0000	

Dictionary Name


This field is used to designate the dictionary name. Dictionary name chosen must relate to the master map of the same name except for the first character, i.e., \$COUNTY would be the dictionary of the master map designated *COUNTY. Note that the Dictionary field is only 9 characters in length instead of the normal 12-character name. This

to facilitate the use of aggregate area definitions. A dictionary name is a combination of the 9 characters in the Dictionary Name Field in addition to the 3 characters of the Aggregate Area Dictionary Suffixes. The combination comprises the normal 12-character name. If in referencing a dictionary, the last 3 characters are blank, the program assumes that the basic area definitions are being referenced and not the aggregate areas. Dictionary should be defined at the smallest workable area size that is consistent with the study to be performed.

1	GRID CODE	9	DICTONARY NAME	NON-CONTIGUOUS SEARCH FACTOR	2	AREA PRINTER REPRESENTATION GRID	3	4	5	6	7	8
	LEVEL											
8	0000		COUNTY									

Noncontiguous Search Factor

Whenever two or more areas with the same polygon codes do not share the same boundary, then the system must be called upon to perform a search to locate these noncontiguous (not sharing the same boundary) areas. This occurs for example where an island is part of a shoreline county.



NON-CONTIGUOUS SEARCH FACTOR
FOR THIS EXAMPLE IS 2

The number of factors assigned depends on the number of cells between the areas within the same grid. If the island was the only noncontiguous area and was two elements away from the shoreline, it would be placed in the noncontiguous search factor field. Finding the island.

The value or factor may range from 0 through 9. Blank is considered as zero. Since the search will be conducted from the border points of each area, care must be taken that this factor is not made so large that unique areas are also thought to be contiguous. This field saves the use of an area pointer on the C-Card. The area pointer is used to indicate which area within the master map belongs to specific area code and area symbol being defined.

GRID CODE		DICTIONARY NAME		NON CONTIGUOUS SEARCH FACTOR		AREA POINTER REPRESENTATION		AGGREGATE AREA SUFFIXES						
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15

Area Pointer Representation

This field informs the system of the form in which the area pointer is to appear on the following 'C' Cards and the position is to be marked with an X. One and only one pointer type must be marked. The three choices are:

- ° Grid Code - Pointer by sector row-column and element row column
- ° UTM - Pointer with UTM easting, UTM northing and the UTM zone.
- ° Geographic Coordinates - Latitude and Longitude

When 'C' Card processing takes place, the system will convert all pointers internally to grid code form.

Aggregate Area Dictionary Suffixes

Up to six aggregate areas to the basic area definition may be defined. This option is used whenever the basic areas may be aggregated to form a new geographic area of meaning. It is, therefore, possible to define up to seven dictionaries on one set of 'B' and 'C' Cards. The entries on the B-Card are the last three characters of a 12-character name. This name consists of nine characters from columns 9 through

of the B-card followed by the 3-character aggregate area dictionary suffix.

1	GRID CODE LEVEL	2	DICTONARY NAME
0	0000	1	

NON CONTIGUOUS SEARCH FACTOR
35

AREA PAINTER REPRESENTATION GRID UTM GEO
31 32 33
X 0 0


AGGREGATE AREA SUFFIXES					
SO 1	SA 2	SA 3	SA 4	SA 5	SA 6
Dev	SMA	DBS	STA	REG	

C-CARD AREA IDENTIFICATION

The purpose of these cards is to provide a pointer to a specific area location and to define its unique symbol. One or more C-Cards must be provided for each area within the study area. A secondary purpose of the C-Card is to provide the aggregate area symbol coding. This is used whenever a group of areas can be summarized to a higher level. For example, if counties were the areas being defined, new areas can be defined as aggregates of counties such as regions, States, districts, etc. For this reason, dictionaries should be defined at the smallest workable area size that is consistent with the study to be performed.

Area Code


Each unique area must have assigned to it a numeric code to allow the system to interface with data files. This code is at the discretion of the technician. It must, however, match the coding structure of the data files to be used. If, for example, it is desired that 1970 census data are to be mapped, the 1970 census codes must be used as the area codes. Area codes are treated as alphanumeric fields and, therefore, must be left-justified. If more than one C-Card is used the area codes must be in an alphanumeric sequence, with the alpha character taking precedence.



Area Symbol


Area symbols are comprised of three characters: a 1-character alphanumeric prefix, and a 2-character alphanumeric suffix. There are 44 valid symbols which are listed on the K-Card form. Each area must

have a 3-character symbol assigned to it. Within a study area, two areas must never have the same symbol. The prefix symbol character assigned must match the character assigned to the area on the master map element matrix; i.e., if the area has been designated as F on the master map, the symbol assigned on the dictionary must begin with F, such as F02 or F4A, etc.



Area Pointer

The Area pointer field indicates which geographic shape within the master maps belongs to specific area code and area symbol being defined. Since the master maps may have several areas defined as symbol "F" for example, it is necessary to distinguish between F02 and F03. Grid code area pointer: Since each of the sectors has a unique row of column combination, an area on a master map can be easily identified referencing an element within the area by specifying a sector row and column and an element row and column. The entries to be made are numeric in all cases and, therefore, must be right-justified. If the area being defined is totally contained within a single map sector, any element row and column combination falling within the area is valid. If, however, the area extends into other sectors, the element row and column combination must be one of the sector border elements which share the same boundary to the other sectors involved.



Contiguous Area Pointers


Figure C-1

The example above can be used to describe three cases of areas extending into more than one sector.

1. If the area in question were contained entirely within sectors 3-1 and 3-2, the element row and column designat would be valid at any point along the border between 3-1 3-2 and could be on either side of this border. Area Pc indicates one such point.
2. If the area were contained entirely in sectors 1-1, 1-2, and 2-2, then the element indicated by the row and colour lie at one of the intersecting corners of the four secti involved (Area Pointer A).
3. If the area extended into more than four sectors, then single entry point would not suffice to link the areas.

[illegible]

A-C-4



Noncontiguous Area Pointers

Figure C-2

When the island appears in a different sector than the mainland, as is the case in Sectors 4-1 and 4-2, there is no place along the common border of sectors 4-1 and 4-2 where the related areas touch, therefore, two area pointers are also required in this case. This is necessary regardless of the search factor size since searching does not continue across sector boundaries.

Pointer Representations


UTM Area Pointer: If the area is entered with the UTM coordinate system then a UTM easting, northing and zone are necessary. The point is immediately converted by the system into the grid code coordinate system and then handled as grid code pointer as previously

defined. Caution must be exercised when attempting to place an area pointer on a sector boundary for use with multi-sector areas. In using UTM area pointers, it is safer to enter a pointer to the same area twice than trying to hit one of the sector edge rows or columns. Multiple area pointers to the same geographic area will not confuse the system.

Geographic Area Pointer: The area pointer is given with a latitude-longitude combination and immediately converted to grid code coordinate system. The same rules and cautions apply to geographic pointer as with UTM area pointer.

Area Name


The area name is assigned to assist the user in retaining the identity of the area. It generally refers to the basic area and not the aggregate areas. If counties are the areas being coded, the names of the counties would be included in this field. The area name is not used by the program; however, it is listed on the transaction register output. The program will accept any combination of numbers and characters.



Aggregate Area Symbols

Frequently areas are aggregations of the ones being coded, such as States, districts, regions, watersheds, etc. If this occurs in the process of coding various areas into a dictionary, the aggregate areas may also be coded with their own unique 3-character symbols. An aggregate map could then be created using these symbols by referencing the appropriate 9-character master map name and the 3-character

aggregate area suffix defined on the B-Card all combined into one 12-character master map name. Each aggregate area can be considered a dictionary in its own right and is independent of any other aggregate area. Each, however, is dependent upon the basic area defined in columns 16 through 18.



Introduction

D and E Cards are used to interface the system with external data bases. Before discussing the D and E Cards individually, a brief discussion of the interface needed for external files is in order to provide a basis for understanding the required entries. If we view the data tape as a coded card deck, it would appear as shown below. The deck would contain coded information on various attributes such as median income, population, etc., for various entities such as counties, regions, etc.




Figure D-1

The first interface requirement then would be to describe the data to the program. It is necessary that the program knows where on the card the information resides, and which attributes the data represent. This is accomplished by a data format which indicates the fields of the cards and what information they contain. Within GRID this requirement is met by naming and describing each field on the E-Card in combination with the D-Card.

The second interface requirement is to provide a means of linking the code such as State 5, and County 11 (combined to a common field such

as 5011) with the master map area. The master maps stored correspond to geographic areas and are designated by alpha and numeric symbols within a sector. These symbols do not correspond to the codes of the data deck. To further complicate the problem, a given code on the card deck may provide data for several sectors since, for example, a county could lie in four sectors. This requirement is met by referencing the suitable cross-reference dictionary or master map on the D-card.

Digitized data provides an immediate form of cross-referencing, since the coordinates describe the geographical area with which the attribute values are linked. No other cross-referencing mechanism (master map, dictionary) is necessary in this case.

D-CARD EXTERNAL DATA FILE

External File Name

Columns 3 through 14 should contain the name of the external data file. This file name, in some instances, is checked against the actual data file to verify that the correct file is mounted. This field must be left adjusted and may contain a maximum of 12 characters.

File Type Selection

The system accepts nine categories of external file inputs. A file in any one of these categories is selected by coding its index number in the file type selection field of the D-card. The categories and their index numbers are:

01 FORTRAN I/O FORMATTED

FORTRAN format is defined to be any external file which meets the following requirements:

- Data records must be in either IBM-BCD or UNIVAC-Fieldata format.
- Each record must not be greater than 132 characters long and must be fixed length.
- One field in each record must be the identifying code, symbol or area pointer supplied in a field whose maximum size is 12 characters.
- The tape may be in any sequence.
- The tape must be readable without software translation, unblocked, without header or trailer records and closed with an EOF mark.
- Internal unit must be numeric.

02 FMPS FILES (FUNCTIONAL MATHEMATICAL PROGRAMING SYSTEM)

- Variable names used in an FMPS model become part of the records output by FMPS and serve as a reference link to their data.
- GRID users intending to map FMPS data must observe some restrictions in variable naming within FMPS. Any FMPS variable which is to be mapped must have some spatial aspect; and this aspect is represented within its name. These variable names have two parts:
 1. A 5-character descriptive part.
 2. A 3-character area symbol (dictionary cross-reference).

An example is TIMBRA3U where "TIMBR" is the descriptive part, and "A3U" is the symbol for some area (this symbol must be blank if the variable has no spatial meaning). The procedure for defining FMPS records (E-cards) is different from those for other files. For a given variable, not only its solution value, but other derivative values are stored. The system uses certain key-words as qualifiers to variable names to indicate which derivative item is to be mapped. The naming syntax in GRID is (variable . qualifier). The qualifiers and

and their meanings are:

1. ACTIV Activity
2. SLACT Slack Activity
3. DUACT Dual Activity
4. INCST Input Cost
5. MRACT Marginal Activity

Coding TIMBR.ACTIV (on an E-Card) would direct the system to collect, for possible mapping, the primal activity value for the variable, TIMBR, for all geographical areas in the file. Internal unit must be numeric.

03 GIM DATA BASE

- ° Unimplemented

04 ERTS IMAGERY

- ° Unimplemented

05 F-CARDS DATA ONLY

- ° Data appears immediately in GRID runstream (See F-Cards).

06 "USER" DATA

- ° This is defined as any foreign data base for which additional programing is necessary for processing, either prior to or during system execution. A file type of 06 as indicated on this card, means that data is to come from a user defined source. Too many varieties of input tapes exist to enable an easy input request to be constructed specifying all the required parameters.

In all cases involving user defined external data, a read routine has to be supplied. This routine has to be written in FORTRAN IV or V and must be a subroutine called USERRD.

The parameters for this subroutine are shown in the following GRID call statement: CALL USERRD (NCOND, NSTAT, BUFFER, LENGTH, unit)

NCOND is a one word variable, used by the system to tell the read routine what is to be done:

NCOND = 1 Open the file, perform all functions necessary to start reading records, such as reading header records, reading format data cards from the cardstream, etc.

NCOND = 2 Return the data for one area to be mapped in the array BUFFER.

NCOND = 3 Close the file, if necessary print out record counters, etc.

NSTAT is a one word variable used by the read routine to tell the system the outcome of the requested action.

NSTAT = negative An error of some kind occurred, the read routine is not able to recover.

NSTAT = 0 Requested actions completed, essentially the data for the next area have been transferred to the array BUFFER.

NSTAT = positive The end of the external data has been reached, or the end of the file has been encountered, etc.

The array BUFFER does not contain any more data.

BUFFER is a 2,000 word work array for the routine USERRD, which will transfer the data for each area into the first words of BUFFER.

LENGTH is a one word variable defining the number of words of data expected by the system in BUFFER and computed according to the specifications of the E-cards.

UNIT is the indicated unit from column 19 of D-card.

All data to be transferred to the system have to be numeric decimal numbers except the cross-reference field. The sequence of the data fields is expected to be the same as that of the names given on the E-cards which represent one word each, again except for the

cross-reference field.

The cross-reference field, found on the E-cards and in the proper sequence on the E-card, stands for a one, two or three word field depending on the type of cross-reference being used. If the data read in by USERRD contain the code structure used in a dictionary, this field must be two alpha words equal to the 12-character code in the dictionary. If the cross-reference is by symbol, (basic areas or aggregate areas), then this field is one alpha word long, 3 characters left-adjusted. For a cross-reference by area pointer (geographic or UTM) this field is two or three words long respectively.

Figure D-2 shows a flowchart of a read routine. Figure D-3 is a sample read routine used to read a binary tape.

07 GIRAS FILES

GRID is capable of processing any of the USGS "GIRAS" data files. The map-based data contained in these files are represented as a set of polygons, arc segments and coordinates in digital form. Associated with each polygon is an "attribute," which is a coded representation of the feature which polygon boundary describes. Up to six data sets (map-layers) may exist in a GIRAS file. These are:

1. Land Use and Land Cover
2. Political Unit: (places, counties, States)
3. Hydrologic Units
4. Census County Subdivisions
5. Federal Land Ownership
6. State Land Ownership (optional)

In GRID, a given data set is handled by separately preprocessing it into GRID-standard form. The program, PREPRC/GIRAS, performs this operation on the GIRAS data files. Preprocessing consists of chaining all the arc segments which make up each polygon and applying a digital




Figure D-2: Flow

```

SUBROUTINE USERRI(NCOND,NSTAT,BUFFER,LENGTH,UNIT)
C
C SUBROUTINE TO READ AN EXTERNAL BINARY DATA FILE FOR RAP.
C ALL DATA ARE INTEGER NUMBERS EXCEPT FOR THE CROSS REFERENCE CODE
C IN WORDS 1 AND 2, WHICH IS ALPHA.
C NCOND OPERATION TO BE DONE
C 1 OPEN FILE
C 2 READ A RECORD INTO BUFFER
C 3 CLOSE FILE
C NSTAT STATUS OF OPERATION
C 0 NORMAL RETURN
C +1 END OF DATA
C -1 READ ERROR
C BUFFER WORK BUFFER OF 2000 WORDS
C LENGTH NUMBER OF WORDS EXPECTED BY RAP
C UNIT THE UNIT NAME LEFT JUSTIFIED IN THIS WORD
C
C DIMENSION BUFFER(2000)
C EQUIVALENCE (DECL,INT)
C NSTAT=0
C GO TO (100, 200, 300), NCOND
C
C OPEN FILE, READ 13 WORD HEADER RECORD
C CHECK LENGTH, HAS TO BE EQUAL TO 28
100 IF(LENGTH.EQ.28) GO TO 105
WRITE(6,101),LENGTH
101 FORMAT(/,56H RECORD LENGTH INCORRECT, 28 WORDS DEFINED, RAP EXPECTS ,I4)
STOP ERROR
105 CALL NTRAN(UNIT,2,13,BUFFER,L)
110 IF(L+1) 900,110,120
C CHECK L FOR LENGTH OF RECORD READ
120 IF(L.EQ.13) RETURN
C
C ERROR, HEADER RECORD MISSING, STOP RUN
C WRITE(6,130)
130 FORMAT(/,40H ERROR, NO HEADER RECORD FOUND ON UNIT)
NSTAT=-1
RETURN
C
C READ A RECORD, 30 WORDS
200 CALL NTRAN(UNIT,2,30,BUFFER,L)
210 IF(L+1) 900,210,220
C SKIP WORDS 3 AND 4, WHICH ARE NOT USED, CONVERT ALL NUMBERS TO DECIMALS
220 DO 250 I=3,28
DECL=BUFFER(I+2)
250 BUFFER(I)=INT
RETURN
C
C CLOSE FILE, NO ACTION NECESSARY
300 RETURN
C
C STATUS NEGATIVE ON UNIT READ, CHECK FOR END-OF-FILE
900 IF(L.EQ.-2) GO TO 920
C READ ERROR
NSTAT=-1
RETURN
C
C END OF FILE REACHED
920 NSTAT=+1
RETURN
END

```

Figure D-3

to geographic coordinate transformation. PREPRC/GIRAS assumes that base maps are in the UTM projection. The GRID-standard file may then be input into GRID using runstreams described in the following sections. GIRAS files are generally produced with standard IBM tape-labelling at 1600 BPI density. PREPRC/GIRAS handles all label record manipulations.

Runstream to Preprocess a GIRAS Data Set

@RUN

@ASG,TVRJ	1,U9V,reel#	° GIRAS Input File
@ASG,TVW	B,U9V,reel#	° Preprocessed Output
@ASG,A	RID*GRID.	° Program file containing PREPRC/GIRAS
@XQT,OU	RID*GRID.PREPRC/GIRAS	
FILE#4		° Directs preprocessor to operate on the fourth data set (Census County Subdivisions)

Sample Output From Preprocessor

The following pages show what output should be expected from a preprocessor runstream.

First, the map-header of the requested data set is printed. This contains a textual description of the data set, control point coordinates (digital and geographic) and other technical information which the preprocessor requires.

For each map section in the data set, the section-header is printed. In the example data set, there is only one map section. The master map symbol to polygon attribute correspondence table, which is printed after sections are preprocessed, associates a unique 3-character master map symbol to each polygon attribute code. Attribute codes are stored on GRID-standard files as UNIVAC floating-point numbers. Two types of maps may be created from a preprocessed GIRAS data set-- either a master map, directly from the master map symbols, or a real-valued map from the single attribute code. Both may be transformed into other types using R-Card sequences.

Next, a summary report is printed. Summary statistics should match information given in the map-header. Next, the data set name is printed. The preprocessor retrieves this name from the "data set identifier" field of the HDR1 label record preceding the map-header data. As the message indicates, the first twelve characters of this name must be recorded in Columns 3-14 of the D-Card in a subsequent GRID runstream used to process the GRID-standard file created by the GIRAS preprocessor.

A geographic window is then printed which gives the extreme geographic coordinates calculated for the entire map using the digital to geographic transformation. In order to display the entire map, the user should enter "clipping" coordinates on the D-Card which contain this window.

GRID Runstream to Process a Standardized GIRAS Data Set

The following is a batch runstream which shows the necessary EXEC-8 control language and GRID control cards for producing and displaying a master map from a standardized GIRAS data set:

MAP HEADER: KANSAS CITY,KAN-MO 1:250000 QUAD HYDROLOGIC UNITS

NUMBER OF ARC RECORDS(MA) IN MAP IS 36
NUMBER OF COORDINATES(C) IN MAP IS 11928
NUMBER OF POLYGON RECORDS(P) IN MAP IS 13

FILE TOLERANCE(PTL) IS 5 ARC LENGTH TOLERANCE(ATL) IS 15
NUMBER OF MAP SECTIONS(NSC) IS 1 MAP TYPE CODE(MTP) IS 10
LENGTH OF TEXT FILE(LTX) IS 0 MAP PROJECTION CODE(MPJ) IS 1
MAP SCALE(MSC) IS 250000 MAP DATE(MDA) IS 1973

MAP COORDINATES: MINIMUM X (XMM) IS 0 Y (YMM) IS -70
MAXIMUM X (XMX) IS 27267 Y (YMX) IS 17485

MAP HEADER CONTROL POINTS

ARC POINT	COORDINATE TYPE	CONTROL POINT COORDINATES (DIGITIZER UNITS)	CONTROL POINT COORDINATES (LONGITUDE AND LATITUDE)
SW	X: LONGITUDE Y: LATITUDE	0 (SWX) 0 (SWY)	96 (SWLO) 39 (SWLA)
NA	X: LONGITUDE Y: LATITUDE	290 (NAX) 17485 (NAY)	96 (NWLO) 40 (NWLA)
NC	X: LONGITUDE Y: LATITUDE	0 (NCX) 0 (NCY)	0 (NCLO) 0 (NCLE)
NE	X: LONGITUDE Y: LATITUDE	27070 (NEX) 17465 (NEY)	94 (NELO) 40 (NELA)
SE	X: LONGITUDE Y: LATITUDE	27268 (SEX) 0 (SEY)	94 (SELO) 39 (SELA)
	X: LONGITUDE Y: LATITUDE	0 (SCX) 0 (SCY)	0 (SCLO) 0 (SCLE)

NUMBERED DATA(MAD) IS 0 LENGTH OF MAP FILE(LFP) IS
NUMBER OF (NCH) IS 49 TITLE: KANSAS CITY, KAN-MO 1:250000 QUAD HYDROLOGIC UNITS

NOTE: 1 IN MAP HEADER, SEE LUDA DOCUMENT 10N

SECTION HEADER		1	
SECTION NUMBER(SEC) IS	1	NUMBER OF ARCS IN SECTION(NAS) IS	36
NUMBER OF COORDINATES IN SECTION(NCS) IS	5904	NUMBER OF POLYGONS IN SECTION(NPS) IS	13
LENGTH OF FILE ASSIGNING ARCS TO POLYGONS(LFS) IS	60	SECTION ERROR-FREE INDICATOR(MARK) IS	3

SECTION COORDINATES: MINIMUM X (XMAX) IS 0 Y (YMAX) IS -70
 MAXIMUM X (XMAX) IS 27267 Y (YMAX) IS 17485

END OF SECTION 1 OUTPUT.

MASTER MAP SYMBOL TO POLYGON ATTRIBUTE CORRESPONDENCE TABLE

MASTER MAP SYMBOL	POLYGON ATTRIBUTE CODE
A--	10240005
B--	10240007
C--	10240008
D--	10240010
E--	10240011
F--	10240012
G--	10240013
H--	10270102
I--	10270103
J--	10270104
K--	10280101
L--	10300101

MAP SUMMARY STATISTICS

NUMBER OF POLYGONS PROCESSED THIS MAP IS	13	(13	UNIQUE)
NUMBER OF ARCS PROCESSED THIS MAP IS	60	(36	UNIQUE)
NUMBER OF COORDINATES PROCESSED THIS MAP IS	10668	(11928	TOTAL)

EXTERNAL FILE NAME USED ON D CARD OF RAP RUNSTREAM (FIRST 12 CHARACTERS ONLY): FILE 3

MAP GEOGRAPHIC WINDOW

MAP COORDINATES:	MINIMUM	LONGITUDE IS 93.99989	LATITUDE IS 39.00012
	MAXIMUM	LONGITUDE IS 96.00003	LATITUDE IS 40.00004

The following is a batch runstream which shows the necessary EXEC-8 control language and GRID control cards producing and displaying a master map from a standardized GIRAS data set:

@ASG,TVR	C,U9V,reel#	*Standardized File
@ASG,A	RID*GRID	*Assign Program File
@XOT,OU	RID*GRID.GRID	

REQUESTOR		ORGANIZATION		TRANS ACTION		SPECIAL SUBSET UNITS			MERGER OR SUBST MAP FILE NAME		NO INPUT MAP FILE		MAP FILE NAME		
A	AW	17	BBB	35		36	40	42		44		46		61	GIRAS

EXTERNAL FILE NAME (OR FMPS MODEL NAME)		FILE TYPE UNIT		DICTIONARY OR MASTER MAP NAME		CLIPPING COORDINATES									
D	FILE 4	16	07 C	23		34	37	38	39	40	41	42	43	44	45
						S	GRID CODE	NORTH SECTOR	SOUTH SECTOR	WEST SECTOR	EAST SECTOR				
COORDINATE SYSTEM {						SECTOR	NORTH LATITUDE	SOUTH LATITUDE	WEST LONGITUDE	EAST LONGITUDE					
						GEOGRAPHIC	E	40.1	25.9	96.1	93.9				
						UTM	U	MIN EASTING ZONE	MAX EASTING ZONE	MIN NORTHING	MAX NORTHING				

REFERENCE FIELD RADIUS ACCEPT LABEL ACCEPT VALUE
 a b c d e f g h i j k

a = DIGITIZER b = INTERNAL COMPOSITION RULE c = IP MODEL d = NO SCALING REQUIRED e = MASK SYMBOL f = AUTO SCALING g = NO. OF INTERVALS h = RELATION

*

OF IN

The clipping coordinates and the data set name on the D-Card are taken from the preprocessor output.

An E-Card with one data name is necessary since all preprocessed GIRAS files are written with one attribute value.

The GRID sector rows and columns are calculated from the geographic window, using the method in Section A. (These and the clipping coordinates may possibly be more restrictive than the window if only a subarea needs to be mapped.)

Operational Notes

Preprocessed data may be written to mass-storage files instead of to tape (as is shown in the sample runstream). File assignments need only be changed. The internal (@USE) name, 'B', must be attached to the file in the preprocessor run.

If more than one data set on a GIRAS tape is to be preprocessed in a single runstream, the tape must be rewound prior to each execution of PREPRC/GIRAS. It is not currently possible to stack several preprocessed data sets onto one reel (or one mass-storage file); separate assignments must be made for each.

GIRAS tapes may be available without IBM Standard Labels. In order to process such a tape, use a 'B' option on the @XQT card. This directs the preprocessor to "bypass label processing." In this case no data set identifier will be recoverable; the preprocessor will then write an image of the "FILE~~n~~" input card onto the standardized file. The preprocessor runstream on A-9-9 assumes that the Census County Subdivision data set is written fourth in order on the file (same order as is given on A-9-6). Data may not necessarily be recorded in the same order on other GIRAS files. The user should establish the content and data ordering within any GIRAS file prior to running the preprocessor.

The source cited in footnote (2) gives documentation on the GIRAS file structure, system design, data content and coding. Familiarity with this and any other GIRAS related information available from USGS is recommended. Figure D-1 gives details on the GIRAS File Structure. A run time estimate for processing a map section within a GIRAS data set may be calculated by the following formula:

#SECONDS = (.005 X LFS) + (.00002 X LFS X NCS), where LFS and NCS are defined as in the section header.

08 CENSUS - (DIGITIZED)

° This category consists, presently, of the "DIMECO" county outline file (scale 1:500,000), which contains only geographic coordinate information, that is, no attributes exist on the file in conjunction with the county boundaries. Therefore, only a county master map may be created from this file.

09 COMLUPS FORMATTED TAPES - (DIGITIZED)

° An off-line preprocessor exists to standardize COMLUPS data for mapping in this system. (See "Handling Digitized Data" Section C.)

10 F-CARDS - (DATA + DIGITIZED)

° Allows immediate input of data and polygonal coordinates within GRID runstream (See "F-Cards").

11 "OTHER" DIGITIZED DATA BASES

° This is defined as any foreign data base containing polygonal coordinates, for which some programing is ne
process it in this system.

2) See William B. Mitchell, et al, GIRAS: A Geographic Information Retrieval and Analysis System for Handling Land Use and Land Cover Data, USGS, Geological Survey Paper 1059 (Washington, DC, Government Printing Office) 1977.

It is the user's responsibility to produce system-standard files prior to input to the system. Briefly, he must insure that:

1. All coordinates written out are geographic.
2. The requisite information in the prefix for each feature is present--'master map' symbol, feature type, number of vertices, etc.
3. For a polygon, that the arcs or edges of its boundary are chained such that the region of interest is always to the right (clockwise) or to the left (counterclockwise) of the arcs.
4. The file is properly closed after all features are written out.

The partial program, Figure D2, will help explain what is required.

Also, there are subprograms in the system program file which the user will 'collect' with his own to perform the standardization and coordinate transformation.

Explanation of Variables

The common block, (USERDG) forces consecutive storage arrangement of the variables in it.

HDR - A 14-word header is written out on every standard file. The first two words must be as assigned in the program HDR (3) and HDR (4) will contain some text describing the user must code this text in the "external" on the D-Card in order to pro

IDENT - Receives a master map symbol unique feature.

ITYPE - Feature type.

NVERT - Number of vertices (polygons

USER PROGRAM AND RUNSTREAM

QFOR, IS USER-PREP, USER-PREP

```
COMMON /USERDGR/ HDR(14), IDENT, ITYPE, NVERT, XO, YO,  
$      XMIN, YMIN, XMAX, YMAX, VERTS(2, ...), ATTRIB(...)  
DIMENSION PRE(9), OUT(1176)  
EQUIVALENCE (PRE, IDENT)
```

ANY USER STATEMENTS

```
HDR(1) = 'USER'
HDR(2) = 'PREPRC'
HDR(3) = <SOME USER TEXT>
HDR(4) = <SOME USER TEXT>
```

USER STATEMENTS

C WRITE HEADER ON STANDARDIZED FILE.

CALL INOUT (0, 'B', HDR, 14)

```

: USER STATEMENTS TO READ IN DATA, PERFORM
: COORDINATE TRANSFORMATIONS, CHAIN POLYGON ARCS,
: SET NECESSARY VALUES IN PREFIX, COLLECT ATTRIBUTE
: VALUES, ETC,

```

```

C      SEQUENCE FOR WRITING A POLYGON

```

```

ITYPE = 1
CALL STDIZE ('R',PRE,9,OUT)
CALL STDIZE ('P',VERTS,2*(NVERT+1),OUT)
CALL STDIZE ('B',ATTRIB,NATTRB,OUT)

```

SEQUENCE FOR WRITING AN ARC.

```

1TYPE = 2
CALL STDIZE ('B',PRE,3,OUT)
CALL STDIZE ('B',VERTS,2*INVERT,OUT)
CALL STDIZE ('B',ATTRIB,NATTRB,OUT)

```

C SEQUENCE FOR WRITING A POINT.

```

JTYPE = 3
CALL STDIZE ('R',PRE,2,OUT)
CALL STDIZE ('R',VFRIS,2,OUT)
CALL STDIZE ('R',ATTRIB,NATTRIB,OUT)

```


XO,YO - Interior point coordinates of polygon
 XMIN... - Coordinate extent of polygon
 YMAX
 VERTS - A two-dimensional array, sufficiently large enough to
 contain all the vertices of any polygon in the file.
 VERTS (1, I) = Longitude_I
 VERTS (2, I) = Latitude_I
 OUT - "STDIZE" uses this to buffer the data as it is written
 out
 ATTRIB - Array containing the attribute value(s) for a feature
 NATTRB - Number of attributes per feature

Coordinate Transformation--Digitizer to Geographic

In the event that the user's digitized data originates from source maps in the UTM projection, he may use this sequence at the beginning of his program to set up the transformation:

CALL D2GINT

CALL D2UBLD

D2GINT reads in the fiducial (registration) points for the data, and also the geographic coordinates of the boundary of the source map via:

NAMelist/ FIDUC/

LNG1, LAT1, LNG2, LAT2, LNG3, LAT3,

IX1, IY1, IX2, IY2, IX3, IY3

TOLER

LNG1, LAT1, . . ., LNG3, LAT3 (real) are the geographic coordinates of the fiducials,

IX1, IY1, . . ., IX3, IY3 (integer) are the digitizer coordinates of the same fiducials, given in thousandths of an inch,

TOLER is equal point tolerance in inches.

Three fiducial coordinates are usually necessary to inform D2UBLD of the orientation of the source map.

The user's NAMELIST input should appear immediately after @XQT (unless he reads in other cards prior to the call to D2GINT); e.g.,

```
@XQT,OU USER-PREP
```

```
$FIDUC
```

```
LNG1 = 71., LAT1 = 42., LNG2 = 73., LAT2 = 42.,
```

```

1X1 = 0, 1Y1 = 0, 1X2 = 403, 1Y2 = 34557, 1X3 = 25185, 1Y3 = 0
ORNTX = 0, -1, ORNTY = 1,0
$END

```

CALL DIG2G (GEOG, IDIG, N)

will transform the N pairs of digitizer coordinates in the two-dimensional array, IDIG (integer) into N pairs of geographic coordinates in the array, GEOG. IDIG must be ordered, (X,Y). In his program, the user would declare:

```
DIMENSION GEOG (2,N), IDIG (2,N)
```


where N should be replaced by an integer or a parameter variable.

12 PLOT FORMATTED TAPES - (DIGITIZED)

° An off-line preprocessor exists to standardize PLOT data for mapping in this system. (See "Processing Polygon Digitized Data In Grid System, Section D.)

13 - 99 UNASSIGNED INDICES

Column 19 must contain a single-character internal unit name (which appears on either a @ASG or an @USE Card). For FORTRAN files and FMPS files this must be an numeric entry; for other files, it may be numeric or alpha.




Dictionary

This field is to be used in conjunction with file types 01 through 06 only. For data items arriving without digitized polygonal areas, an appropriate map dictionary must be referenced. The name always begins with a \$ and must correspond to the desired master map name containing the same characters in position 2 through 12 of the name. An example:
POSITION 2

\$TIMBER = DICTIONARY NAME

*TIMBER = MASTER MAP NAME

If the data field references an aggregate area dictionary, the last three characters of the dictionary name must reference the appropriate aggregate area dictionary suffix.



Clipping Coordinates

To minimize the processing time associated with external data, it may be necessary to limit the study area to that which is of interest to the user. This is accomplished through the use of clipping coordinates.

Type of Clipping Coordinates

Column 34 must indicate the coordinate system used as clipping coordinates. The valid entries are 'S' for sector coordinate, 'G' for geographical coordinate system and 'U' for UTM coordinate system. Whichever is indicated will determine the manner in which the remainder of the card is interpreted.

Sector Coordinate System

Columns 37 through 40 must contain the grid code of the clipping coordinate system. The next four fields indicate the northern sector row, southern sector row, western sector column and the eastern sector column. If the same sector is both northern and southern boundary then the same number is entered in both north and south boundary. South boundary row must be greater than or equal to northern sector boundary. Eastern column boundary must also be greater than or equal to the western boundary.

Geographic Coordinate System

The maximum latitude (north boundary) is entered first with decimal point indicated, followed by the minimum latitude (south boundary). Maximum longitude (west boundary), followed by minimum longitude (east boundary), come next. This coordinate system is immediately converted to the sector system upon entering the GRID Processor.

If any portion of a sector is included within the clipping coordinates indicated by the geographic coordinate system, then the entire sector is included. Thus, clipping is along sector borders eventually. Decimal point must be included on all coordinates.

UTM Coordinate System

The minimum UTM easting coordinate (west-boundary) is followed by the UTM zone which contains the west boundary. Next is the maximum UTM easting coordinate (east boundary) and its zone. Minimum northing coordinate (south border) followed by maximum northing coordinate (north boundary) are the last two entries made on this card. Decimal points must be entered or assumed to follow the last digit. UTM is converted to sector coordinate system with the same rules applying here as on the geographic conversion.

EXTERNAL FILE NAME (OR FMPS MODEL NAME)		FILE TYPE UNIT		DICTIONARY OR MASTER MAP NAME		CLIPPING COORDINATES				
1	3	16	18	21	23	34	37	40	43	46
						GRID CODE	NORTH SECTOR	SOUTH SECTOR	WEST SECTOR	EAST SECTOR
D						S	0648	3	5	2
COORDINATE SYSTEM {						SECTOR				
						GEOGRAPHIC				
						UTM				
						NORTH LATITUDE	SOUTH LATITUDE	WEST LONGITUDE	EAST LONGITUDE	
						36	38	41	44	
						G	27.0	29.6	82.0	87.0
						MIN EASTING ZONE	MAX EASTING ZONE	MIN NORTHING	MAX NORTHING	
						39	45	48	54	
						U	28861917	71324817	4378863	4661005

Field Label

The E-card enables field labels to be assigned to each of the input data fields. The names used will eventually be referenced on Q-cards to generate maps. A variable number of E-cards may be used to describe a data file. Generally, once a file has been defined, the set of E-cards is retained by the user for future runs with the same data file.

With the exception of FMPS files and COMLUP formatted tape files E-card entries must list the data items in each record and must appear in the same order as the data appears physically. For FMPS files, the user enters only those items that he intends to map.

1	2	FIELD LABEL	17	FORMAT	26	FIELD LABEL	40	FORMAT	49	FIELD LABEL	63	FORMAT
E		TIMBER OAK		4		SYMBOL		6				8

When using COMLUP formatted tape files the E-card is required but only the field label portion of the card is used. The word REQUIRED placed in this field will be sufficient. The format field is not used.


1	2	FIELD LABEL	17	FORMAT	26	FIELD LABEL	40	FORMAT	49	FIELD LABEL	63	FORMAT
E		REQUIRED										

Format

This field is only used for FORTRAN formatted files. Using a FORTRAN formatted file, the format fields are used to specify the type and size of each input field. Permissible types are:

- A = alpha
- I = integer
- D or F = decimal
- S or X = skip

The values must be placed relative to the system generated decimal point with whole numbers being to the left and decimal portions to the right. For example, if the input file contains two integer fields, each 6 characters long, followed by a space of 3 characters, an integer field of 5 characters and a decimal field of 3 characters, the fields will be filled out as indicated below.



The format for decimal numbers must be described by the total field width which specifies the number of characters, including a sign and/or a decimal point if present, and the field width of the fractional portion, i.e., if the number is 12.3 it might be stored and 123 or 12.3 or +12.3, etc., in which case the format would be D3.1, D4.1, D5.1 respectively. Note that the alpha designator is for a cross-reference by symbol.

F-CARDS EXTERNAL DATA ON CARD-INPUT FILE

Data appearing on F-cards is processed in this system similarly to other external files; the user described format and order of appearance of the data has to be described on E-cards. F-cards allow polygonal coordinates to be input along with any associated attributes. The coordinates must be geographic (longitude, latitude), and all attribute names must precede any coordinates. If no attribute feature appears on the F-cards with the polygonal data, then a cross-reference link must appear; this is needed so the data may be linked to the proper geographic areas in the master map.

Feature Type

The feature type, column 3, pertains to digitized features (if none, leave blank). Use with file type 10 only, never with type 05.

Three types are recognized:

Column 3

- 1 - Closed Polygon. Coordinates must be in clockwise or counterclockwise order; each coordinate pair is ordered longitude, latitude. The last coordinate must be identical to the first.
- 2 - Arc (open polygon)
- 3 - Single Vertex or Point

Data Fields

There are seven data fields on the F-cards, columns 4 through 73. Each field may contain a maximum of 10 characters. In these fields, the user enters either attribute values, polygon coordinates, or cross-reference information.

For every feature which is to be mapped, the user must enter as many attribute values on the F-card as there are field tables on the E-cards. These attribute values must be real numbers. The feature

type code (column 3) is entered only on the first card of each set. F-cards may be used only in conjunction with D and E-cards, which are necessary to define the file, to indicate the type of cross-referencing, and name the dictionary for that cross-reference. Use of digitized data constitutes an immediate form of cross-referencing. A sample runstream showing the appropriate entries on the D, E and F-Cards now follows:

EXTERNAL FILE NAME (OR IMPS MODEL NAME)		FILE TYPE UNIT	DICTIONARY OR MASTER MAP NAME		CLIPPING COORDINATES					
1	3	16	21	34	37	43	49	55		
0	F-CARDS	10		S						
COORDINATE SYSTEM {					SECTOR	NORTH LATITUDE	SOUTH LATITUDE	WEST LONGITUDE	EAST LONGITUDE	
					GEOGRAPHIC	6	39	39	112	108
					UTM	0				
					MIN EASTING ZONE	MAX EASTING ZONE	MIN NORTHING	MAX NORTHING		

1	3	16	21	34	40	46	52
E	REGION		DENSITY				

DATA OR COORDINATE VALUES								
1	3	14	24	34	44	54	64	74
F	1	3	27.6	111.76	39.3	110.8	40.8	108.7
1- FEATURE TYPE								

DATA OR COORDINATE VALUES								
1	3	14	24	34	44	54	64	74
F		40.93	108.22	39.61	111.76	39.3		
1- FEATURE TYPE								

On the D-card, note that "F-CARDS" have been coded in the external file name field--this is not required, but does give a reminder of the data source. File type "10", which indicates F-cards (digitized), has been indicated. No unit name or dictionary name is necessary. Geographic clipping coordinates have been entered. These are necessary even though the user wishes to map his entire file. The E-card specifies that two attributes, "REGION" and "DENSITY" will be associated with each feature. The feature type on the first F-card, column 3, is '1' indicating a closed polygon. The first two data entries are attribute values.

The 3 in the first field goes with the field label Region and the 27.6 in the second field is the density. The remainder are polygon coordinates, continued to the next card.

Another F-card set would follow for the next feature.


See section on Q-cards for an explanation of procedure for mapping this data.

G-CARD MAP DEFINITION

The Map Definition Card provides a unique identification for the map being prepared.

Grid Code

Since sectors of various sizes may have the same row and column designation along with equal names, they are separated by designating a grid code. A grid code is merely a numeric means of separating the various maps, depending on the amount of area covered.



Both the shaded sector and the larger sector have the same sector row and column designation, but cover different area sizes.

The grid code is divided into two parts: level, and lines-per-inch. The level refers to the relative size of the elements within the map. See Table 2, Section A for correspondence between level designation and map scale. The second part, lines-per-inch (8 or 6) is dependent on the configuration of the available line printer equipment. The system can take advantage of this to minimize distortion. At 6 lines-per-inch a map sector is displayed at 120 by 90 elements. At 8 lines-per-inch a map sector is displayed at 120 by 120 elements. It is not possible to create an 8 lines-per-inch map from a 6, or vice versa.

Map Name

This field is used to designate the name of the map being manipulated. The map name field may contain up to 12 alphanumeric characters designating the particular map being manipulated. All alpha map names must begin with a dot (.); names of master maps must begin with an asterisk (*); names of numeric maps must begin with a pound-sign (#); real-valued maps with an equals sign (=); boundary maps with a hyphen (-); and titles and scales with a colon (:). Map names chosen should relate meaningful information such as a real-valued map depicting rainfall for 1973 might be designated =RAIN1973, or a county map designated as *COUNTY.

If a master map *COUNTY was created then an existing dictionary would have the same name except for the first character, i.e., \$COUNTY. The master map name should not exceed 9 characters in length instead of the normal 12 characters. This is to facilitate the use of dictionary aggregate area definitions. A dictionary name is a combination of the 9 characters in the dictionary field in addition to the 3 characters of the Aggregate Area Dictionary Suffixes. The combination comprises the normal 12-character name. If when referencing a dictionary, the last 3 characters are blank, the program assumes that the basic area definitions are being referenced and not the aggregate areas.

Sector Size Reduction

Normally, this field is left blank. If, however, the output sector map is to cover an area larger than the stored sector map, the size of the sector desired should be placed in this box. The first position, column 22, must indicate the method for combining the desired sectors and can contain 'A' or 'M' or 'P'.

'A' stands for average rule; this rule is only valid for numeric and real-valued maps. The values of the map cells to be combined are

first added together and then divided by the number of entries to obtain their average.

'M' represents modal rule; the concerned cells are tested to find the modal value and this value is placed in the representative cell. In the place of 'A', the system will default to the precedence table.

The default values in the table are in descending order as follows:

9876543210AB

CDEFGHIJKLMN

PQRSTUVWXYZ

--+*,\$/()

'P' stands for precedence table entry. All cell values to be combined are assigned a value from the precedence table and then the symbol with highest precedence is chosen for inclusion into the representative cell (See X-card for changing precedence table). For example, if it is desired to reduce sectors into the same 120 x 120 print positions of an output map,

Column 22 = A or M or P

A = Average M = Modal P = Precedence

a sector size of 04 would be entered specifying that the output sector is comprised of four input sectors. Legitimate sector size codes must be the square of a positive integer number.

<u>LINES/INCH</u>		<u>SIZE CODES</u>
6 & 8 2 ²	=	04 4 stored sectors summariz output sector
6 & 8 3 ²	=	09 9 stored sectors summariz output sector
8 4 ²	=	16 16 stored sectors summari output sector

6 & 8 5^2 = 25 25 stored sectors summarized into 1
output sector

6 & 8 6^2 = 36 36 stored sectors summarized into 1
output sector

8 8^2 = 64 64 stored sectors summarized into 1
output sector

All codes can be used for 8 lines-per-inch; only 04, 09, 25, and 36
can be used if 6 lines-per-inch.

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
6	0048			TIMBER										22		27ND29ROW 32COL 35ROW 38COL										42ND44ROW 47COL 50ROW 53COL										57ND59ROW 62COL 65ROW 68COL																																																															

Number Down (No. Dn.)

This field is normally left blank. If, however, it is desired to
perform topic generation or display definition on a strip of sectors
in the north-south direction, the number of sectors in the north-
south direction should be entered in this field.

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
6														22		4										27ND29ROW 32COL 35ROW 38COL										42ND44ROW 47COL 50ROW 53COL										57ND59ROW 62COL 65ROW 68COL																																																					

Sector Row and Column


The two fields designated as sector row and sector column provide a
means of identifying a specific map sector. Normally sectors will be
designated by using only the sector row and column fields. To
reference a second sector, not adjacent in the north-south direction,
use the next sector row and column fields.

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
6														22		612										27ND29ROW 32COL 35ROW 38COL										42ND44ROW 47COL 50ROW 53COL										57ND59ROW 62COL 65ROW 68COL																																																					

Element Row and Column (For Display Purposes Only)

An output map equivalent to the stored map will be generated if the element row and column is left blank. If, however, it is desired to display a sector map whose geographic area does not have the same reference point as that of a stored sector, entries in the element row and column fields can be made. An output map will be generated for output only consisting of portions of each stored sector which falls within the boundaries of the new sector requested.

GRID CODE LEVEL 1PI	MAP NAME	REDUCTION RULE SIZE	SECTOR 27ND29ROW 32COL 35ROW 38COL	ELEMENT 6 12 61 69	SECTOR 43ND44ROW 47COL 50ROW 53COL	ELEMENT	SECTOR 57ND58ROW 62COL 65ROW 68COL	ELEMENT
------------------------	----------	------------------------	---------------------------------------	-----------------------	---------------------------------------	---------	---------------------------------------	---------



NEW SECTOR DISPLAY ONLY

H-CARD TEXT OVERLAY

It is often desirable to overlay short text statements within the body of a map to assist in interpretation of the display. Use of the H-card allows this capability. Any number of H-cards may be used.

Row and Column

The element row and column where the text is to originate are entered in these fields. The entries must all be numeric and right-justified. Note that when using the text overlay option only one sector can be specified in the G-card.

Length in Characters

This field is used to designate the length of the text to be printed. This field must be numeric and can vary from 1 to 12. If a number is specified which is larger than 12, the text will be truncated at 12 characters regardless. If more characters are specified than can be accommodated due to the boundary limits of the sector, the text characters which exceed the sector boundaries will also be truncated.

Text

This field is used to specify the actual text to be displayed on the output topic map. If fewer characters of text are entered than indicated in the "length" field, the remaining field will be filled with blanks on the map. The text begins at the row and column point indicated and extends horizontally to the right.

ROW	COL	LENGTH	TEXT STRING
12	2	12	PULPWOOD

ROW	COL	LENGTH	TEXT STRING

ROW	COL	LENGTH	TEXT STRING


I-CARD TITLE

All maps should have a title. Since new maps do not have titles stored, they must be supplied when generating new maps. This is accomplished by specifying the map name on the "G"-card and the title on the "I"-cards.

Title

The title, Columns 3 through 72 of the I-cards, is an alphanumeric free form entry. Free form means that whatever is placed in this field is used directly on the output maps without modification and, therefore, the field is not restricted by any conventions. These fields should be used to provide a descriptive and unique map title, properly spaced, using the center line as a spacing guide. Examples of possible usage are: notes regarding the data source, a verbal description of the map contents, or any information the user feels will enhance the map.

If the information is the title of a composited map, the text supplied should include a description of what is being combined. A maximum of 30 cards may be used.



J-CARD-SCALE

These cards provide a means for scaling the initial values of data to the symbol display range of the mapping system. (Alternatives are discussed with the Q-card.) A maximum of 35 J-cards can be included for a specific topic.

To avoid weighting the map data as they are being recorded (reserving this role for the compositing expressions or symbol conversions) it is necessary to center the distribution on a common value. The value 5 on the scale 0 to 9 is used for the mean of each factor distribution. Avoid undue influence by extreme variations of data. One method of smoothing in socio-economic data is to state it as per capita values. Another smoothing which is useful when the data are approximately normally distributed, is to compute the standard deviation and use it to control stratification of data.

Category Name

Each name which describes a range of values or a category is entered in columns 3 through 50 of the J-card. These names are not used specifically for reference at any point in the system and, therefore, can be free form. The category names will appear as part of the map heading along with the symbol and associated range of values.

Symbol

The symbol entry is used to enter the map symbol of the category described above. It may be alpha or numeric, however, if it is alpha, the map name has to begin with a dot (.) as the first character.

Thresholds

Each set of threshold values provides the boundaries within which the input data values will be set to a constant map symbol. The lower threshold represents the smallest value which will be set equal to

a constant map value and the upper threshold represents the first value which will not be set equal to this particular map value. Thus, a given number must be equal to or greater than the lower threshold and less than the upper threshold to fall within the category range. It is normal for the upper threshold for one map symbol to be equal to the lower threshold for the next larger map symbol.

If the lower threshold of the smallest category is left blank, the symbol for the smallest category will be inserted for all numbers less than the upper threshold for this smallest category. That is, if the smallest threshold value was 1,000, all values less than 1,000 including negative numbers would be set to the symbol of the smallest category. If a specific number is inserted in the lower threshold of the smallest category, all numbers which are less than this number, will be flagged as an error. The same philosophy holds true for the largest category. All numbers greater than the lower threshold of the largest category will be set equal to the symbol of the largest category unless the field for the upper threshold is filled in. In this case, all numbers greater than the upper threshold of the largest category will be flagged as an error.

The categories defined must cover all possible input data values. If an input value occurs which does not correspond to an established category, an error will be generated.

DESCRIPTIVE TEXT		SYMBOL	THRESHOLDS	
			LOWER (L)	UPPER (U)
1	TIMBER DENSITY LESS THAN 10 PERCENT	1		10.

DESCRIPTIVE TEXT		SYMBOL	THRESHOLDS	
			LOWER (L)	UPPER (U)
2	10 - 50 PERCENT	2	10.	50.

DESCRIPTIVE TEXT		SYMBOL	THRESHOLDS	
			LOWER (L)	UPPER (U)
3	GREATER THAN 50 PERCENT	3	50.	

K-CARD MAP GENERATION BY SYMBOL CONVERSION

The K-card allows for the generation of new maps which may be created from (existing) maps. The name of the map to be created appears in columns 8 through 19 of the G-card. The new map is set equal to the reference map designated in columns 3 through 14 of the K-card. The values of the reference map (which appear above the blanks) may be replaced by the values designated in columns 24 through 67.

Reference Map

The reference map may be either numeric or alpha, or master and may have been previously stored or newly created. Equal map names cannot appear in both the "map name" field of the G-card and the "reference map" field of the K-card, unless a MODIFY transaction is occurring. In all other cases, an error message will be generated.

Mask

The "mas^k" field is used to assign 2 masking maps. The new map will be created with the sixth character in the field being used as both mask and replacing symbol. This field takes precedence over the "conversion symbols" field.

Symbols Conversions

To create new maps from existing maps the symbols of the reference map preprinted on the form are replaced by the designated symbols entered in the blank spaces underneath the preprinted characters. A symbol must be supplied for every symbol of the reference map. If a symbol is present on a reference map for which a new symbol is not supplied, an error message will result.

REFERENCE MAP MASK CONVERSION SYMBOLS

1 3 16 24 32 29

K •FOREST-TYPE• *MASK* - 0 1 1 A B C D E F G H I J K L M N P O R S T U V W X Y Z 0 1 2 3 4 5 6 7 8 9

349009

N-CARD MAP GENERATION BY DICTIONARY SYMBOL CONVERSION

If the desired map to be generated is based upon areas defined in a dictionary, use of the N-cards is required. In this case, dictionary symbols are converted to the desired new symbols or values.

Reference Dictionary

The dictionary to be referenced when creating the new map is entered in columns 3 through 14 of the N-card. The creation of new maps can also reference the aggregate area coding of the dictionary. If, for example, counties were the entities defined in the dictionary, with regions as one of the coded aggregate areas, a new map could be created where the symbols of the aggregate area are converted to the desired symbols of the new map. The new map would then depict data conforming to region blocks.

REFERENCED DICTIONARY OR MASTER MAP			SYMBOL AND VALUE CORRESPONDENCES											
			SYMBOL	1	2	SYMBOL	1	2	SYMBOL	1	2	SYMBOL	1	2
N			WEBSTER											

Symbol

Area symbols are comprised of three characters: a 1-character alphanumeric prefix, and a 2-character alphanumeric suffix. The valid prefix symbols are the same as those listed on the K-card and are seen on master maps. The suffix characters are defined in the dictionary. The symbol characters to be used on the N-card must match the characters assigned to the area in the reference dictionary, i.e., if the area has been designated as "F01" in the referenced dictionary, the symbol assigned on the L-card must also be "F01."

REFERENCED DICTIONARY OR MASTER MAP			SYMBOL AND VALUE CORRESPONDENCES											
			SYMBOL	1	2	SYMBOL	1	2	SYMBOL	1	2	SYMBOL	1	2
N			WEBSTER	F	01	2AC	0	1CT	5	2A9	2	AD	5	

Value

The value replacing the dictionary symbols may be alpha or numeric, but the name of the map to be generated (as specified on the G-card) must follow the appropriate naming convention.

O-CARD MAP GENERATION BY POINTS OR LINES

The O-cards provide the facility of generating maps by defining data points or data lines within the study area with associated values. After all the values have been defined, an equation is used to generate a contour (continuous) or equidistant (proximal) map of the area. The exact outcome of the map depends upon the equation chosen. Note that only one sector may be specified on the corresponding G-card when generating topics by points or lines.

Formula Number

The formula number entry refers to the internal calculations to be performed by the system. There are four possible entries;

- 1 = Continuous generation by points
- 2 = Proximal generation by points
- 3 = Continuous generation by lines
- 4 = Proximal generation by lines

One must be entered in column 16.

Dispersion Global

The dispersion value may range from 0 through 9 and the effect varies as listed below:

- 0 = Point or line has no influence.
- 1 = Normal case. No special consideration.
- 2 = Effect of value is limited to approximately 96 elements.
- 3 = Effect of value is limited to approximately 64 elements.
- 4 = Effect of value is limited to approximately 48 elements.
- 5 = Effect of value is limited to approximately 38 elements.
- 6 = Effect of value is limited to approximately 32 elements.
- 7 = Effect of value is limited to approximately 27 elements.
- 8 = Effect of value is limited to approximately 24 elements.
- 9 = Effect of value is limited to approximately 21 elements.

This specification of dispersion is "global" in that it applies to all points or lines except those for which a separate dispersion has been specified.

a	b	c	SECTOR		ELEMENT		ELEMENT		ELEMENT		ELEMENT	
16	17	18	19 ROW	20 COL	21 ROW	22 COL	23 ROW	24 COL	25 ROW	26 COL	27 ROW	28 COL
76												

a = FORMULA NUMBER b = GLOBAL DISPERSION c = CONVERGENCE UNIT d = LOCAL DISPERSION

Convergence Limit

The convergence limit provides a background value for the created map. This is a non-sealed number. When the dispersion value is set to 1, then the conversion limit would have no effect. A generated map element is given this value whenever, due to the effects of dispersion, the element is not influenced by any of the points of lines. Columns 18 through 21 contain the convergence limit.

Reference Sector Row and Column


The reference sector specifies the map sector to which all point or line coordinates are relative. When this field is blank, coordinates are assumed to be relative to the current sector.

a	b	c	SECTOR		ELEMENT		ELEMENT		ELEMENT		ELEMENT	
16	17	18	19 ROW	20 COL	21 ROW	22 COL	23 ROW	24 COL	25 ROW	26 COL	27 ROW	28 COL
76	9		1	21								

a = FORMULA NUMBER b = GLOBAL DISPERSION c = CONVERGENCE UNIT d = LOCAL DISPERSION

Point/Line Definition (Row and Column)

Values for the point and line map generation are entered in the appropriate positions. If map generation by points is requested, then a starting and ending point must be specified. If map generation by lines is requested, then both the starting row and column fields and the ending row and column fields must be specified. Dispersion is required only if it is desired to be different than the global dispersion. A value is required in all cases.



- Θ +10 +10 Positive Row, Positive Column, Inside
- Ø -10 +10 Negative Row, Positive Column, Outside
- O +10 -10 Positive Row, Negative Column, Outside
- X +100 +130 Positive Row, Positive Column, Outside

Sign Values for Point Entries

Figure 0-1

The row and column entries are a reference to the specific element associated with the data values. The entries to be made are numeric in all cases and, therefore, must be right-justified. If the value to be referenced to a sector all fall within the boundaries of the sector specified on the G-Card, entries do not have to be made in the sign fields. If, however, the data values were collected at points outside the boundaries of the sector specified, a sign indicating a negative direction will have to be supplied in some cases. All points have a row and column designation in relation to the northwest corner of the sector being mapped. The sign fields for rows and columns is used as shown above.

Dispersion (local)

The local dispersion operates the same as the global dispersion except the value is only applied to the specific data value it accompanies. All values must have either a local or global dispersion specified--refer to global dispersion for specific values, columns 46 and 68.

Values

The value of the data corresponding to the row and column location within the sector is entered in the value field. This must always be a numeric entry. However, it need not be right-adjusted if a decimal point is supplied. The value entries may be either scaled or non-scaled. If non-scaled numbers are used, then appropriate J-cards must be supplied with the run.

1
0

SECTOR			ELEMENT		ELEMENT		ELEMENT		ELEMENT	
16	17	18	23 ROW	24 COL	30 ROW	31 COL	38 ROW	39 COL	46 ROW	47 COL
					62	30			27.	
									-40	10
										3 4.

a = FORMULA NUMBER b = GLOBAL DISPERSION c = CONVERGENCE UNIT d = LOCAL DISPERSION

P-CARD GENERATION BY ELEMENT MATRIX

Using the element matrix, P-cards, maps may be generated. The geographic outlines of all areas within a sector have to be placed on a P-card matrix. All elements with equal values must be designated by the same symbols, which can be either numeric or alpha. A preceding G-card then indicates through the name of such a map the presence of numeric or alpha symbols or both. Note that only one sector may be specified on the corresponding G-card when generating maps by element matrix.

To generate maps by element matrix, the area boundaries are placed on a P-card matrix and each area is assigned a symbol. The method of assigning symbols is arbitrary, however, adjacent areas must not have equal symbols. When assigning symbols, equal symbols should be kept as far apart as possible. This rule also applies when crossing sectors. Areas which appear in more than one sector must have equal symbols in each sector, i.e., if a county is designated as "L" and a sector borderline cuts through it, it must be designated as "L" in both sectors. To eliminate problem areas between sectors, it is often wise to assign numeric symbols to all border areas and assign alpha symbols to all other areas, although this is not a system requirement.

When a map dictionary is used, each area is assigned a 3-character symbol: the first character (symbol prefix) is used for display and to define the geographic shape on the P-cards, the second and third characters (symbol suffix) are used to define an area uniquely. Note that such a map will define the geographic shape of the basic area as defined in the associated dictionary and not the aggregate areas. This must be indicated in the name which has to equal the

9-character dictionary name except for the first character. A map of an aggregate area can be generated by reference only and not through the use of the element matrix.

Row Number

The row number field is to be used to designate each individual line within a sector numbered from 001 to 120 for 8 or 10-character-per-inch maps and 001 to 090 for 6-character-per-inch maps. If each line is unique, the numbers 001 through 120 or 001 through 090 will appear in columns 3 through 5 (the start column) of the left-hand cards and in columns 63 through 65 of the right-hand cards. If consecutive lines are identical they may be described on one card using the start and end columns to indicate the row number of the first and last identical row. This option is available for either the left or the right-hand cards.


Print Positions

At any point in the data matrix with the exception of the first data position of each left and right-hand card, a period (.) may be used to indicate the column repetition of the previous data value until a new data value in the same row is encountered. Using this technique, the insertion of a "7" in column 9 and a period (.) in column 10 would yield an entire line of 7's for print positions 1 through 60. (Note that the symbol is not continued through to column 120 and must be redefined on the right-hand card.)

There cannot be any elements unaccounted for when creating a map. Each element must contain a valid character or have a valid character designated through use of the period (.) option. If an element is unaccounted for, an error message will result. Further, all rows must be accounted for, either as unique line entries or through use of the column "start to end" option on both the left-hand and right-hand

cards. A maximum of 120 left-hand and 120 right-hand cards may be used for an 8 or 10 row-per-inch map, 90 left and 90 right for 6-character-per-inch maps.

When assembling the resultant deck, all left-hand cards must precede the right-hand cards (Figure P-1).



Input Sequence

Figure P-1

Q-CARD TOPIC GENERATION BY EXTERNAL DATA

The Q-card is used in conjunction with an external data file defined on D and E-cards. Each of the data fields are defined on the E-cards. A given field which is to be mapped is referenced on the Q-card, and the appropriate action is taken to cause a map of the data to be created.

Once the data fields have been defined, it is necessary to indicate which sectors are to have maps created; the sectors are defined on a G-card. Since the incoming data may encompass more than the specified sectors or less than the specified sectors, two possible situations present themselves:

1. There are more data than required for the specified sectors. In this case, the extra data will be passed over. This would occur if the sectors to be generated were to cover a regional area and the data tape contained information for a much larger area.

2. There is less data than required for the specified sectors. This would occur when the data tape contained only regional data, and the sectors desired covered a much larger area. Under these circumstances, warning messages would be generated for those sectors where there were insufficient data and Ø or blank inserted in the areas depending on whether the topic is numeric or alpha respectively.


Reference Field Label

This 12-character field is used to define the data field of the external data file which is to be mapped. It must correspond to the proper field label supplied on the last previous set of E-cards. It must be non-blank, except in the case where a master map is being created from digitized data. If more than one data field from the external data file is to be mapped in one run, the Q-cards must be

interlaced with G-Cards defining the topic name of the map to be generated, and the sectors to be mapped.

Digitized Data Indicator

Placing a mark in this position (Column 16) informs GRID that the attribute to be mapped comes from a GRID-standard digitized data set or F-Cards.



Proximity, Service Radius and Accessibility Maps

Often data is available which is not continuous across an area and can only be represented as discrete points (incidences). With radius and corridor mapping the user can represent these occurrences as either a point or as a circular area. An example of a point might be the occurrences of births, where proximity is not important. On the other hand, an airport should have a service radius associated with it. Another form of proximity could be a service corridor for highways or electrical power lines. With the use of radius and corridor options the user may automatically produce these service areas given the location of the incidence. The field in columns 19 - 30 is used to determine the radius of the service area and should be expressed in miles. A name appearing in this field must have been previously defined on the preceding E-Card sequence and will be used for the local radius value. A floating point number will serve as a global radius value for all the points or areas in the digitized file.

Internal Composition Rule

A decision must be established as to which values appear in the intersections of services radii and corridors; this raises the need

'+' Additive rule (real-valued only). Used to create proximity maps. Not legal for corridors. The intersection of several circular regions will have as its value, the sum of the values of the intersecting regions.

'X' Use the maximum value (real, numeric).

'Ø' (Blank) Use the last value in (all map types).

If data is a SIMPDX or FMPS file, then the user must enter the LP model number. Up to 20 LP models are allowed in GRID.

Normally the data values from the external data file are scaled as defined on the J-Cards prior to map generation. In special cases, the data values to be used in creating maps will reside within the range of 0 through 9. Under these circumstances, topic scaling is not required and an "X" is placed in column 39 of the Q-Card to indicate this.

Mask Symbol

A-Q-3

Auto-Scaling and Number of Intervals

Generally, external data will not be in single-character form, suitable for display; more often, it arrives as real or floating

point values which must be scaled.

The user may elect to have the system scale his data as a map is being created, rather than to pre-specify scaling intervals (J-cards). Two options are available--equal interval scaling, and scaling by the technique of nested means. These are selected by placing the appropriate character in column 43.

'E' = Equal intervals

'N' = Nested means

The user then codes the number of intervals in columns 45 through 46 in a way consistent with his option:

'E' - If equal intervals are selected, just code the number of intervals. Up to 32 are allowed.

'N' - The nested means procedure first calculates a mean, and then recursively calculates the mean of all data which is less than, and of all data which is greater than the mean just calculated--up to a depth of five. Thus, $2^6 - 1$ means may be calculated and $2^6 (=32)$ intervals defined. For nested means, code the maximum depth of recursion (1 through 5).



Reference Accept Label and Value

Occasionally the user may want to map an attribute for a given area conditionally, depending upon the value of some other attribute of the area. (The dictionary cross-reference symbol is often used as the determining attribute.)

In this case, the user would enter the name of the determining attribute (name must appear on E-cards) in columns 48 through 59, and the value to which it is computed in columns 63 through 70 (this value

must be numeric). In column 61 he enters a relation-code for the type of comparison. The codes are:

'E' equal to

'L' less-than

'G' greater-than

'N' not-equal-to

R-CARDS MAP COMPOSITION

R-Expressions

Map composition, i.e., producing a map as a function of several "layers" or maps, is accomplished in this system with the use of R-cards, which allow the user to define a composite map by means of arithmetic, or conditional (IF...THEN...ELSE) expressions (collectively called "R-expressions") involving up to ten maps. The composition may be done in stages if more than ten maps are needed. Changing the "color" of a given map, that is, transforming its symbols into different symbols can also be done. R-cards are essentially free format, although only the first 72 columns are significant and blanks should separate the "words" in the statements.

Since the R-expressions are evaluated for each cell, maps involved in a composition, including the one being defined, must all have the same grid code.

GRID recognizes five types of maps, indicated by the first characters of their names. The resultant types of the values of R-expressions must be consistent with the type of the map being defined, i.e., numeric maps receive "NUMERIC" values, real-valued maps receive "REAL" values, etc.

Examples:

1. Suppose that two real-valued maps, =POP-TRC (population by census tract) and =INC-TRC (aggregate income by census tract) exist; and it is desired to produce a map showing per capita income by tract, =PERCAP. Then the following sequence could be used:

G . . . =PERCAP

R $[=INC-TRC] / [=POP-TRC];$

Note that R-expressions are terminated by semicolons, and that map names are enclosed in square brackets, since names with embedded spaces are allowed (master map aggregates).

2. Invert the coloring of the numeric map, #XYZ:

```
G . . . #XYZ-NEW
```

```
R      10 - [#XYZ];
```

3. Produce a numeric map, #ABC, which is colored as follows:

'9' - privately owned timber land

'6' - private range*

'3' - public timber

'1' - other land

given the map, #LAND such that

'6' - denotes timber

'7' - denotes range

and the map, #OWNERSHIP such that

'1' - denotes public

'2' - denotes private

Solution:

```
G . . . #ABC
```

```
R      IF [#LAND] EQL '6' THEN IF [#OWNERSHIP] EQL '2'
```

```
R      THEN '9' ELSE '3'
```

```
R      ELSE IF ( [#LAND] EQL '7' AND [#OWNERSHIP] EQL '2')
```

```
R      THEN '6' ELSE '1';
```

Equivalently:

```
G . . . #ABC
```

```
R      IF [#OWNERSHIP] EQL '1' THEN
```

```
R      IF [#LAND] EQL '6' THEN '3' ELSE '1';
```

```
R      IF [#LAND] EQL '6' THEN '9';
```

```
R      IF [#LAND] EQL '7' THEN '6' ELSE '1';
```

And more simply:

G. . . #ABC

```
R      IF [#OWNERSHIP] EQL '1' AND [#LAND] EQL '6' THEN '3';  
R      IF [#OWNERSHIP] EQL '1' AND [#LAND] NEQ '6' THEN '1';  
R      IF [#LAND] EQL '6' THEN '9';  
R      IF [#LAND] EQL '7' THEN '6' ELSE '1';
```

When there are several conditionals, a value is returned as soon as one is satisfied.

If the R-expressions are insufficient to cover all the combinations of values actually appearing in the factor maps, a warning will be issued and a unique null value will be returned. A final "ELSE" clause insures that a significant value will always be returned.

Literals in R-Expressions

Numbers are written as you would ordinarily write them. A number in scientific notation; e.g., 1.5×10^{-2} would be written as 1.5E-2.

Values for alpha, numeric, and master maps are enclosed in quotes; e.g., 'P', '5', 'XZ4', respectively.

Data Types

Every R-expression has a type. The type of any arithmetic expression is "REAL". The types of all branches of conditional expressions must be the same. Exception: "REAL" and "NUMERIC" values may be used interchangeably.

The only data types which may participate in an arithmetic expression are "NUMERIC" and "REAL". All data types, including "MASTER", participate in relations (EQL, NEG, etc.); however, the values must be comparable.

As was seen in the examples, R-expressions may be constructed using arithmetic operators, conditionals, or both. The basic language elements (operators, connectives, and functions) are shown at the

AVAILABLE OPERATORS, CONNECTIVES AND FUNCTIONS

Data Types: Alpha, Numeric, Real

1. Logical Operators

NOT

AND

OR

2. Regional operators (all data types)

EQL (equal to)

NEQ (not equal to)

GEQ (greater than or equal to)

GTR (greater than)

LEQ (less than or equal to)

LSS (less than)

3. Arithmetic operators (use with numeric and real data types only)

** (exponentiation)

* (multiplication)

/ (division)

+

(plus)

- (difference, or negative sign)

4. Functions

A = Alpha

N = Numeric

R = Real

<u>Name</u>	<u>Number of Arguments</u>	<u>Description</u>
ABS	1 (R)	Absolute value
MAX	2 (A,N,R)	Maximum
MIN	2 (A,N,R)	Minimum
EXP	1 (R)	Exponentiation, base e
SQRT	1 (R)	logarithm, base e
PRECED	1 (A,N)	precedence function (see 'X'-Card chapter)
ALPHA	1 (M)	Master to Alpha

5. Literal Keywords

NULL Refers to background symbol of any map generated by
digitized data routines

DESCRIPTION OF GRAMMAR

<R-EXPR> = <COND>;|<ARITH>;
 <COND> = IF<BOOLEAN>THEN VALUE|IF <BOOLEAN>THEN<VALUE>ELSE<VALUE>
 <BOOLEAN> = <BOOL-TERM>|<BOOL-TERM> or <BOOLEAN>
 <BOOL-TERM> = <BOOL-FACTOR>|<BOOL-FACTOR> and <BOOL-TERM>
 <BOOL-FACTOR> =NOT <BOOL-FACTOR>| (<BOOLEAN>)| <RELATION>
 <RELATION> = <ARITH> <REL-OP> <ARITH>|<SYMB> <REL-OP> <SYMB>
 <SYMB> = <E-SYMB>|PRECED (<E-SYMB>)
 <E-SYMB> = Literal|Map Name (see text)|NULL
 <VALUE> = <COND>| <ARITH>| <E-SYMB>
 <ARITH> = <TERM>| <TERM> <PLUSOP> <ARITH>
 <TERM> = <FACTOR>| <FACTOR> <MULTOP> <TERM>
 <FACTOR> = <PRIMARY>| <PRIMARY> ** <FACTOR>
 <PRIMARY> = number (see text)| <E-SYMB>| <FUNCTION>| -<PRIMARY>|
 (<ARITH>)
 <FUNCTION> = <FNAME> (<ARGLIST>)
 <ARGLIST> = <ARITH>| <ARITH>, <ARGLIST>
 <FNAME> = function name (see table)

* Note: The letter "O" is not a legal symbol for any kind of map.
 All legal symbols are listed with the "K" card.

SAMPLE USAGE OF OPERATORS, CONNECTIVES AND FUNCTIONS

<COND>

```
IF [#LAND] EQL '5' AND ( [#SOIL] EQL '1' OR [.TBR]  
    EQL 'A') OR [#LAND] EQL '0' THEN 'A'  
    ELSE 'B'
```

<BOOLEAN>

1. [#LAND] EQL '5' AND ([#SOIL] EQL '1' OR [.TBR] EQL
 'A') OR [#LAND] EQL '0'
2. [#LAND] EQL '5' AND ([#SOIL] EQL '1' OR [.TBR] EQL 'A')
3. [#LAND] EQL '0'
4. [#LAND] EQL '5'
5. ([#SOIL] EQL '1' OR [.TBR] EQL 'A')
6. [#SOIL] EQL '1' OR [.TBR] EQL 'A'
7. [#SOIL] EQL '1'
8. [.TBR] EQL 'A'

<BOOL-TERM>

1. [#LAND] EQL '5' AND ([#SOIL] EQL '1' OR [.TBR] EQL 'A')
2. [#LAND] EQL '0'
3. [#LAND] EQL '5'
4. ([#SOIL] EQL '1' OR [.TBR] EQL 'A')
5. [#SOIL] EQL '1'
6. [.TBR] EQL 'A'

<BOOL-FACTOR>

1. [#LAND] EQL '5'
2. ([#SOIL] EQL '1' OR [.TBR] EQL 'A')
3. [#LAND] EQL '0'
4. [#SOIL] EQL '1'
5. [.TBR] EQL 'A'

<RELATION>

1. [#LAND] EQL '5'
2. [#SOIL] EQL '1'
3. [TBR] EQL 'A'
4. [#LAND] EQL '0'

<EXPR>

1. [#LAND]
2. '5'
3. [#SOIL]
4. '1'
5. [TBR]
6. 'A'
7. '0'

Boolean expressions are evaluated as follows:

1. Relational expressions are evaluated for their truth or false value.
2. NOT operations are evaluated for their truth or false value.
3. AND operations are evaluated for their truth or false value from right to left.
4. OR operations are evaluated for their truth or false value from right to left.

Arithmetic expressions are evaluated as follows:

1. Arithmetic primaries are evaluated first.
2. Exponentiation operations are evaluated second.
3. Multiplications and divisions are evaluated third from right to left.
4. Additions and subtractions are evaluated fourth from right to left.

S, T, AND U CARDS STATISTICAL REPORTS

Introduction

Statistical reports can be generated in the same runstream without the need for a separate pass. The values entered into the statistical routines will be the element values from the selected maps.

When using this feature it should be remembered that the data being dealt with have a geographic distribution. Therefore, to perform statistics on absolute figures instead of geographic figures will introduce substantial error. For example, if data are available on county population, these data are best processed in tabular form external to GRID. If, however, the population data are expressed as people per square mile, then these data can be automatically mapped and combined with other topics in obtaining statistical reports.

S-CARD REPORT TITLE

The statistics report title, columns 3 through 72 of the S-cards are alphanumeric free form entries. A maximum of 3 title cards may be used for a given statistical report. The input information should be properly spaced using the center line as a spacing guide. The title is not stored in the system and must be supplied whenever a statistical report is generated.

	TEXT	CENTER	TEXT
8	REGRESSION ANALYSIS	EDUCATION	WITH AGES, SEX AND INCOME

T-CARD STATISTICS PARAMETERS

One T-card must be supplied when requesting a statistical report. It is possible to generate a statistical report and at the same time generate a map for the sector indicated on the G-card.

Type

Six types of statistical reports are available:

- FP = Frequency Polygon
- HI = Histogram
- MH = Multivariate Histogram
- MF = Multivariate Frequency
- MR = Multiple Linear Regression
- SR = Stepwise Multiple Regression

The appropriate two letter combination of the type of report desired must be entered in columns 3 and 4 of the T-card.

A frequency polygon request will plot the frequency of occurrence of each type of element symbol. The abscissa (X-axis) will display the N possible categories, and the ordinate (Y-axis) will plot the cumulative occurrence from 0 to 100 percent.

A histogram request will plot the frequency of occurrence of each type of element symbol. The abscissa will display the n possible categories, and the ordinate will present a bar chart of the frequency of occurrence.

A multivariate histogram or multivariate frequency request will provide a cross-tabulation of two topics displaying the frequency of occurrence of each symbol. It is, therefore, possible to determine how many times a 3 occurred in one map when a 5 occurred in another map.

The above four statistics may be obtained from alpha, numeric or master maps.

STATISTIC TYPE 1	LIMIT VALUE 11	DEPENDENT OR MULTIVARIATE MAP 17	STARTING POINT 31 ROW 24 INC 7 34 COL 11 INC 7		45 MASKING TOPIC	MASK SYMBOL 58	EXCLUDED SYMBOLS 62 64 70		
------------------------	----------------------	--	--	--	------------------	----------------------	------------------------------	--	--

1 - GRAPH SUPPRESSION

Multiple Linear Regression produces a regression analysis of independent maps indicated on U-cards explaining the dependent map on this card.

Stepwise Multiple Regression request will provide a regression of the maps indicated on the following U-cards as independent maps to the map referenced on this card. Maps will be entered in the order of significance unless forced into the model.

No Graph

When producing either frequency polygons, histograms, or multiple frequency and histograms, if the maps do not involve a master map then a graph will also be produced showing pictorially the statistical distribution. By checking column 6 with any character this graph will be suppressed from printout. Because of a possibly enormous set of combinations when using master maps, the graphs will be suppressed.

Limit Value for Stepwise Regression

The limit value is used when a stepwise regression is requested and is the significance level for removing a variable from the regression, i.e., a variable whose percentage contribution to the sum of squares is less than this number will not be included in the analysis, unless forced to be. See U-card--Force Option.

Dependent or Multivariate Histogram Map

The dependent map name for use in either multiple linear stepwise multiple regression or the name of the map for cross-tabulations in a multivariate histogram request is entered in columns 17 through 28.

STATISTIC TYPE 1	LIMIT VALUE 11	DEPENDENT OR MULTIVARIATE MAP 17	STARTING POINT 31 ROW 24 INC 7 34 COL 11 INC 7		45 MASKING TOPIC	MASK SYMBOL 58	EXCLUDED SYMBOLS 62 64 70		
------------------------	----------------------	--	--	--	------------------	----------------------	------------------------------	--	--

1 - GRAPH SUPPRESSION

Starting Point

The starting point consists of a row and increment, and a column and increment. This is the point at which selection of elements for any of the statistical reports begin. The row and column entries may vary from 1 to 120 and the increment may vary from 1 to 99. The row and column increment entries control the iteration loop of the starting row and column to determine the elements to be selected. An entry of 10 in both row and column fields and 20 in each of the increments fields would result in elements 10-10, 10-30, 10-50, 10-70, 10-90, 10-110, 30-10, 30-30, etc., being selected for a total of 36 elements per map. This is used in "sampling" map data.

Masking Map

In a number of statistical problems, it is desirable not to allow certain areas to have an influence on the report being generated. This occurs, for example, when working with sectors which border the oceans. Sampling a median income topic map across an entire sector which contained 50 percent water would bias the output report severely. The masking map allows reference to another map which can mask out areas not desired in the analysis. In a sense, it can be considered an override to the starting point iteration.

Masking Symbol

Any valid symbol can be entered in this field. The masking symbol works in conjunction with the masking map and cancels the starting point element iteration whenever the sampled element symbol matches that of the masking symbol entry. If water was represented by the symbol "(" then an entry of this symbol in the masking symbol column 59 would eliminate any reference to this area in the statistical run. If the masking map is a master map then this masking symbol applies to the first of the three master map symbols only.

Excluded Symbols

Within the map being analyzed for statistics there are often areas which are not desirable to be included into the statistical report. Columns 62-64, 66-68 and 70-72 are three fields which can indicate three symbols to be excluded from any report. For non-master map entries only the first column of each field is valid. If this symbol appears on the multivariate map then that cell is disregarded from the statistics report.

U-CARD INDEPENDENT MAPS

The U-card is used only when a multiple or stepwise regression has been requested on a T-card. Up to five U-cards may be used for specifying the independent maps to be used in the regression run.

Independent Map

The independent maps to be used in a multiple regression or stepwise regression are entered on U-cards. Up to five independent maps per U-card may be entered providing a total of 25 possible independent maps to be used for a statistical report request.

Force(F)

An entry in this field forces the use of the respective independent map. A character from 0 to 7 may be used

Blank or 0 = Free

1-9 Order entered

INDEPENDENT VARIABLES OF REGRESSION (F = FORCE OPTION FOR STEPWISE)				
1	2	3	4	5
INDEPENDENT MAP	INDEPENDENT MAP	INDEPENDENT MAP	INDEPENDENT MAP	INDEPENDENT MAP
AGE	SEX-RATIO			

V-CARD STUDY AREA LEGEND

Whenever a study area is established, there is often the need to supply notes to the generated maps which are pertinent, not just to a single map, but to all maps within the study area. If this need arises, the Study Area Legend cards provide the capability.

Legends

The Study Area Legend, columns 3 through 72 of the V-cards, is an alphanumeric free form entry. Free form means that whatever is placed in this field is used directly on the output maps without modification. A maximum of 3 legend cards may be used for a given run. The input should be properly spaced using the center line as a spacing guide. This legend is not stored in the system and must be supplied whenever it is desired to see it appear on generated maps.

	TEXT	CENTER	TEXT
1	SOURCE	BUREAU OF THE CENSUS	US DEPARTMENT OF COMMERCE

Often a previous G-card will define a multitude of sectors to be processed, but only a few key positions might be needed for display. This is especially true for demand mode processing. The W-card is designed for selectively displaying portions of the area defined on the last G-card. A maximum of one sector can be requested for each W-card. No boundaries may appear on a window display.

Sector Position

Columns 3 through 5 and 6 through 8 indicate the sector row and column which contains the upper left cell of the window of interest. The sector row and column must be one of the sectors referenced by the previous G-card.

Element Position

This field indicates the actual cell row and cell column to be the upper left of the window display. With the two coordinates, sector position and element position, the system is able to uniquely define the starting position of the display.

Dimensions

Columns 17 through 19 should contain an integer indicating the number of rows to print. The maximum value for this field is 120. Columns 20 through 22 contain an integer indicating the columns to print. The maximum value for this field is also 120. Columns 20 through 22 also have a minimum value of 7. The window to be displayed can cross sector boundaries in both directions.

Grey Tone

If a numeric map is to be displayed, and a grey tone is to be shown in place of the numeric characters, an X can be placed in column 24.

Exercising this option will yield a display with the same geographic

to its numeric value. The conversion to a grey tone will be in the following manner:

<u>Numeric</u>		<u>Grey Tone</u>
<u>Map Value</u>		<u>Value</u>
Ø	=	Blank
1	=	.
2	=	-
3	=	+
4	=	=
5	=	0
6	=	0
7	=	Ø
8	=	⚡
9	=	✱

To change this combination of symbols, refer to Y-card.

Display Symbol Conversion

The character set of the requested map may be changed before displaying it through use of the display symbol conversion fields. A new symbol or character may be inserted for each symbol which exists on the requested map.

All available symbols are indicated above the symbol conversion field. Any changes of characters can be indicated by placing the symbol below the preprinted one. Those fields which do not have an entry will be retained in their original state. If it is desired to have blanks appear, the insertion of a period (.) will suppress a given symbol and cause blanks to appear wherever the symbol is used.

Using this technique, it is possible to generate both upper and lower map thresholds. If, for example, a given numeric map has a range of

0 - 9, and it is desired to display only the values 3 through 6, with blanks being displayed with the remaining values, the example below depicts how this can be easily accomplished.

SECTOR		ELEMENT		DIMENSIONS		GRAY	DISPLAY SYMBOL CONVERSION																																					
1	2	3	4	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50
1	2	3	4	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50

This will generate a lower threshold of 3 and an upper threshold of 6. Special displays can be generated using the same capability by setting the numeric values equivalent to alpha values or numeric values. For example, if a road runs through a sector and it is desired for a special report to designate the road in a manner more easily read than the normal numeric distribution map, the values could be adjusted using this feature on the output.

Negative maps or inverted maps can easily be generated by referencing the values of the output map using the following option:

SECTOR		ELEMENT		DIMENSIONS		GRAY	DISPLAY SYMBOL CONVERSION																																					
1	2	3	4	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50
1	2	3	4	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50

If a map is desired with more contrast but with few categories, a symbol conversion can be used in conjunction with the grey-tone option. An example of this would be a symbol conversion setting 1, 2 and 3 equal to 1; 4, 5, and 6 equal to 5; and 7, 8 and 9 equal to 9.

X-CARD PRECEDENCE TABLE CHANGE

When reducing maps as indicated on the G-card, columns 22 through 24, if a 'P' is entered in column 22 then sector size reduction is performed through the use of the precedence table. This system has a default setting for this table, but often this may not fit the requirements of the user. Through the use of the X-card, a user may change the values of this table. The default values in the table are in descending order as follows:

9 8 7 6 5 4 3 2 1 Ø A B
C D E F G H I J K L M N
P Q R S T U V W X Y Z
- = + * , \$ / ()

There are 44 entries in this table, note that the letter 'O' is not a valid symbol.

Precedence Ordering

From columns 3 through 46 enter the new precedence order in descending order of importance. All 44 symbols should be entered, with none entered more than once.

HIGH PRECEDENCE ORDERING LOW
ABCDEFGHIJKLMNPQRSTU VWXYZ 0 1 2 3 4 5 6 7 8 9 = + * , \$ / () -


Y-CARD CHANGE OVERPRINT COMBINATION

When W or Z cards are requested, the user has the option to request a grey tone output for numeric maps. Some users find that the combination of 3 characters which this system uses are not satisfactory to their needs. Through the Y-card a user may change the actual symbols used as overprints. This system has some standard combinations which it defaults to, if none are indicated.

These are:

0	prints	blank
1	prints	.
2	prints	-
3	prints	+
4	prints	=
5	prints	0
6	prints	0. overstrike
7	prints	0/ overstrike
8	prints	0+ overstrike
9	prints	0+X overstrike

When changing these values, enter any 3 or less symbols in the indicated columns.



Z-CARD MAP DISPLAY

All maps, dictionaries, and glossaries which are to be presented for display must have a Z-card supplied. It is, therefore, possible to generate intermediate maps for statistical purposes without the necessity of displaying them. Before the map is printed, a last opportunity is available to modify it for display purposes. For display without modification the Z-card is supplied behind the appropriate G-card without additional parameters.

An 'X' in column 2 indicates this is a multiple overlay border card.

The symbol conversion codes are not used on a multiple card.

Note: To display a glossary of the map file specified on the A-card, a G-card must be supplied with the keyword of "GLOSSARY" in columns 9 through 16. A glossary depicts the following information about the map file.

RECORD	GRID	LINE/	MAP	SECTOR	CREATION	
NUMBER	CODE	INCH	NAMES	ROW COL	DATE	REFERENCE

Boundary Overlay Map

If it is desired to overlay the map being displayed with boundaries of another map, such as State boundaries on a county map or county boundaries on a Forest map, then an entry must be made in columns 3 through 14 of the Z-card. The name of the overlay map has to be entered here and a boundary symbol must be placed in columns 16 through 18.

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
		OVERLAY MAP		OVERLAY MAP SYMBOLS		BASE MAP SYMBOLS		a b c		DISPLAY SYMBOL CONVERSION																				PLOT SCALE																																																																					
		COUNTY		[Symbol]		[Symbol]		[Symbol]		[Conversion Table]																				[Scale]																																																																					

a = GRAY TONE b = MASK SYMBOL c = AUTO TRANSLATION

Overlay Map Symbols

If the boundary overlay map field is used, up to 3 overprint combination symbols can be entered in columns 16 through 18. These

symbols will be used to define borders between areas of the overlay topic, such as State borders. If these borders are to appear blank, a period (.) must be entered in column 16. If the border is to be plotted on an X-Y plotter, a (\$) must be entered in 16.

Base Map Symbols

If symbols are placed in columns 20 through 22, each geographic area of the map specified in the preceding G-card is separated using this overprinted combination between it and adjacent areas. The same rules apply, as above, for blank borders and plots. If a plot is asked for in either column 16 or 20 with a dollar sign (\$), no bordering will occur on the printed copy. Columns 73 through 78 contain the scaling factor for the plot.

For example,

- 1. = Same size as print 2. = Twice as big
- .5 = 1/2 as big

The actual size of the map is not changed to facilitate the use of the boundary symbol. To obtain a border, the left-most and top-most characters of each geographic area are set equal to the specified symbols.



Grey Tone

If a numeric map is to be displayed, and a grey tone is to be shown in place of the numeric characters, an X can be placed in column 24.

When this option will yield a display with the same geographic symbols whose intensity is approximately proportional to its numeric value. The conversion to a grey tone will be in the following manner:

<u>Numeric</u>		<u>Grey Tone</u>
<u>Map Value</u>		<u>Value</u>
0	=	Blank
1	=	.
2	=	-
3	=	+
4	=	=
5	=	0
6	=	0
7	=	0
8	=	0
9	=	0

However, the combination of symbols used to produce the grey tone values may be modified if desired by using the Y-card.

Mask Symbol

If a non-blank character is placed in column 25, the system will attempt to match this character with the sixth character of all masking maps in the system (.MASK/). If the match is successful, then all instances of the coded character appearing in the mask map will be changed to null and the resultant mask will overlay the map being displayed.

Should no matching mask map be found, an error message will be issued and display will be inhibited.

Auto Translation


Entries in this column, column 26, apply only to numeric (#) or real valued (=) maps which are to be displayed. The values in a real valued map must always be transformed into single-character symbols before display is possible.

The valid entries and their meanings are:

A-Z-3

- ## Display Symbol Conversion

Using this technique, it is possible to generate both upper and lower map thresholds. If, for example, a given numeric map has a range of 0-9, and it is desired to display only the values 3-6 with blanks being displayed with the remaining values, this can be easily accomplished by designating the map values.



example, if a road runs through a sector and it is desired for a special report to designate the road in a manner more easily read than the normal numeric distribution map, the values could be adjusted using this feature on the output.

Negative maps or inverted maps can easily be generated by referencing the values of the output map using the following option:

OVERLAY TOPIC		OVERLAY TOPIC	BASE TOPIC	BASE TOPIC	DISPLAY SYMBOL CONVERSION																										PLOT SCALE								
1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0
1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0

1 GRAY TONE 2 MASK SYMBOL 3 AUTO TRANSLATION

Multiple Overlay Boundaries

Multiple Overlay Boundaries may be produced by entering a mark in column 2 of subsequent Z-cards. When this is requested card columns 24 through 80 are not used. The multiple boundary takes precedence over those boundaries mentioned on the previous Z-card. For example, if county boundaries were requested on a Z-card, and immediately following this Z-card request another Z-card were entered with column 2 non-blank and States boundaries requested, the State boundary would be seen when it coincided with county boundaries.

OVERLAY MAP		OVERLAY MAP	BASE MAP	BASE MAP	DISPLAY SYMBOL CONVERSION																										PLOT SCALE								
1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0
1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0

1 GRAY TONE 2 MASK SYMBOL 3 AUTO TRANSLATION

\$-CARD CSF\$ REQUEST

The Dollar card permits the system user to submit certain control statements in field data for interpretation and processing during program execution rather than from the runstream. The allowable control image statements are limited to the 15 which are executable by a call to CSF\$. The system calls ER TRAN to pass the image to CSF\$. All options and fields must conform to the formats indicated in the Univac Program Reference Manual.

Text

Beginning in column 3 and extending through column 63, the control statement must appear. Column 3 must have an '@' symbol designating this image as an EXEC 8 statement.

Allowable CSF\$ images are:

@ADD	@CKPT	@RSPAR
@ASG	@FREE	@RSTRT
@BRKPT	@LOG	@START
@CAT	@MODE	@SYM
@CKPAR	@QUAL	@USE

11 ~~Use A-1, EXTER.~~ TEXT

PROGRAM MESSAGES

Program messages are printed whenever there are problems which have been detected during execution of the Resource Analysis Procedure or when it is desired to bring to the user's attention certain uncommon occurrences which are noteworthy. Generally, the messages are self evident; however, further explanation may prove helpful at times. This chapter presents all the RAP system Error and Warning Messages and Run Stop notifications with further explanations.

ERRORS AND WARNINGS - EDIT PHASE

ERROR 1 INVALID FIRST CHARACTER IN ABOVE CARD, CARD
 IGNORED

Column 1 has a character which cannot be recognized as a valid RAP card type.

ERROR 2 G-CARD MISSING, ABOVE CARD IGNORED

An action on a map was requested, but was not preceded by a G-card, or the preceding G-card was in error.

```

ERROR      3  '*****' ALREADY GENERATED, ABOVE CAP
            IGNORED

```

A topic generation following a G-card can only be specified by one type of card from the set: K, N-U; or a G-card is missing.

ERROR 4. COLUMN 58 DIFFERS FROM PREVIOUS A-CARDS, CARD
IGNORED

An input map file was assigned on tape 7 and column 58 of

- the A-card was marked, or no input map file was assigned on tape 7, but column 58 of the A-card was not marked.
- ERROR 5 MAP FILE '*****' PROCESSED, FILE NAME
INCORRECT
- The map file name of the input file or, in case of "no input tape," of the first request differs from the map file name indicated in columns 61 through 72 of the A-card.
- ERROR 6 TRANSACTION '*****' INVALID, CARD IGNORED
- The transaction code on the A-card was misspelled.
- ERROR 7 GRID CODE MISSING, CARD IGNORED
- The B-card or G-card does not indicate any grid code in columns 3 through 7.
- ERROR 8 INCORRECT OR MISSING DICTIONARY NAME
- The dictionary name on the B-card was either not filled in or does not start with a dollar sign in column 9.
- ERROR 9 'DELETE' HAS BEEN SPECIFIED, ABOVE CARD IGNORED
- Under a "delete" transaction, no C-cards need be supplied, as the entire dictionary will be destroyed.
- ERROR 10 NONNUMERIC CODE FOUND FOR SEARCH FACTOR,
CARD IGNORED
- The B-card shows a nonnumeric character in column 26 for the search factor. Enter a number between 1 and 9.
- ERROR 11 AREA CODE MISSING, CARD IGNORED
- The area code in column 3 through 14 of the C-card is missing.
- ERROR 12 AREA SYMBOL MISSING, CARD IGNORED
- The area symbol in columns 16 through 18 of the C-card is missing.
- ERROR 13 SECTOR ROW INCORRECT, CARD IGNORED
- The sector row designation in columns 20 to 22 of the C-card is less than 1 or is nonnumeric. Enter a number between 1 and 999.

- ERROR 14 SECTOR COLUMN INCORRECT, CARD IGNORED
The sector column designation in columns 23 to 25 of the C-card is less than 1 or is nonnumeric. Enter a number between 1 and 999.
- ERROR 15 ELEMENT ROW INCORRECT, CARD IGNORED
The element row designation in columns 27 to 29 of the C-card is less than 1 or greater than 120. Enter a number between 1 and 120.
- ERROR 16 ELEMENT COLUMN INCORRECT, CARD IGNORED
The element column designation in column 30 to 32 of the C-card is less than 1 or greater than 120. Enter a number between 1 and 120.
- ERROR 17 SYMBOL '***' ALREADY DEFINED FOR THIS CODE, CARD IGNORED
The area code on this C-card has been used with another symbol than the one used in columns 16 to 18. Use equal symbols for equal area codes.
- ERROR 18 CODE LESS THAN LAST CODE, INPUT OUT OF SEQUENCE
The C-cards have to be submitted in ascending order by area code. Offending card is ignored.
- ERROR 19 THE SAME SYMBOL HAS BEEN USED FOR CODE

The area symbol in columns 16 to 18 has been used before with another area code. Use different area symbols with different area codes. Offending card is ignored.
- WARNING 20 CODE USED TWICE UNDER TRANSACTION 'REMOVE', CARD IGNORED
Under a transaction code of "remove" only one C-card per area code needs to be supplied.
- WARNING 21 MORE THAN 4800 CODES AND SYMBOLS
COMPARISON STOP

A maximum of 4800 codes per dictionary is allowed.

Study area should be reorganized into smaller sectors.

ERROR 23 INDICATED FILE FORMAT IS IN ERROR

File type index must be a number between 1 and 11. See D-card definition for correct code.

ERROR 24 EXTERNAL FILE NAME MISSING OR INCORRECT

The external file name must appear in columns 3 thru 14.

ERROR 25 DICTIONARY NAME MISSING OR INCORRECT

The dictionary name in columns 21 through 32 of the D-card has either been left out or does not start with a dollar sign in column 21.

ERROR 26 CLIPPING COORDINATES ARE MISSING OR INCORRECT

Coordinates contain nonnumeric characters, or are inconsistent, or are out of range for the system indicated in column 34.

ERROR 27 CLIPPING COORDINATE SYSTEM UNDEFINED

Only 'S', 'G', or 'U' may be entered in column 34.

ERROR 28 D-CARD MISSING OR INCORRECT, ALL E-CARDS
IGNORED

Either no D-card has been found preceding the E-cards or the D-card found was incorrect.

ERROR 29 NEXT CARD IS NOT AN (E -CARD, T -CARD), ABOVE
(D-CARD, S-CARD) IGNORED

All (E-cards, T-cards) have to follow immediately the (D-card, S-card).

ERROR 30 ONLY ONE SET OF E-CARDS FOR EACH D-CARD

E-cards must immediately follow a D-card.

ERROR 31 FORMAT MISSING OR INCORRECT

The format description fields on E-cards have to be filled in for a "FORTRAN" formatted file. These fields were either not filled out or incorrectly filled out.

- ERROR 32 ALPHA FORMAT FOUND FOR FIELD LABEL '*****',
BUT LABEL DOES NOT EQUAL 'SYMBOL' OR
'CODE#1' OR 'CODE#2'
Alphanumeric format descriptors on the P-cards are only
allowed for a cross-reference field label in case of a
cross-reference by symbol or code.
- ERROR 33 MORE THAN 132 CHARACTERS DEFINED FOR EXTERNAL
RECORDS
The combined fields defined on E-cards for a "FORTRAN"
formatted external data file specify more than 132
characters. 132 is the limit for Fieldata external data
files.
- ERROR 34 MORE THAN 3 'V' CARDS, ABOVE CARD IGNORED
A legend on V-cards is restricted to 3 cards per run.
- ERROR 35 'V' CARDS FOUND BEFORE, ABOVE CARD IGNORED
All V-cards have to be supplied together.
- ERROR 36 B-CARD MISSING, ABOVE CARD IGNORED
A C-card has been found, but was not preceded by a
B-card.
- ERROR 37 DICTIONARY NAME INVALID ON G-CARDS
For transactions concerning dictionaries use B-cards and
not G-cards.
- ERROR 38 COLUMN 9 MUST BE EITHER '*/-/:./#/= ' TO BE
ACCEPTED
Column 9 indicates the data-type for the referenced map
and must be one of the above symbols.
- ERROR 39 SECTOR DESIGNATION IN COLUMNS ** THROUGH **
INCORRECT
- ERROR 40 CROSS-REFERENCE FIELD LABEL KEYWORDS NOT
FOUND

One of the following sets of keywords must be found:

SYMBOL

CODE#1, CODE#2

LATITUDE, LONGITUDE

UTMF, UTMN, UTMZONE

- ERROR 41 NONNUMERIC CHARACTER IN SECTOR DEFINITION
A nonnumeric character has been found in a sector row and column designation on the G-card. Enter numbers only.
- ERROR 42 TEXT OVERLAY HAS ALREADY BEEN DEFINED FOR THIS SECTOR, ABOVE CARD IGNORED
All text overlay H-cards for one specific sector have to be supplied together.
- ERROR 43 ROW OR COLUMN DESIGNATION MISSING IN COLUMNS ** THROUGH **
The row or column designation on the H-card has to contain 2 numeric entries of numbers between 1 and 120.
- ERROR 44 NUMBER OF CHARACTERS IN COLUMN ** INCORRECT
The number of characters for a text overlay on the H-card has to be a number between 1 and 12.
- ERROR 45 NONNUMERIC CHARACTER IN ROW, COLUMN OR NUMBER OF CHARACTERS FIELD
A nonnumeric character has been found in a numeric field on the H-card. Row and column pointers and the number of characters can only be numeric entries.
- WARNING 46 MORE THAN 30 I-CARDS, ABOVE CARD IGNORED
A maximum of 30 I-cards, title cards, is allowed per topic.
- ERROR 47 MORE THAN 35 J-CARDS, SCALE IGNORED
- ERROR 48 NONNUMERIC CHARACTER IN FIELD, COLUMN **
A threshold field on a J-card contains a nonnumeric character. Enter only integer or decimal numbers in the threshold fields.

ERROR 49 LOW END OF SCALE ALREADY DEFINED FOR SYMBOL

'4'

For only one symbol is a blank lower threshold field
accepted on the J-card scale.

ERROR 50 HIGH END OF SCALE ALREADY DEFINED FOR

SYMBOL '4'

For only one symbol is a blank upper threshold field
accepted on the J-card scale.

ERROR 51 EXT-FILE '*****' EXPECTED BUT '*****'

FOUND

External file name from columns 3-14 was not found on the
external data file, the indicated text was found instead.

ERROR 52 TOPIC NAME ON PREVIOUS G-CARD MISSING OR

INCORRECT, ABOVE CARD IGNORED

The topic name in columns 9 through 20 of the previous
G-card is missing or not left adjusted.

ERROR 53 SECTOR DEFINITION MISSING ON PREVIOUS G-CARD,

ABOVE CARD IGNORED

No sector designation has been found on the previous
G-card.

ERROR 54 REFERENCE TOPIC NAME MISSING OR INCORRECT

The reference topic name in columns 3 through 14 of the
K-card is either missing or not left adjusted.

ERROR 55 INSUFFICIENT SPACE FOR I-T-E PROGRAM

User's source code for map composition is too large.
Compose maps in stages.

ERROR 56 ONLY DICTIONARY NAMES ALLOWED AS REFERENCE

TOPIC

The reference dictionary in column
N-card is either missing or does
sign in column 3.

- ERROR 57 VALUE MISSING FOR SYMBOL ' : '
- A 3-character symbol has been found on the N-card with no associated value to replace the symbol.
- ERROR 58 NONNUMERIC VALUE '*' DEFINED FOR NEW NUMERIC TOPIC
- The topic name on the previous G-card defines a new numeric topic. All values replacing the dictionary symbols have to be numbers between 0 and 9.
- ERROR 59 SYMBOL MISSING FOR VALUE '*'
- A value has been found on an N-card with no associated dictionary symbol, which the value will replace.
- ERROR 60 SECOND REFERENCE TOPIC NOT ALLOWED FOR THIS TRANSACTION
- Following a G-card two N-cards with a reference dictionary in columns 3 through 14 have been found. Use only one reference dictionary.
- ERROR 61 LEFT (RIGHT) SIDE LINE MISSING AFTER LINE * * *
- The element matrix P-cards do not account for 120 left and 120 right-hand lines.
- ERROR 62 TOO MANY MATRIX CARDS
- All lines of an element matrix have been accounted for, but still more P-cards, left or right-hand cards have been found.
- ERROR 63 ROW *** EXPECTED, BUT ROW *** FOUND
- The row designation in columns 3 through 5 of a left-hand P-card or columns 63 to 65 of a right-hand card is not correct.
- ERROR 64 DOT INVALID AS FIRST CHARACTER ON LINE
- The first matrix element on a left or right-hand matrix card cannot be a dot. Enter the correct character.

- ERROR 65 DOT MISSING COLUMN, *
A symbol repetition has not been designated on a matrix card.
- ERROR 66 NONNUMERIC CHARACTER '*' FOUND IN COLUMN **,
INVALID TO GENERATE A NUMERIC TOPIC MAP
The previous G-card defined a numeric topic name in columns 9 through 20. Only numbers between 0 and 9 are allowed as elements on an element matrix.
- ERROR 67 'ROW TO' *** INCORRECT
The "row to" designation in columns 6 through 8 of the left-hand P-card or columns 66 to 68 of the right-hand matrix card is either greater than 120 or less than the "row from" entry in the preceding 3 columns.
- ERROR 68 NONNUMERIC CHARACTER IN ROW DESIGNATION
The row designations have to be numbers between 1 and 120.
- ERROR 69 INCORRECT LINEAR PROGRAMMING FUNCTION CODE
Only the key words 'SIMPDX' or 'FMPS' are allowed in columns 3 - 8.
- ERROR 70 MASTER MAP NAME MISSING OR INCORRECT
Columns 27 thru 38 must contain the master map used as the area cross-reference. Column 27 must be '*'.
- ERROR 71 NONNUMERIC VALUE IN NUMERIC FIELDS OF L-CARDS
Columns 14 thru 19 contain a nonnumeric character, this should be numeric only.
- ERROR 72 LP-MATRIX TOO LARGE FOR RAP, ENTER FMPS
FUNCTION CODE
The LP matrix is
Reenter as FMP
- ERROR 73 ONLY 20 DIFFE
RESUBMIT

RAP can keep track of only 20 LP modes per run. Resubmit jobs in groups of 20 or less LP modes per run.

- ERROR 74 NONNUMERIC ENTRY IN ROW OR COLUMN FIELDS
Columns 3 - 5 and 16 - 18 contain nonnumeric characters, these columns must have numbers 0 - 9 only.
- ERROR 75 TYPE OF MATRIX VALUE EITHER MISSING OR
INCORRECT
Column 32, indicating type of matrix value must contain either 'L' for literal, 'V' for value or 'A' for area.
- ERROR 76 D AND E-CARDS MISSING OR INCORRECT
A Q-card has been found, but either no D and E-cards, or the D and E-cards found contained errors.
- ERROR 77 REFERENCE FIELD LABEL MISSING
The reference field label in columns 3 through 14 of the Q-card has been left blank.
- ERROR 78 LABEL '*****' NOT FOUND ON E-CARDS
The reference field label in columns 3 through 14 of the Q-card has not been defined on the set of E-cards. Enter this name in the appropriate sequence on the E-card set.
- ERROR 79 NONNUMERIC CHARACTER IN FORMULA NUMBER,
COLUMN **
A formula number has been entered in column 32 or 34, but entries can be only numbers 1 to 9 in column 32 or 1 or 2 in column 34.
- ERROR 80 POINT FORMULA NUMBER MISSING, BARRIER ONLY
USED IN CONJUNCTION WITH POINTS
A barrier topic name has been entered in columns 19 through 30 of the Q-card, but no entry has been made in the point formula field in column 34. Enter a 1 or 2 in column 34.
- ERROR 81 NUMBER OF INTERVALS SPECIFIED FOR AUTO-SCALE
IS INVALID

A maximum of 32 intervals is allowed. If column 43 equals 'E', a number between 1 and 32 must be entered. If column 43 equals 'N', a number between 1 and 5 (power of 2) must be entered.

ERROR 82 NONNUMERIC CHARACTER IN ACCEPTANCE VALUE,
COLUMNS 63 - 70

ERROR 83 EXTERNAL FILE NOT ASSIGNED OR MOUNTED
Rerun and assign the unit indicated in column 19 (via @ASG or @USE).

ERROR 84 GREATER THAN 16 SECTORS SPECIFIED ON G-CARD
Subdivide the current map into subareas with no more than 16 sectors per area. (External data must be reread for each subarea)

ERROR 85 UNIT ENTRY MUST BE NUMERIC FOR THIS FILE TYPE
For FORTRAN formatted or IMPPS files the unit appearing in column 19 must be one of the numbers 1 - 4, or 8.

ERROR 86 BOUNDARY OVERLAY TOPIC HAS INVALID ENTRY

The boundary overlay topic field in columns 3 through 14 of the Z-card must be of type master, alpha, numeric or boundary.

WARNING 87 BOUNDARY OVERLAY SYMBOL NOT SPECIFIED.
BLANK ASSUMED.

No entry has been made in column 16 or column 20 of the Z-card.

ERROR 88 PRINTOUT OF GLOSSARY NOT POSSIBLE, NO INPUT
MAP FILE ASSIGNED

A glossary printout request has been made with a G-card, but no input map file has been assigned.

ERROR 89 ***** IS AN ILLEGAL MAP NAME IF

A dictionary or a title/scale has been used in an R-expression.

- ERROR 90 SYMBOL '*' IN CARD COLUMN ** INVALID, NOT
ALLOWED FOR SYMBOL CONVERSION
- A symbol on the K-card has been found which is not in the set of characters preprinted above the card. Use only entries which are preprinted above the K-card.
- ERROR 91 ALPHA SYMBOL '*' IN COLUMN ** NOT ALLOWED AS
CONVERSION SYMBOL FOR A NUMERIC TOPIC
- A numeric new topic name has been specified on the preceding G-card. Enter only numbers between 0 and 9 as replacing symbols on the K-card.
- WARNING 92 SYMBOL '*' IN COLUMN ** REPLACES ALPHA SYMBOL
'*', WHICH DOES NOT EXIST ON THE NUMERIC
REFERENCE MAP
- A numeric topic name has been defined in columns 3 through 14 of the K-card, which does not contain alpha symbols. All entries in columns 17 through 50 are unnecessary.
- WARNING 93 ASTERISK-CARD MISSING IN FRONT OF REQUEST DECK
- Precede the RAP request deck with a card with an asterisk in column 1.
- WARNING 94 ASTERISK CARD MISSING BEHIND REQUEST DECK
- Follow the RAP request deck with a card with an asterisk in column 1.
- ERROR 95 K-CARD REFERENCE AND G-CARD TOPIC NAME
CANNOT BE EQUAL
- The topic name on the G-card has to differ from the reference topic name used on the K-card. Only in case of a 'modify' transaction can the names be equal.
- ERROR 96 '...' IS AN ILLEGAL LITERAL
- Only "numeric", "alpha" or "master" type literals are admissible. The string within quotes in the R-expression is longer than 3 characters.

- ERROR 97 MORE THAN 120 ENTRIES SPECIFIED FOR MODIFY OR
REMOVE, ABOVE CARD IGNORED
The "change" table for dictionary processing has been
exceeded. Reduce the size of the run and resubmit it.
- WARNING 98 NO MORE THAN 3 S-CARDS ALLOWED
More than 3 report title cards were specified. All entries
after 3 are ignored.
- ERROR 99 STATISTICS TYPE MISSING OR INCORRECT, ABOVE
CARD IGNORED
Type of statistical run specified in T card does not match
the acceptable types.
- ERROR 100 LIMIT IGNORED FOR TYPE **
A limit value was specified for a statistical run which does
not use a limit value.
- ERROR 101 STARTING POINT OR INCREMENT MISSING, ABOVE
CARD IGNORED
A required starting point or increment is missing for the
statistical run type specified.
- ERROR 102 STARTING ROW GREATER THAN *** OR STARTING
COLUMN GREATER THAN 120
A starting row or column out of range has been specified.
- ERROR 103 NONNUMERIC LIMIT OR STARTING POINT, ABOVE
CARD IGNORED
A nonnumeric character has been used as a parameter in
the limit or starting point parameter.
- WARNING 104 STARTING POINT AND INCREMENT IGNORED FOR
TYPE **
A starting point and increment was specified for a
statistical run type which does not use those values.
- ERROR 105 INCORRECT MASKING TOPIC ***** ABOVE
CARD IGNORED
A masking topic was specified which could not be located
or is incorrectly specified.

ERROR 106 MASKING SYMBOL * INCORRECT, ABOVE CARD
IGNORED

A masking symbol was specified which is not a suitable
suffix.

WARNING 107 DEPENDENT TOPIC IGNORED FOR TYPE **

A dependent topic was specified for a statistical run type
which does not use these values.

ERROR 108 DEPENDENT TOPIC ***** INCORRECT, ABOVE
CARD IGNORED

A dependent topic was specified which could not be
located.

ERROR 109 DEPENDENT TOPIC MISSING, ABOVE CARD IGNORED

A dependent topic was not specified for a statistical run
type which requires this entry.

ERROR 110 U-CARDS NOT EXPECTED, ABOVE CARD IGNORED

U-cards are not required for this statistical run type and
therefore should be omitted.

ERROR 111 T-CARD MISSING, ABOVE CARD IGNORED

Either cards are out of sequence or the T-card was not
provided. The T-card must immediately precede the
U-cards.

ERROR 112 INDEPENDENT TOPIC MISSING FOR F

An independent topic was not specified in the U-card
where expected for type of run specified.

ERROR 113 INDEPENDENT TOPIC ***** EQUAL TO DEPENDENT
TOPIC

An independent topic was specified which has the same
name as a specified dependent topic.

ERROR 114 INDEPENDENT TOPIC ***** INCORRECT

An independent topic was specified that cannot be located.

ERROR 115 MERGER FILE '*****' INCORRECT

Name in column 44-55 does not match with header found
on "MERGER" file.

ERROR 116 MERGER INPUT FILE ERROR, UNIT *, STATUS ***

ERROR 117 SUBSET FILE NAME IS INCORRECT
 Subset file name must have a non-blank entry with action of "SUBSET".

ERROR 118 SUBSET OUTPUT FILE ERROR, UNIT *, STATUS ***

ERROR 119 NUMBER OF MAPS REFERENCED MUST NOT EXCEED 10
 There are more than 10 map names referenced in R-expressions. Compose the maps in stages.

ERROR 120 INSUFFICIENT SPACE FOR PARSER OUTPUT
 During the parse of a set of R-expressions, output buffer overflowed. Compose the maps in stages.

ERROR 121 PARSER STACK OVERFLOW
 R-expressions are too heavily nested. Simplify.

ERROR 122 NO MAPS REFERENCED IN R-EXPRESSIONS

SYNTAX ERROR 123 STMT ***; OCCURS BEFORE LINE ***,
 COLUMN ***
 Error in R-expression grammar. Refer to R-card section and grammar description.

ERROR 124 LITERAL TABLE OVERFLOW
 Caused either by deeply nested expressions, or simply too many literal values. Simplify.

ERROR 125 TITLE/SCALE NOT POSSIBLE, NO INPUT MAP FILE
 Title/scale request is performed on existing title/scale blocks and none were found.

ERROR 126 MORE THAN ONE SECTOR DEFINED ON G-CARD
 Topic generation can only reference one sector when creating topic map.

ERROR 127 NONNUMERIC TOPIC '*****' USED AS BARRIER
 TOPIC
 Barrier topic should be a numeric map, columns 3 through 14.

ERROR 128 ILLEGAL VALUE IN COLUMN, **
 A value was specified in the column noted which is incorrect.

ERROR 129 COLUMNS 02 22 MUST BE BLANK ON O-CARDS

(OTHER THAN FIRST)

Only the first O-card may contain the control characters for topic generation by points or lines.

ERROR 130 ERROR IN CONVERTING O-CARD DATA, POSSIBLY NON-NUMERIC CHARACTER IN NUMERIC FIELD

Check all entries in point and line values for blanks or other nonnumeric characters.

ERROR 131 POINT VALUES OUTSIDE THE RANGE (-0.5, 9.5)

REQUIRE SCALING

When scaling has not been provided via J-cards, all data values must be greater than or equal to -0.5 and less than 9.5.

ERROR 132 DISPERSION MUST BE SPECIFIED FOR EACH POINT/
LINE WHEN GLOBAL DISPERSION (COLUMN 17)
IS BLANK

Dispersion must be specified either for each individual point, or for the entire set of values with an entry in column 17 of the O-card.

ERROR 133 COLUMNS ** THROUGH ** SHOULD BE SPECIFIED FOR
GENERATION BY LINES, STARTING VALUES
ASSUMED

When generating maps by lines, both a starting point and an ending point are to be specified. Check values and resubmit.

ERROR 134 INCORRECT POINT/LINE DEFINITION IN COLUMNS **
THROUGH **

The values specified in the stated columns are not consistent for map generation. Check the values within the stated columns and resubmit.

ERROR 135 MERGER, SUBSET AND STATISTICS UNITS MUST BE
UNIQUE

Columns 38, 40 and 42 must not have the same values.

- ERROR 136 MFRGER, SUBSET AND STATISTICS MUST BE UNITS A
THRU Z
Columns 38, 40 and 42 must have unit assignments of A
thru Z.
- ERROR 137 ONLY A ' ' CARD OR EXIT ARE ALLOWABLE
In demand mode, only. For cards which can appear in
multiples, 'EXIT' must be entered to terminate the card
series.
- ERROR 138 AREA POINTER TYPE HAS NOT BEEN INDICATED
One of columns 31, 33 or 35 must be non-blank indicating
type of area pointer to appear on subsequent C-cards.
- ERROR 139 ONLY ONE AREA POINTER MAY BE MARKED
One of columns 31, 33 or 35 must be non-blank indicating
type of area pointer to appear on subsequent C-cards.
- ERROR 140 ONLY MAPS CAN BE DISPLAYED WITH A W-CARD
A non map name was entered on previous G-card.
- ERROR 141 DATA TYPES: ***** AND/OR ***** ILLEGAL FOR
***** MAP
The map being created must receive values of a type
consistent with its own; for example, alpha maps must
receive alpha values.
- ERROR 142 F-CARD DOES NOT CONFORM TO FORMAT OR DOES
NOT CONFORM TO E-CARDS
- ERROR 143 MORE F-CARDS EXPECTED
Premature end to F-card series. Number of data items
as specified on E-cards not yet encountered or a closed
polygon (feature type 1) was indicated but coordinates are
missing.
- ERROR 144 SEGMENTS MISSING IN POLYGON
First point does not equal last point to close polygon.
- ERROR 146 ROW VALUE IS GREATER THAN NUMBER OF CONSTRAINTS
Row value indicated in columns 3 - 5 of M-card must not exceed
number of constraints indicated in columns 14-16 of L-card.

- ERROR 147 COLUMN VALUE IS GREATER THAN NUMBER OF
VARIABLES
Row value indicated in columns 16 - 18 of M-card must
not exceed number of constraints indicated in columns
17 - 19 of L-card.
- ERROR 148 BOTH ROW AND COLUMNS CANNOT BE ZERO
Row zero column zero is undefined.
- ERROR 149 BOTH ROW AND COLUMN NAMES CANNOT BE BLANK
- ERROR 150 THIS RELATIONSHIP HAS INVALID ENTRY
With column equal to zero or blank, THIS entry must be one
of the following:
 'EQ' for equal
 'GE' for greater than or equal
 'LE' for less than or equal
- ERROR 151 NONNUMERIC VALUE IN LITERAL FIELD, COLUMNS
34 - 45
Literal indicated in column 32 but nonnumeric found.
- ERROR 152 MAP-NAME MISSING OR INCORRECT
Column 32 indicates 'A' area or 'V' value, and columns
34 - 45 must contain a valid map name.
- ERROR 153 MISSING OR INVALID POINTER-TYPE CODE
Column 47 must contain either 'S' for sector pointer or
'G' for geographic pointer or 'U' for UTM pointer or 'A'
for area codes.
- ERROR 154 NONNUMERIC VALUE IN POINTER FIELD
- ERROR 155 AN L-CARD MUST PRECEDE A GROUP OF M-CARDS
LP model must be defined with L-cards before matrix
generation by M-cards.
- ERROR 156 AREA SYMBOLS NOT VALID FOR VALUE OF MAP
POINTER
When 'V' is used in column 32 indicating map value, only
'S', 'U' or 'G' may be entered in column 47.

ERROR 157 ROW AND COLUMN POINTERS MUST BE BETWEEN 1
AND 120

Each sector is only 120-by-120 and pointer must be
within this sector.

ERROR 158 MASTER MAPS MUST HAVE 3-CHARACTER SYMBOL

When columns 34 thru 45 contain a master map and
column 47 equals 'A' then the symbols entered in
columns 56 - 58 and/or 61 - 63 and/or 66-68 and/or
71 - 73 must be either 3-character or blank.

ERROR 159 NUMERIC MAPS MUST HAVE ONLY A SINGLE
CHARACTER

See explanation on ERROR 158.

ERROR 160 THERE IS A CONFLICT ON THE NAME/SYMBOL FOR
THIS ROW

This row was previously given another name or symbol.

ERROR 161 THERE IS A CONFLICT IN THE NAME/SYMBOL FOR
THIS COLUMN

This column was previously given another name or symbol.

ERROR 162 POINTER FALLS OUTSIDE CLIPPING VALUES FROM
L-CARD

Enlarge clipping window on L-card or correct pointer
value.

WARNING 163 NOT ABLE TO DETERMINE UNIQUENESS OF ROW AND
COLUMN NAMES ON LP MODIFICATION

On restart option some error checking is inhibited.

ERROR 164 FOR A LP MODEL MODIFICATION, ONLY FUNCTION
AND MODEL NUMBER ARE NECESSARY

The values from the restarted LP model are used in this
new model.

ERROR 165 THIS LP MODEL CANNOT BE FOUND FOR MODIFICATION
Check columns 10 and 11 for correct restart model number.

- ERROR 166 THE LP MODEL MUST HAVE M-CARDS FOR INITIAL
MODEL
The first LP model must have matrix entries enter via
the M-cards.
- ERROR 167 FMPS DATA FILE MUST BE CROSS-REFERENCED BY
SYMBOL
Master map symbols are used as the cross-reference
between FMPS data and the RAP system.
- ERROR 168 LP MODEL NUMBER IS GREATER THAN THE LP's
DEFINED
- ERROR 169 THE CHARACTER '*' IS ILLEGAL
Illegal area code symbol entered in columns 56 - 58 or
61 - 63 or 66 - 68 or 71 - 73 when an 'A' was entered in
column 47.
- ERROR 170 THIS ROW NAME HAS BEEN GIVEN TO A COLUMN
PREVIOUSLY
Row names must be unique from all column names.
- ERROR 171 THIS COLUMN NAME HAS BEEN GIVEN TO A ROW
PREVIOUSLY
Column names must be unique from all row names.
- ERROR 172 NUMERIC MAP MAY HAVE ONLY 10 OR FEWER VALUES
- ERROR 173 F-CARDS ILLEGAL; D AND E-CARDS ARE MISSING
- ERROR 174 SECTOR ROW *** COLUMN *** MULTIPLY DEFINED
- ERROR 175 NEXT CARD IS NOT A 'U' CARD, ABOVE T-CARD
IGNORED
Regression asked for on T-card but no independent maps
indicated, because no U-cards found.
- ERROR 176 ONLY 'B' OR 'C' CARD ALLOWED WITH A 'REMOVE'
ACTION
- ERROR 177 ONLY 'B' OR 'G' CARDS ALLOWED WITH A 'DELETE'
OR 'MERGER' OR 'SUBSET' ACTION
- ERROR 178 CODE GENERATES MORE THAN 2400 INSTRUCTIONS,
SIMPLIFY

- ERROR 179 THIS IMAGE MUST HAVE A '@' IN COLUMN 3
All calls to CSF\$ must be EXEC-8 control images which start with a '@'.
- ERROR 180 CONTROL STATEMENT IS NOT LEGAL FOR CSF\$,
REFER TO PRM
Only a limited set of control statements may be entered dynamically. Please refer to PRM for legal statements.
- ERROR 181 SUBSET OR MERGER FILE NOT ASSIGNED, EXECUTE
'\$' CARD
- ERROR 182 CROSS-REFERENCE KEY WORDS ARE MULTIPLY
DEFINED
Only one set of the cross reference key words may be entered on E-cards.
- ERROR 183 REDUCTION RULE MUST BE 'A', 'M', 'P' or 'B'
See G-card section for explanation of codes.
- ERROR 184 'AVERAGE' RULE IS INVALID FOR TOPIC SPECIFIED
Since arithmetic operations are involved in employing the reduction rule, topic must be either type numeric or real.
- ERROR 185 E-CARDS ARE MISSING OR INCORRECT
Data must be entered before map topics can be created via Q-cards.
- ERROR 186 RADIUS SPECIFICATION WRONG
The radius value is extremely large, it is greater than a sector in size. Either make the radius smaller or increase the scale of the map.
- ERROR 187 UNKNOWN COMPOSITION RULE. USE B1
The internal composition rule for intersector
corridor is incorrectly stated
valid code interpretation

ERROR 188 INTERNAL COMPOSITION RULE ILLEGAL FOR THIS MAP

Composition rules often are valid for only a particular kind of map. The Q-card documentation indicates which rules apply to which map types.

ERROR 189 ADDITIVE COMPOSITION ILLEGAL WITH 'E' OR 'N' SCALING

The automatic scaling options of 'E' or 'N' act on the actual external values and do not include the values which are intersections of areas; therefore, this combination has been indicated as illegal. To do an equal-interval or nested-means display of such a map, first create a real-valued map with 'E' or 'N' in column 43 of the Q-card. Then display the map with a Z-card indicating automatic nesting or equal-interval.

WARNING 190 REAL VALUED MAPS MUST BE SCALED FOR DISPLAY

The previous G-card indicates that this is a real valued map but column 26 contains neither an 'E' nor a 'N'. Also, up to this time, a set of J-cards for scaling has not been entered. If there already exists a title/scale block on the map file then the real valued map will be scaled for output by that scale. If not then an error will occur at map display time in phase II.

ERROR 191 J-CARDS NOT VALID FOR TOPIC DEFINED ON G-CARD

Scale entries apply to numeric or alpha or real-valued map types only.

ERROR 192 SCALING OPTIONS INCONSISTENT WITH TYPE OF MAP

Nested-means and equal-interval scaling are only valid for real-valued maps. Range expansion and translation are valid only for numeric maps.

ERROR 193 ELEMENT DESIGNATION IN COLUMNS XX THROUGH XX
INCORRECT

The row and column positions for the element displacement must be between 1 and 120 for an 8 or 10 line-per-inch map in both row and column. For a 6 line-per-inch map, row designation can be between 1 and 90 while column is still 1 through 120.

ERRORS AND WARNINGS - PROCESSING PHASE

ERROR 200 MORE THAN 1210 BORDER POINTS - PROGRAM
STOPPED IN SUBROUTINE POINT

Simplify the master map into smaller regions by
disaggregation of complex areas.

ERROR 201 DICTIONARY ***** NOT FOUND, NO UPDATE
MADE

Dictionary transactions of modify or remove have been
specified, but the dictionary has not been found on the
input map file.

ERROR 202 TOO MANY ENTRIES FOR FMPS, RUN FMPS OFF -LINE

ERROR 203 DICTIONARY '*****' NOT FOUND, NO TOPIC
GENERATION BY DICTIONARY SYMBOL
CONVERSION

Dictionary name on N-cards was not found, or dictionary
implied by R-cards not found.

ERROR 204 REFERENCE TO MAP ***** NOT FOUND FOR
THIS SECTOR, NO TOPIC GENERATION BY SYMBOL
CONVERSION FOR THIS SECTOR

The reference topic defined on a K-card has not been
found on the map-file and has not been created in this run.

ERROR 205 AGGREGATE AREA DICTIONARY '*****' NOT
FOUND, NO TOPIC GENERATION BY SYMBOL
CONVERSION FOR THIS SECTOR

ERROR 207 NO CONVERSION SYMBOLS HAVE BEEN SPECIFIED FOR
THE FOLLOWING SYMBOLS ON REFERENCE
TOPIC *****

The K-card conversion symbols have not defined replacing
characters for number of symbols found on the reference
topic.

ERROR 208 THERE ARE COMBINATIONS OF MAP VALUES NOT
SPECIFIED FOR SECTOR ***-*** (*****)

Conditional expressions on R-cards are not sufficient to
cover all possible combinations of values on factor maps.
Use a final 'ELSE' clause to resolve.

ERROR 209 MASTER MAP ***** NOT FOUND FOR THIS SECTOR

A topic generation by external data uses a master map to
find the area outlines, this map has not been found on the
map file and not been created previously in this run.

ERROR 210 DICTIONARY ***** NOT FOUND, ELEMENT MAP
IGNORED

A master-map name has been specified on a G-card but
the appropriate dictionary which defined the 2-character
area suffices for this master map has not been found on
the map file nor been created in this run.

ERROR 211 NO AREA POINTERS FOUND IN DICTIONARY *****

FOR THIS SECTOR, ELEMENT MATRIX IGNORED

The dictionary with the same name as the element matrix
does not contain any area pointers which point to this
sector. Check section designation on the G-card or
modify dictionary.

ERROR 212 NO AREA POINTERS HAVE BEEN FOUND IN THE
DICTIONARY ***** FOR THE FOLLOWING
AREA SYMBOLS

The dictionary with the same name as the element matrix
does not contain area pointers for areas designated on the
matrix. This message is followed by one or more errors 213.

ERROR 213 SYMBOL ? IN ROW ?? , COL. ???

Enter an area pointer for this symbol in the dictionary.

ERROR 214 MAP '*****', SECTOR ROW ***, COLUMN ***
NOT FOUND

Map indicated on statistics cards was not found in the
directory

ERROR 215 SCALE NOT FOUND, NO TOPIC GENERATION FOR ALL
SECTORS

A topic generation by external data needs a scale. No
J-cards have been supplied nor has auto-scale been
indicated.

ERROR 216 SCALE INCORRECT FOR THIS TOPIC, NO RANGE
PROVIDED FOR THE FOLLOWING VALUE

The scale defined for the topic to be generated by external
data does not cover the whole range of incoming data.
Change the scale to cover all data.

ERROR 217 THE FOLLOWING AREA POINTERS IN THE DICTIONARY
***** ARE INCORRECT FOR THIS SECTOR

The dictionary with the same name as the element matrix
does contain pointers to areas in this sector which do not
agree with the matrix area outlines. Check dictionary and
matrix. This message is followed by one or more
warnings 245.

ERROR 218 REFERENCE TOPIC ***** NOT FOUND, NO
TOPIC GENERATION BY COMPUTATIONS FOR
THIS SECTOR

A reference topic used in computations on R-cards has not
been found on the map file nor been created in this run.

ERROR 219 DICTIONARY ***** NOT FOUND, NO DISPLAY
POSSIBLE

A dictionary to be displayed has neither been found on the
map file nor been created in this run.

ERROR 220 DICTIONARY '*****' NOT FOUND TO MAKE

AGGREGATE

Dictionary referenced for statistics cards was not found in the directory.

ERROR 221 DICTIONARY ***** NOT FOUND TO GENERATE

THE AGGREGATE AREA OVERLAY MAP *****

The aggregate area master map to be used as boundary overlay topic for display requires a basic area dictionary to be available. This dictionary has not been found on the map file and has not been created in this run.

ERROR 222 SECTOR NOT FOUND FOR DISPLAY

A topic sector to be displayed has not been found on the map file and not been created in this run.

ERROR 223 SECTOR ***-*** OF OVERLAY MAP ***** NOT
FOUND

A boundary overlay map used indicated has not been found on the map file and not been created in this run.

ERROR 224 AGGREGATE AREA DICTIONARY ***** NOT
FOUND, TO GENERATE AGGREGATE AREA MAP

The aggregate area master map requires an aggregate area dictionary, which has not been found on the map file and not been created in this run.

ERROR 225 AGGREGATE AREA DICTIONARY ***** NOT

FOUND, TO GENERATE OVERLAY MAP *****

The aggregate area master map boundary overlay topic requires an aggregate area dictionary, which has not been found on the map file and not been created in this run.

ERROR 227 MASKING TOPIC ***** NOT FOUND, NO TOPIC GENERATION
BY EXTERNAL DATA FOR THIS SECTOR

The masking topic specified was not located on the map file and therefore topic generation for the specified sector is impossible to complete. Check spelling of the masking topic and the latest dictionary listing.

ERROR 228 TOO FEW VALUES FOR DESIRED LEVEL OF NESTED
MEANS
The number of unique values is less than the number of
intervals or the distribution of data does not fit the number
of levels specified. Select fewer intervals.

ERROR 229 ILLEGAL CHARACTERS IN RHS RELATION

ERROR 230 UPDATE FOR DICTIONARY INCORRECT
Modify transactions for a dictionary have been defined for
areas which use area symbols, which have already been
used for other areas. Use different symbols for different
areas. This error message is followed by one or more errors
231.

ERROR 231 CODE '*****' IN EXISTING DICTIONARY USES
SYMBOL '***'. UPDATE FOR CODE '*****'
IGNORED
Submit another modify transaction using a new unique area
symbol.

ERROR 232 MULTIVARIATE MAP '*****' SECTOR *** ***,
ROW ***, COL *** HAS ILLEGAL SYMBOL *

ERROR 233 TABLE OVERFLOW IN COMPUTING SYMBOL COUNT FOR
MASTER MAP MULTIVARIATE TOPIC
Study area is too large, partition study area into smaller
segments.

ERROR 234 SYMBOL COUNT TABLE HAS EXCEEDED 312 DIFFERENT
MASTER MAP SYMBOLS, SIMPLIFY TO FEWER
AREAS

ERROR 235 ILLEGAL SYMBOL IN MAP '*****' SECTOR *** ***,
THE SYMBOL WAS *

ERROR 236 SYMBOL *** WAS NOT FOUND IN TEMPORARY
DICTIONARY

ERROR 237 SECTOR LINK ERROR FOR SYMBOL ***

ERROR 238 DUPLICATE SECTOR ENTRIES ENDED UP EQUAL TO ***

- ERROR 239 EXTERNAL DATA FILE IN ERROR
Either incorrect file has been mounted, or data does not conform to E-card specifications or there are hardware problems.
- ERROR 240 THERE ARE TOO MANY VARIABLES IN THE LP MODEL
There were greater than 1740 items in the LP matrix, use FMPS as the LP model and run offline.
- ERROR 241 MULTIVARIATE MAP '*****' SECTOR ROW ***
COLUMN ***, NOT FOUND
The map specified as the multivariate topic on 'T' cards was not in the directory.
- WARNING 242 NO VALUES HAVE BEEN FOUND FOR THE FOLLOWING
SYMBOLS ON REFERENCE TOPIC *****
During generation of a topic map, the areas of the reference topic listed received no input values and therefore it was impossible to create output for these areas. Check the input data file.
- ERROR 243 INSUFFICIENT SPACE ON FILE A\$A
Resubmit job with fewer transactions or explicitly assign (@ASG,T A\$A., F///n) where 'n' is some number greater than 1000. 1000 is the default value used by RAP.
- ERROR 244 SEGMENTS MISSING IN POLYGON '*****'
There is an error on the census "DIMECO" file in that a polygon is not completely digitized.
- WARNING 245 POINTER FOR SYMBOL ***, ROW ***, COLUMN ***,
WHERE SYMBOL *** HAS BEEN FOUND
Check these areas in the dictionary and in the element matrix.
- ERROR 246 INSUFFICIENT CORE SPACE FOR POLYGON BOUNDARY
Partition map into subsets with fewer sectors.
- ERROR 247 TITLE AND SCALE RECORD WAS NOT FOUND
The title and scale were requested but no title and scale by the name mentioned was found in the dictionary.

ERROR 248 NUMBER OF ENTRIES ON E-CARDS DOES NOT MATCH
NUMBER OF DATA ITEMS IN FILE

An error was discovered when processing the external data file, indicating there was either too much data or too little. Compare the data file with the entries on the E-cards. There should be a one-to-one correspondence.

ERROR 249 NUMBER OF VERTICES IN POLYGON IS TOO LARGE

RAP has a limited amount of storage to contain all the vertices of a polygon, and the user has exceeded that limit. Run a thinning program to remove some of the points from the polygon or divide the polygon into smaller polygons which can be processed separately.

WARNINGS - NEW MAP FILE GENERATION PHASE

WARNING 301 'CREATE' SPECIFIED FOR GRID *** TOPIC *****
SECTOR ROW *** COLUMN ***, BUT TOPIC EXISTS
ALREADY, NO ACTION TAKEN

Self explanatory.

WARNING 302 'CREATE' SPECIFIED FOR GRID *** TITLE *****,
BUT TITLE EXISTS ALREADY, NO ACTION TAKEN

Self explanatory.

WARNING 303 'CREATE' SPECIFIED FOR GRID *** DICTIONARY *****,
BUT DICTIONARY EXISTS ALREADY, NO ACTION TAKEN

Self explanatory.

WARNING 304 'MODIFY' OR 'DELETE' SPECIFIED FOR GRID *** TOPIC
***** SECTOR ROW *** COLUMN ***, BUT
TOPIC DOES NOT EXIST, NO ACTION TAKEN

Self explanatory.

WARNING 305 'MODIFY' OR 'DELETE' SPECIFIED FOR GRID *** TITLE
*****, BUT TITLE DOES NOT EXIST, NO
ACTION TAKEN

Self explanatory.

WARNING 306 'MODIFY' OR 'DELETE' SPECIFIED FOR GRID ***
DICTIONARY *****, BUT DICTIONARY DOES
NOT EXIST, NO ACTION TAKEN

Self explanatory.

WARNING 307 SUBSET TAPE SPECIFIED FOR GRID ***, 'TOPIC*****',
SECTOR ROW ***, COLUMN ***, BUT TOPIC DOES
NOT EXIST. NO ACTION TAKEN

WARNING 308 SUBSET TAPE SPECIFIED FOR TITLE '*****' BUT
TITLE DOES NOT EXIST. NO ACTION TAKEN

WARNING 309 SUBSET TAPE SPECIFIED FOR DICTIONARY '*****'
BUT DICTIONARY DOES NOT EXIST. NO ACTION
TAKEN

RUN STOP MESSAGES

RUN STOP 401 DRUM WRITE ERROR, STATUS =***

Resubmit the run.

RUN STOP 402 DRUM READ ERROR, STATUS =***

Resubmit the run.

RUN STOP 403 TAPE WRITE ERROR ON UNIT **, STATUS =***

Resubmit the run, if error occurs again, use another output tape on the defined unit.

RUN STOP 404 TAPE READ ERROR ON UNIT **, STATUS =***

Resubmit the run. If error occurs again repeat the previous run in the map file cycle (if the unit is unit 7).

RUN STOP 405 TABLE OVERFLOW, TOO MANY TRANSACTIONS

Too many sectors and topics have been referenced and/or generated.

RUN STOP 406 TABLE OVERFLOW, TOO MANY SORT ENTRIES

RESUBMIT THIS BATCH IN 2 OR MORE SEPARATE DECKS

Too many sectors and topics have been referenced and/or generated.

RUN STOP 407 PARAMETER TABLE OVERFLOW, RESUBMIT THIS BATCH

IN 2 OR MORE SEPARATE DECKS

Too many symbol conversions have been specified.

RUN STOP 408 REQUESTER TABLE OVERFLOW, TOO MANY A-CARDS

RESUBMIT THIS BATCH IN 2 OR MORE SEPARATE DECKS

A maximum of 20 'A' cards may be submitted in one runstream

RUN STOP 409 SECTOR READ OR SECTOR WRITE ERROR

RUN STOP 410 INOUT ERROR, SEE STATUS CODE

RUN STOP 411 PROGRAM ERROR IN GENERATION BY POINTS/LINES.

RUN STOP 412 INCONSISTENCY IN STEPWISE REGRESSION ANALYSIS
RUN STOP 413 UNKNOWN ERROR TYPE

APPENDIX C

GLOSSARY

- A -- AGGREGATE - A collection of topic elements by symbol or area.
- ALGORITHM - A prescribed set of well defined rules or process for the solution of a problem. Algorithms are implemented on a computer by a programmed sequence of instructions.
- ALPHA MAP - A map output represented by alphanumeric characters.
- ALPHANUMERIC - The characters which include letters of the alphabet, numbers and other symbols such as punctuation or math symbols.
- ACTIVE MODE - The process of making actual changes to a map file in the GRID system.
- ACTIVE PARTICIPATION - See Active Mode.
- ANNOTATE - The marking of features on a map or photograph for the purpose of clarification using letters, numbers and symbols.
- ARC - A part of a mathematically defined curve, such as part of a polygon.
- AREAL (INFORMATION, FEATURE, STATISTICS) - Pertains to a such as vegetation, soils, etc., which enclosed by a boundary of any polygon.
- AREA POINTER - Indicates which geographic map that is being defined (geographic).

ARITHMETIC - Computation or problem solving involving real numbers and the arithmetic operations.

ARRAY - The arrangement of a sequence of items according to their values, such as from largest to smallest.

ATTRIBUTE - A quality, characteristic or object which serves to describe, classify or identify something. Quantitative data associated with polygons, arcs, or points.

B -- BATCH PROCESSING - A technique by which similar input items are grouped for processing during the same machine run.

BOOLEAN EXPRESSION - An algebraic process formulated by George Boole. Similar to ordinary algebra but with classes, propositions, etc., for variables rather than data values. It includes operators such as AND, OR, NOT, IF, etc.

BOUNDARY MAP - Contains the boundaries separating homogeneous areas within the parent map, i.e., soil boundaries from soil type maps.

C -- CALCOMP - A trade name of California Computer Products, Inc., Anaheim, California, manufacturers of digital graphic systems used for plotting.

CARD - Paperboard material formed in uniform size and shape which is punched in various arrays to be sensed electronically by a card reader. Standard card is 7 3/8 X 3 1/4 inches and contains 80 columns.

CARTESIAN COORDINATES - Values representing the location of a point in a plane in relation to two perpendicular intersecting straight lines, called axes. The point is located by measuring its distance from each axis along a parallel to the other axis.

CELL - The storage for one unit of information, usually one character, i.e., soil type A.

CELLULAR MAP - A display of input cell data by single characters for each cell.

CHARACTER - One symbol of a set of elementary symbols such as those corresponding to the keys on a typewriter. See Alphanumeric.

CODING, CODED - A system of symbols representing cell data for input to a computer.

COMPLEX POLYGON - A polygon which has an exterior boundary and one or more interior boundaries. Area within interior boundary is called a DONUT or hole in the polygon.

COMPOSITE - The bringing together of pieces to obtain a whole, i.e., selected data from two or maps, each of which shows the distribution of individual resources or topics necessary for a solution to a problem.

COMPOSITE MAP - A map which results from overlaying two or more layers of the same area.

COMPUTER - A device capable of accepting information, applying prescribed processes to the information, and supplying the results of these processes.

CONDITIONAL EXPRESSION - An expression which has a particular characteristic, which when taken as a whole, it may be either true or false in accordance with the rules. See Appendix A, Input Form, R-Card.

CONFORMAL MAP - A map where the basic geographic shape conforms to some previously defined boundaries such as counties or regions.

CONNECTIVES - In Boolean algebra, it is that specific symbol (NOT, AND, OR) which signifies the operation to be performed.

CONTIGUOUS - Adjacent or adjoining.

CONTINUOUS MAP - Shows variations from element to element of data for topics such as soil types, land use, etc.

CONTINUOUS MODE DIGITIZING - See Digitize.

CONTOUR MAP - A topographic map which portrays relief by the use of contour lines.

COORDINATE - One of a set of numbers used to determine the location of a point on a given plane or system. Linear or angular quantities which designate the position of a point in a given reference or grid system. Also used as a general term to designate the particular kind of reference frame or system such as plane rectangular coordinates.

COORDINATE TRANSFORMATION - A mathematical process of obtaining a modified set of coordinates by rotating the coordinate axes from their point of origin.

CREATE - An "A" Card transaction used when any new map, dictionary or title is to be added to the Map File.

CURSOR - The mechanical or electromechanical tracking device or pointer on the digitizing table, sometimes referred to as a stylus.

CURVILINEAR COORDINATES - Any linear coordinates which are not cartesian coordinates.

CURVILINEAR LINES - Pertains to curved lines, as in curvilinear coordinates.

D -- DATA BASE - A set of data or information on which operations can be performed and conclusions can be based.

DATA FILE - A collection of data sets that has been stored on some computer compatible medium.

DELETE - An "A" Card transaction used to destroy an entire dictionary, map or title on a map file.

DEMAND PROCESS - The processing of data as quickly as it becomes available or ready. This is real-time and thus avoids the need for storage of any appreciable amount of unprocessed data.

DIAGNOSTIC - Pertaining to the detection, discovery and further isolation of a malfunction or a mistake.

DICTIONARY - A map dictionary is a table which relates shapes defined by a master map the area. See Appendix A. Index

DIGITAL - Term used loosely to refer to equipment, techniques and data involved in the digitizing process.

DIGITIZE - The process which converts information, generally graphic or pictorial, into computer recognizable characters which are locatable in some coordinate system. The recording of data by indicating a point coordinate on a data processing medium (e.g., card type).

DIGITIZE CONTINUOUS MODE - The process of recording points at a pre-set increment or determined by the operator.

DIGITIZE POINT MODE - The process of recording individual points as selected by the operator.

DONUT "HOLE" - A polygon or polygons contained within the exterior boundary of a complex polygon.

DOUBLE TRACE - The process of digitizing polygons separate of each other resulting in a double line for common polygon boundaries.

DOUBLE LINE DIGITIZING - See Double Trace.

E -- ELEMENT - An element of a map corresponds to one grid position within a sector.

EQUIDISTANT - Being the same distance from some given object.

EQUIDISTANT MAP - Generated by mathematical equation displaying areas which are constructed using an imaginary line equidistant from each pair of adjacent points (i.e., topics such as income and crop production).

EXTERNAL DATA FILE - A data file which is not defined in the GRID system.

EXTRACT - To copy from a set of items all those items which meet a specific criterion, (e.g., user creates a new polygon or grid files which are subsets of existing files).

F -- FIDUCIAL POINT - A point used as a basis of reference.

FIDUCIAL COORDINATE - See Fiducial Point.

FILE - A collection of related records treated as a unit.

FLOW CHART - A system analysis tool that provides a graphical presentation of a procedure.

FMPS - Functional Mathematical Programing System. A UNIVAC library used for the processing of mathematical problems.

FREQUENCY POLYGON - A plot or statistical summary showing the frequency of occurrence of each type of element symbol.

FUNCTION - A specific purpose of an entity or its characteristic action.

G -- GEOGRAPHIC - Signifying basic relationship to the earth considered as a globe-shaped body.

GEOGRAPHIC COORDINATE - The position of a point on the surface of the earth expressed in terms of latitude and longitude.

GEOGRAPHIC COORDINATE SYSTEM - A coordinate system that is referenced to points of latitude and longitude.

GEOGRAPHIC POSITION - See Geographic Coordinate.

GEOGRAPHIC WINDOW - An area represented by user selected geographic coordinates.

GRAPHIC DISPLAY - A physical or pictorial representation of data, such as printing, plotting output.

GREY TONE - A method of displaying a map that contains numeric characters. The output will yield a display with the same shape as the numeric values but with symbols whose intensity is proportional to its numeric value.

GREY SCALE - See Grey Tone.

GRID - A pattern of horizontal and vertical lines which form a system of blocks used as a reference system on graphic or photographs. See Grid Cell Method.

GRID CELL METHOD - A pattern of horizontal and vertical lines which forms a system of blocks. The blocks are used to determine area locations and amounts for resource management. See Grid.

GRID CODE - In the GRID system it is a numeric means of separating the various maps, depending on the amount of area covered.

H -- HANDCODE - A manual procedure for recording cell data using a grid overlayed onto a map.

HEADER RECORD - A record which contains information identify types and characteristics about the data in the records that follow.

HIGH SPEED PRINTER - A printer that operates at a speed more compatible with the speed of computation and data processing so that it may operate on line.

I -- IDENTIFIER - A symbol whose purpose is to identify, as to indicate or name a body of data. A key.

INPUT - Information or data transferred or to be transferred from an external storage medium into the internal storage of the computer. Data to be processed.

INTEGER - Any positive or negative counting number or zero.

INTERACTIVE MODE - Reciprocal action between two entities such as terminal and computer. See Demand Process.

INTERSECTION - The procedure of overlaying two or more layers of information in order to satisfy a user inputted request. The intersection of two sets is the set consisting of all elements common to both of the two sets. (e.g., soil type A with timber type M)

INTERFACE - A common boundary (e.g., the boundary between two systems or devices).

K -- KEYPUNCH - A special device to record information on cards by punching holes in the cards to represent letters, digits and special characters.

L -- LABEL - A unique identification of individual ~

LATITUDE - A linear or angular distance from the equator on a sphere or 90 degrees.

- LAYER - A single topic of information. Also a map or overlay that contains information about an area that is distinct from other information. (e.g., tree type, soil type, etc.)
- LEFT JUSTIFIED - Data is left justified when the left hand digit or character occupies the left hand position of the space allotted for that data.
- LEFT ADJUSTED - See Left Justified.
- LINEAR COMBINATION - A compositing method achieved by assigning a weighting coefficient per topic for data manipulation.
- LINE PRINTER - A printer in which an entire line of characters is composed and determined within the device prior to printing.
- LITERAL - A word or number which names or describes itself and remains unaltered during the operation of the program.
- LOCAL COORDINATE SYSTEM - A coordinate system that references itself and is not necessarily geographically oriented (e.g., the X, Y coordinate system of the digitizing table.)
- LONGITUDE - A linear or angular distance measured East or West from a reference meridian (usually Greenwich England) on a sphere or spheroid, and measured through 180 degrees.
- M -- MANIPULATE - The performance of those data processing chores common to most users, such as sorting, input/output operations, and report generation.

MAP DICTIONARY - See Dictionary.

MAP LAYER - See Layer.

MAP SECTOR - See Sector.

MASTER GRID - An original grid normally produced on a stable base medium such as mylar used for preparing duplicate copies for user needs.

MASTER MAP - Are alpha maps which have a dictionary associated with them. Used primarily for the purpose of storing geographic shapes such as county boundary, state boundaries, etc.

MATH MODEL - A mathematical representation of a process, device or concept.

MERGER - An "A" Card transaction used to combine existing dictionaries, maps, or titles from one map file to another.

MINICOMPUTER - A small computer which in its basic configuration has at least 4096 words of memory, employing words between 8 and 16 bits in length.

MODAL - Of or pertaining to a statistical mode; most frequent, common or typical.

MODIFY - An "A" Card transaction used to add new entries to a dictionary or to change current entries in an existing dictionary, map or title on the map file.

MONITOR - To control the operation of several "mono" machine runs so that the computer runs advantageously. In the "A" Card, the map file indicates that the map file is affected, only "monitor

MULTIVARIATE FREQUENCY - See Multivariate Histogram.

MULTIVARIATE HISTOGRAM - Provides cross tabulation of two topics displaying the frequency of occurrence of each symbol.

MULTIPLE LINEAR REGRESSION - Produces a regression analysis of independent maps indicated on "V" Cards explaining the dependent map topic on t "T" Card.

MYLAR - Trademark of Dupont for a stable base polyester film.

MAP JOINING - The process of matching map sheets that have a common edge.

N -- NESTED MEANS - A family of sets where, given any two of its sets, one is contained in the other.

NONCONTIGUOUS - Not adjacent or adjoining, areas that are physically separated.

NUMERIC CHARACTER - Composed of numerals, the value of a number as opposed or contrasted to character representation

NUMERIC OUTPUT - A printer output represented by numeric characters.

O -- OFF-LINE PROGRAM - Operations performed by auxiliary computer equipment independent of the computer mainframe.

OPEN-ENDED - Having the capability of being extended or expanded.

OPERATOR - The what-to-do portion of an operation.

OPTIMIZATION - The maximizing or minimizing of a given function subject to some type of constraint (s).

OVERLAY - A printing or drawing that shows detail not appearing, or requiring special emphasis, on the original map.

OVERLAYING - The process of compositing (superimposing) one layer of information with another to obtain an overlay of common areas.

P -- PARAMETER - A definable characteristic of an item, device, or system.

PASSIVE MODE - See Passive Participation.

PASSIVE PARTICIPATION - Indicates that the map file is not physically affected, only monitored. See Monitor.

POINT MODE - A method of digitizing; the digitizer is set to produce a discrete point after location of the cursor. This method is used to locate discrete points of long, straight line segments.

PLOT - To map or diagram.

POLYGON - A closed plane figure bounded by three or more line segments.

Q -- QUAD - Abbreviated form for quadrangle.

QUADRANGLE - A rectangular, or nearly so, area covered by a map, usually bounded by given meridians of longitude and parallels of latitude, usually 7 1/2 or 15 minutes apart.

QUALIFIER - A name that is associated with another name to give information about the latter and distinguish it from other things that have the same name.

REAL-VALUED MAP - Allows for continuous quantitative information to be stored. Real values must be transformed to either a numeric or alpha map for display purposes.

REGISTRATION POINT - A discrete point where the local coordinates as well as the latitude and longitude are known. It serves as the basis of conversion between coordinate systems.

RELATIONAL OPERATORS - An expression that describes a relationship between two terms; (e.g., A is less than B.).

REMOTE TERMINAL - An input/output unit, or other piece of equipment which is removed from the computer center but connected by a communication line.

REMOVE - An "A" Card transaction used to erase entries on an existing dictionary on the Map File.

RESOURCE DISPLAY - Computer assisted analysis, storage, retrieval, and spatial display of resource information from existing maps, photographs and other sources.

RESOURCE OVERLAY - See Overlay.

RETRIEVE - To find and select specific information.

RIGHT JUSTIFY - Data is right justified when the right hand digit or character occupies the right hand position of the space allocated for that data.

ROUTINE - A sequence of instructions that carry out a well defined function.

RUNSTREAM - A series of requested computer commands used to execute a program.

S -- SCALE - The ratio of a distance on a photograph, map or other graphic to its corresponding distance on the ground, or to another graphic.

SECTOR - A sector is a geographic sized unit within the GRID system represented by 120 rows x 120 columns containing 14400 cells.

SHEET CORNER - The corners that bound the body of a map, usually latitude and longitude.

SOFTWARE - Programming aids that are frequently supplied by manufacturers to facilitate the users efficient operation of the equipment, such as assemblers, computers, subroutine libraries, operating systems, etc.

SOURCE MAP - The map used for the selection of map detail to prepare resource overlays.

SPATIAL - Of or pertaining to space; occupying space.

STATISTICS - A discipline dealing with methods of obtaining data, analyzing and summarizing it, and drawing inferences from data samples by the use of probability theory.

STEPWISE MULTIPLE REGRESSION - Provides a regression of maps indicated on "U" Card as independent topics to the map referenced on this card.

STORE - To retain data in a device from which it can be obtained a later date.

- SUPPRESS - An optional function in either off-line or on-line printing devices that permits them to ignore certain input characters or a group of characters.
- T -- TOLERANCE - A permissible deviation from a specified value, expressed in actual values or more often as a percentage of these nominal values.
- TOPIC - The subject title of a map file.
- TRANSACTION - A general description of updating data relevant any item.
- U -- UNBLOCKING - The process of separating and obtaining one or more records from a block in the memory.
- USER ORIENTED - Increases the accessibility of computers to non-programming problem solvers.
- UTM COORDINATE - Universal Transverse Mercator Coordinates.
- Quantities which designate the location of a point on the UTM Grid.
- UTM GRID - A grid system based on the Universal Transverse Mercator Projection applied to maps of the earth's surface extended to 84° North and 80° South latitude.
- V -- VARIABLE - A data item, or specific area in memory, that can assume any of a set of values.
- W -- WEIGHTING - The process of assigning values to data so that some data is more heavily valued than others.

WINDOW DISPLAY - A display representing a user specified area
one sector.

X -- X-COORDINATE - Defines the location of a point in a horizontal plane
and in an east-west direction from the origin.

X-AXIS - A horizontal axis in a system of rectangular coordinates.

X-DIRECTION - See X-Coordinate.

X-WIDTH - See X-Coordinate.

Y -- Y-COORDINATE - Defines the location of a point in a horizontal plane
and in a north-south direction from the origin.

Y-AXIS - A vertical axis in a system of rectangular coordinates.

Y-DIRECTION - See Y-Coordinate.

Y-WIDTH - See Y-Coordinate.

Z -- Z-COORDINATE - Defines the location of a point perpendicular to the
plane which contains the X and Y Axes. (Commonly
referred to as an elevation.)